

ROAD DAMAGE COST ALLOCATION STUDY




DeWitt County Commissioners Court

Daryl L. Fowler
Curtis G. Afflerbach
James B. Pilchick, Sr.
John C. Oliver
Donald R. Kuecker

County Judge
Precinct 1 Commissioner
Precinct 2 Commissioner
Precinct 3 Commissioner
Precinct 4 Commissioner

June 27, 2012



David M. Underbrink, Sr.

Prepared By



Naismith Engineering, Inc
ARCHITECTURE ■ ENGINEERING ■ ENVIRONMENTAL ■ SURVEYING

ESTABLISHED 1949
OVER 60 YEARS OF ENGINEERING EXCELLENCE

CORPUS CHRISTI
4501 GOLLIHAR ROAD
CORPUS CHRISTI, TEXAS 78411
PHONE: 800-677-2831

AUSTIN
600 WEST 8TH SUITE 300
AUSTIN, TEXAS 78701
PHONE: 512-708-9322

BROWNSVILLE
789 EAST WASHINGTON
BROWNSVILLE, TEXAS 78523
PHONE: 956-541-1155

VICTORIA
405 WEST POWER AVENUE
VICTORIA, TEXAS 77901
PHONE: 800-677-2831

TEXAS BOARD OF PROFESSIONAL ENGINEERS FIRM 355

TABLE OF CONTENTS

EXECUTIVE SUMMARY	3
INTRODUCTION	5
DEWITT COUNTY DATA.....	5
Overview	5
Base Map	5
Typical Existing Pavement	6
Maintenance Expenditures.....	6
OIL AND GAS WELL FIELD CHARACTERISTICS	6
Eagle Ford Shale within County	6
Well Density within County	6
Drilling Rates	6
Well Site Activity	7
Historical Activity.....	8
ANALYSIS	8
Traffic Assignments to a County Road.....	8
Well Information.....	9
Equivalent Single Axle Load (ESAL)	9
Traffic	10
Total EALF's per Well	11
Traffic Assignments.....	11
Pavement Analysis.....	11
Proposed Roads and Estimated Construction Budget.....	12
Proposed Roads and Estimated Construction Budget.....	12
ROAD DAMAGE COST ALLOCATION STUDY SUMMARY	13
REFERENCES	14

EXECUTIVE SUMMARY

DeWitt County contracted with Naismith Engineering, Inc. to evaluate the effect of oil field traffic on the DeWitt County road system and to provide a report of findings from the analysis.

Background Information

The Eagle Ford Shale lies beneath about two-thirds of DeWitt County. The County maintains approximately 342 miles of County Roads within this affected area. These roads, consisting of four to six inches of sand and gravel base courses with asphalt surface treatments, were intended for local, light traffic, with occasional minimal maintenance. As constructed, these roads will support approximately 10,000 ESAL applications during the typical 20-year life of the pavement. The anticipated traffic on this type of road would consist of passenger cars, pickup trucks, and about two 18-wheel tanker trucks (80,000 pounds each) per week.

Oil Field Traffic Characteristics

The existing pavements experience the most distress from vehicles during the rig-up and rig-down stages of well development. Based on data obtained from the Motor Carrier Division, moving the drilling rig in and out applies as many as 25 vehicles weighing up to 6 million pounds with 250 ESAL repetitions in two days. Overall, the Well Development phase produces 7,000 vehicle trips with 1,400 ESAL repetitions to the road system over two months and another 592 vehicles for another 1,030 ESAL for the remainder of the initial year traffic. Thereafter, the Production phase adds another 730 vehicle trips and 1,250 ESAL repetitions per year.

Proposed Pavements and Estimated Construction Costs

In order to provide pavements that will meet the needs of the public, including the oil field industry, recommendations for pavement thicknesses, road widths, and additional right-of-way are based on three levels of improvements:

- a) Road Maintenance. Roads that experience very little oil field traffic and are maintained intermittently. There are approximately 45 miles of these roads within the play.
- b) Basic Reconstruction. Roads that experience up to two well developments per year on average and require a heavier and wider pavement with increased right-of-way and relocated drainage, utilities, and fencing.
- c) Major Reconstruction. Roads that experience more than two well developments per year on average, or geographically provide a collector street function, and require four lanes of pavement, a 100 feet wide right-of-way, and relocated drainage, utilities, and fencing.

Anticipated Oil Field Activity

The Eagle Ford Shale has been called the largest oil and gas find in the last half-century. Because of the widespread characteristic of its geography and historical exploration data, companies are able to drill almost risk-free, making it very attractive for development. Eagle Ford also contains more liquids, compared to Barnett, Marcellus, Haynesville, and other national well fields. When considering expected production periods of twenty years, an ultimate well spacing of 65 acres, and relatively less expensive development costs, this oil and gas play should continue to produce, even after activity in other locations lessen. In addition, there are other productive zones in this area such as the Austin Chalk, Edwards Limestone, Olmos, and

Wilcox formations that may be targeted in the future. Based on 65 acres per well, DeWitt County could see 3,250 wells drilled over the life of the Eagle Ford.

Summary

The anticipated oil field activities traffic demand, including the public usage, will require the construction of heavier roads. Based on 45 miles of anticipated Road Maintenance at \$80,000 per mile per year, 187 miles of anticipated Basic Reconstruction at \$920,000 per mile of road, and 99 miles of anticipated Major Reconstruction at \$1,900,000.00 per mile of road, and with an estimated 3,250 wells that will be accessed by County roads, the cost to provide a County Road system to serve the public, including the oil field industry, is approximately \$432,140,000.00, or almost \$133,000 per well.

INTRODUCTION


Advancements in technology driven by favorable pricing have brought oil and gas exploration to the Eagle Ford Shale. This play has become a major exploration and production area. DeWitt County in South Central Texas sits atop the Edwards Reef Trend within the Eagle Ford Shale Play. For years, natural gas has been the target within the county and now, with the development of Eagle Ford Shale, natural gas and oil is being targeted (Eagle Ford Shale, 2012). Within DeWitt County, oil can be found along the northwestern portion of the County, wet gas along the central portion of the County, and dry gas along the southeastern portion of the County (U.S. Energy Information Administration, 2010). The availability of the most desirable products, condensate and wet gas, have caused an explosion in oilfield activity in DeWitt County. The County is being reported as being located within the most prolific area of the Eagle Ford Shale, where the wells are producing greater amounts of condensate and wet gas (Eagle Ford Shale, 2012). With oil, wet gas, and dry gas being available in the County, DeWitt will likely see activity continue for many years.

The local economy thrives on this increased activity, with more jobs, increased sales and sales tax revenues, and increasing property values and property tax revenues. The corresponding challenge for local public officials is the increased demands on the local infrastructure, with the County being responsible for the County road system and other county maintained infrastructure.

DEWITT COUNTY DATA

Overview

The county is 908.98 square miles (United States Census Bureau, 2012) in size or approximately 581,747 acres with approximately 685 miles of County maintained roads. These roads are fairly narrow, between ten-feet (10') and fourteen-feet (14') in width, and the rights-of-way are also narrow, leaving little room for drainage features such as roadside ditches and culvert pipes. The roads follow common property lines, and were given to the public by easements as a part of the original survey plats recorded with DeWitt County. The roads generally follow the straight property lines and can sometimes contain sharp turns at intersecting property lines. The intended traffic for these low volume roads would primarily be passenger vehicles with a larger truck about twice a week.



Base Map

A base map of the DeWitt County road system was developed to show the location of the County maintained roads, as well as the State maintained roads, the location of Cities and Townships, and the location of creeks and rivers within the County. The information for the base map was obtained from the Texas Natural Resources Information Systems (TNRIS)

website by obtaining the Texas Department of Transportation (TxDOT) Urban File 2003 – DWG (Texas Natural Resources Information System, 2012). This information was then verified and modifications were made to reflect the information that the DeWitt County Commissioners provided for the locations, names, and surface types of County maintained roads.

Typical Existing Pavement

The County road system consists of pavements that usually contain four inches (4”) to six inches (6”) of base material over soils with fair strength, surfaced with an asphalt seal coat. This pavement produces a design structural number for the pavement of less than one (1). These roads were intended to carry local, light traffic. With regular maintenance, this type of a pavement section provides about 10,000 18-kip Equivalent Single Axle Load repetitions over the 20-year life of the pavement. During this study this type of County road will be referred to as “CR-A”.

Maintenance Expenditures

Annual maintenance of the County road system is the responsibility of the County. In 2011 the county spent \$3.7 million on transportation and the 2012 budget allocates approximately \$4.0 million (County of DeWitt Texas, 2011).

OIL AND GAS WELL FIELD CHARACTERISTICS

The Railroad Commission of Texas regulates the oil industry in the State of Texas. The Oil and Gas Division regulates the exploration, production, and transportation of oil and natural gas in Texas (The Railroad Commission of Texas, 2007).

Eagle Ford Shale within County

The Eagle Ford Shale lies beneath the northwestern half of DeWitt County. The play is active from the Karnes County and Gonzales County lines to the approximate location of State Highway 72 and US Highway 77 through Nordheim, Yorktown, Cuero and Yoakum. This area encompasses approximately 270,000 acres, with approximately 211,400 acres that are accessed by 342 miles of County roads.

Well Density within County

The initially anticipated well density within the Eagle Ford Shale was predicted to be at 130 acres, however oil companies have found favorable production rates with well spacing at 65 to 90 acres (EOG Resources, 2012) (2012 Drilling Info Inc., 2012). Since well density is trending toward a decreased well spacing, 65 acres per well will be used for this study. Based on this spacing, the Eagle Ford Shale area can support approximately 4,149 wells in the County.

Drilling Rates


As of June 2012, there were approximately twenty (20) active drilling rigs within the County, and about 280 rigs throughout the Eagle Ford Shale play (Shale, 2012). Assuming slight growth in drilling capacity and favorable markets, the anticipated well spacing of 65 acres could be realized in approximately 15 years. In the meanwhile, other factors such as technological

advancements likely could allow for more efficient product extraction and extend this time period.

Well Site Activity

A typical well exhibits four (4) phases of activity through its life as outlined below:

- **Development Phase.** For this study, the well development phase will include traffic associated with activities in the first year of the well start up. This phase consists of the following stages:
 - **Site Preparation Stage:** During this stage materials are transported to the site and placed to form the pad site, access way, and any berms to hold fluids or contain tanks. The equipment consists of loaders, haulers, dumps, and similar equipment for building a road. The process usually requires 2 to 4 days to complete, and could extend longer, depending on actual site requirements.
 - **Rig-Up Stage:** During this stage the drilling rig and support facilities are moved onto the site and assembled. This process involves multiple large, heavy loads and can include large cranes that lift the components into place.
 - **Drilling Stage:** During this stage drilling components such as pipe and drilling fluids are delivered to the site, maintenance vehicles and passenger vehicles will visit the site on a regular basis.
 - **Rig-Down Stage:** During this stage the drilling rig and support facilities are disassembled and moved off the site in the same manner as the parts were brought in.
 - **Completion Stage:** During this stage coiled tubing is delivered, hydraulic fracturing is performed, and the well is completed so that production can commence.
 - **Production Stage:** For the remainder of the first year, product is removed from the site by tanker trucks, based on the well's productivity, or by pipeline if available. The generated traffic is dependent upon the actual well production. For this study it will be assumed that product will be removed by tankers.
- **Annual Production Phase.** The well annual production phase includes traffic associated with the years subsequent to the Well Development Phase. The product continues to be removed from the site by tanker trucks, based on the well's productivity.
- **Work Over Phase.** Historically, well production may decrease over time and will need to be reworked to increase production to initial amounts. During this phase the well is reworked and/or re-fractured to release flows of additional product. Initial findings within the Eagle Ford Shale show that re-fracturing may not be required during the life of the well (Chesapeake Energy Corporation, 2012). Therefore, for the purposes of this study, there will be no consideration for activities associated with re-working the well.



- **Plugging Phase.** Once a well becomes feasibly unproductive the well must be plugged in accordance with the current regulations. For the purposes of this study, there will be no consideration for activities associated with plugging the well.

Traffic Variances in Wells. Many factors influence the amount and characteristics of the traffic associated with a well development, such as drilling depth, horizontal drilling length, formation characteristics, decline in monthly production, and availability of water. The usual traffic associated with typical well drilling activities has been used to predict total traffic volumes, vehicle types, and wheel loadings. As these factors change with different geographical locations, the traffic would change as well. Other counties may experience slight differences in traffic demand.

Historical Activity


Although there are more wells producing gas than those producing oil, the current favorable oil markets encourages oilfield companies to seek oil. Drilling activity has seen a steady increase since 2005 in DeWitt County, with about 10% per year growth. The limit on this growth appears to be the result of a lack of oil producing acreage, and the most recent 6-months has shown a steady count of drill rigs for the entire Eagle Ford Shale play.

ANALYSIS

This study involved evaluating the effects of the traffic generated by the oil field on the DeWitt County road system. To be able to perform the evaluation an analysis of several features of the oil field had to be considered.

Traffic Assignments to a County Road

The base map for the County was utilized for determining the probable road that would be accessed by any one well development. The area between any two roads was subdivided based on equal distances. Property ownership lines, minor waterways, and other land features that might be barriers to traffic routing were disregarded in determining the contributing areas. The base map with contributing areas can be seen in **Appendix A – DeWitt County Road Location and Contribution Area**. The characteristics of each County Road, such as length and surfacing, and the contributing area that could be developed by the oilfield industry are shown in **Appendix B – DeWitt County Road Information**. The same information contained in Appendix B is narrowed to only those roads within the Eagle Ford Shale play and shown in **Appendix C – Western DeWitt County Road Information for the Eagle Ford Shale Play**. Well density was used to determine traffic volumes based on contributing areas, and traffic assignments were based on traffic volumes and accumulated traffic from adjacent roads.




Well Information

Well Quantity Within County. Evidence supporting a well spacing of 65 acres was utilized to calculate the total number of wells at full development. Referencing the base map, within the Eagle Ford Shale area of the County, it was determined that County roads will serve an anticipated 3,250 wells. The well quantities distributed to each County road, based on contributing areas, is shown by **Appendix D – Well Development Assignment by Roadway for the Eagle Ford Shale Play**. The roads are sorted based on highest well quantity.

Equivalent Single Axle Load (ESAL)

Engineering practice for flexible pavement design relates the relative impact of vehicles on the roadway by converting each axle load repetition to a standard axle load. Factors equating any axle load repetition as a ratio to a standard 18-kip Equivalent Single Axle Load (ESAL) was developed through road testing completed in the 1950's and 1960's by AASHO, and contained in the most recent publication shown by Appendix D of the AASHTO Guide for Design of Pavement Structure (American Association of State Highway and Transportation Officials, 1993).



Determination of Load Factors. Subsequent to AASHTO's work, further research (Drakos, 2005) found that heavier, multi-axles vehicles were better quantified using the Equivalent Axle Load Factor (EALF) equation for tri-axle, quad-axle, and quint-axle combinations. In addition, this equation gave results for single and tandem axle loads that were similar to the AASHTO equation.

$$EALF = \left[\left(\frac{L_{18} + L_{A18}}{L_X + L_{AX}} \right)^{4.79} \left(\frac{10^{\frac{G}{B_X}}}{10^{\frac{G}{B_{18}}}} \right) (L_{AX})^{4.33} \right]^{-1}$$

L_{18} = Standard axle load (18 kips)

L_{A18} = Standard axle quantity (1)

L_X = Total axle load

L_{AX} = Quantity of axles for load

p_t = Terminal serviceability (2)


SN = Structural Number (1)

$$B_{18} = .4 + \left[\frac{0.081(L_{18} + L_{A18})^{3.23}}{((SN+1)^{5.19})(L_{A18})^{3.23}} \right]$$

$$B_X = .4 + \left[\frac{0.081(L_X + L_{AX})^{3.23}}{((SN+1)^{5.19})(L_{AX})^{3.23}} \right]$$

$$G = \log \left[\frac{(4.2 - p_t)}{(4.2 - 1.5)} \right]$$

For the purpose of estimating the distress on County road pavements, the values in the equation for Structural Number ($SN=1$) and the Terminal Serviceability Index ($p_t=2.0$) will be used for each County road. Both of these numbers are likely conservative, considering varying construction materials quality, construction practices, and maintenance practices. The tabulated results of various



combinations of axles and axle loads are shown in **Appendix E – Equivalent Axle Load Factors (EALF) for Flexible Pavement** gives tabulated EALF values for the different axle combinations and weights.

Traffic

Intended Traffic. Current County roads are designed for a relatively low volume, light weight vehicles that consist of mainly passenger vehicles. Over the life of a typical county road one can consider about 500 EALF's per year for a total of 10,000 EALF's at which point the road will require rebuilding.

Well Traffic. Information regarding the traffic was compiled from research projects performed by the Texas Transportation Institute (TTI) (Mason, et al., 1982) and permit data from the Texas Department of Motor Vehicles (TxDMV) (see **Supplemental Appendix 3**). Documentation of the direct measurement of vehicular tire loads and axle weights was not found. Available oil field traffic counts assume axle weights within legal limits, and do not address the effects of triple-axle, quadruple-axle, quintuple-axle, or more, loading combinations found in very heavy vehicles used to develop oil wells. The information from the TxDMV showed that during the rig-up phase and rig-down phase, multiple vehicles carrying a total weight of up to 6 million pounds produced 250 EALF's in two days. Also, coiled-tubing trucks used for hydraulic fracturing exhibited similar weights, but utilized permits that did not capture specific location data.

Vehicle Classification. The vehicles within this study are classified according to axle combinations. This study found that passenger vehicles contribute insignificantly to the EALF totals, and were not considered. **Table 1 – Vehicle Classification** indicates the vehicle code that will be used:

Table 1 Vehicle Classification			
Code	Vehicle Type	Code	Vehicle Type
SU-1	2 Axle	3-3	3 Axle Tractor, 3 Axle trailer
SU-2	3 Axle	3-4	3 Axle Tractor, 4 Axle trailer
2-S1	2 Axle Tractor, 1 Axle	3-5	3 Axle Tractor, 5 Axle trailer
3-S2	2 Axle Tractor, 2 Axle	4-3	4 Axle Tractor, 3 Axle trailer
2-1	2 Axle Tractor, 1 Axle trailer	4-4	4 Axle Tractor, 4 Axle trailer
2-2	2 Axle Tractor, 2 Axle trailer	4-5	4 Axle Tractor, 5 Axle trailer
3-2	3 Axle Tractor, 2 Axle trailer	3-2-5	3 Axle Tractor, 2 Axle, 5 Axle trailer

Well Traffic by Phase. Traffic for a well was segregated into the different phases of a well, with **Table 2 – Traffic Demand** listing a general accounting of the total traffic per well phase and the corresponding total EALF's for that phase. A detailed list is tabulated in **Appendix F – Equivalent Single Axle Loads per Well Phase**. It can be seen that this information includes estimates for overweight vehicles common to the rig-up, rig-down, and completion stages of the Well Development Phase (see **Supplemental Appendix 1 – Rig-Up and Rig-Down Information from the Texas Department of Motor Vehicles Data**). For tabulating the contribution of these overweight vehicles, the TxDMV data was averaged to yield a typical count for a well (see

Supplemental Appendix 2 – Typical Rig Vehicle Combination). Previous research (Mason, et al., 1982) for a similar geographic area shows that approximately 2,968 vehicles during Well Development about 2 vehicles per day for the period thereafter.

Total EALF's per Well

Single Well. The total EALF's associated with one well for the first year is estimated at 2,430, with an annual EALF of 1,250. Considering a study period of 20-years, the total EALF that a well produces is 26,680. Comparatively, one well can produce three times the traffic loading that a typical County Road is expected to provide over a twenty year period. However, the sheer weight of some of the legally permitted steering axle wheel loads would break down the County road pavements, including base and subgrade on the first pass.

Traffic Projection. The accumulated traffic assigned to a typical County road was based on the intended traffic plus one well development per year over a twenty-year period. The resulting tabulation is shown in **Appendix G – 20-Year Projection of EALF Demand.**

Table 2 Traffic Demand		
Phase	Total Vehicles	Total EALF
Development	10,464	2,430
Annual Production	730	1,250
20-Year Total	24,334	26,680

Traffic Assignments

Traffic assignments made to a road were based on an even distribution in each direction along the roadway. Once well traffic encountered an adjacent roadway, that traffic is considered to be commuter traffic on the adjacent road. The adjacent roadway traffic would then include the commuter traffic and its own well traffic. This process was used (1) to accumulate all well traffic and all commuter traffic for all roads in the study area, and (2) so that collector thoroughfares could be identified. In instances where traffic could most directly reach a highway, preference was given to traffic assignments that would optimize travel by highway.

Pavement Analysis

The total distress induced by traffic assigned to any one roadway is derived from accumulating the traffic associated with the number of projected wells during the study period based on contributing area and well spacing and from distributing the well traffic on to adjacent roads based on optimizing highway travel. The total number of 18k-EALF repetitions found for each road is used to classify the roadway pavement section for estimating construction costs.

The soil types in DeWitt County can be found using the Soil Conservation Service soil maps. The Soil Support value can be found using the TxDOT Tri-axial Classification of Surface Soils 1973 report to obtain the soil classification for the soil from the SCS soil maps, then converting the soil classification into a Soil Support value using NCHRP 128. The Structural Number required for the proposed pavement can be found by using the Soil Support value, the anticipated number of 18k-EALF repetitions, and adjusting for a regional factor. The determined Structural Number is used to design the flexible pavement layers, usually consisting of a hot-mix asphaltic concrete surface and a limestone base over natural soils.

Proposed Roads and Estimated Construction Budget

Each County road can be grouped into one of three recommended classifications based on anticipated traffic. Each of these classifications provides varying levels of infrastructure to match anticipated demand. The characteristics considered are Right-of-way width, total number of Driving Lanes, total Pavement Width, and pavement Surface Type. The comparative list of the roadway characteristics for each of these classifications are listed in Table 3 –

Table 3 Proposed County Road Classification and Features				
<i>Road Classification</i>	<i>ROW</i>	<i>Drive Lanes</i>	<i>Pavement Width</i>	<i>Surface Type</i>
<i>CR-A</i>	<i>40'</i>	<i>1</i>	<i>14'</i>	<i>Seal Coat</i>
<i>CR-B</i>	<i>60'</i>	<i>2</i>	<i>30'</i>	<i>HMAC</i>
<i>CR-C</i>	<i>100'</i>	<i>4</i>	<i>56'</i>	<i>HMAC</i>

HMAC – Hot mixed asphaltic concrete

Proposed County Road Classification and Features. The recommended roadway classification for every County road in the Eagle Ford Shale area of DeWitt County is shown in Appendix H – Proposed Road Classification for the Eagle Ford Shale Play. Actual roadway design will depend on the circumstances in each specific road area.

Proposed Roads and Estimated Construction Budget

In order to provide pavements that will meet the needs of the public, including the oil field industry, recommendations for pavement thicknesses, road widths, and additional right-of-way are based on three levels of improvements and an estimated approach and budget for maintaining that pavement. The resulting pavement designs, along with road width, right-of-way acquisition, utility and drainage relocation, engineering and financing costs, and other project costs, are incorporated into total project costs for each type of roadway project.

- Road Maintenance.** Roads (CR-A) that experience very little public and oil field traffic and are maintained intermittently, with an anticipated budget at \$80,000 per mile. There are approximately 45 miles of these roads within the play.
- Basic Reconstruction.** Roads (CR-B) that experience up to two well developments per year on average, and will require a 16½" thick pavement section that is 30-feet wide, accommodating two lanes of traffic, a 60-foot wide right-of-way, and relocation of drainage, utilities, and fencing; with an anticipated budget at \$920,000 per mile. There are approximately 187 miles of the roads within the play.
- Major Reconstruction.** Roads (CR-C) that experience more than two well developments per year on average, or geographically provide a collector street function, and require a 20½" thick pavement section that is 56-feet wide to accommodate four lanes of traffic, a 100-foot wide right-of-way, and relocation of drainage, utilities, and fencing; with an anticipated budget at \$1,900,000 per mile. There are approximately 99 miles of the roads within the play.

Table 4 Budget Estimate Per Proposed Road Type		
Road Type	Description	Total Budget
CR-A	Maintenance	\$72,000,000.00
CR-B	Basic Reconstruction	\$172,040,000.00
CR-C	Major Reconstruction	\$188,100,000.00
	<i>Total Budget</i>	<i>\$432,140,000.00</i>

ROAD DAMAGE COST ALLOCATION STUDY SUMMARY

To meet the needs of the public, including the oil field industry, DeWitt County will be required to maintain and reconstruct County roads. Based on 45 miles of anticipated Road Maintenance at \$80,000 per mile per year, 187 miles of anticipated Basic Reconstruction at \$920,000 per mile of road, and 99 miles of anticipated Major Reconstruction at \$1,900,000.00 per mile of road, and with an estimated 3,250 wells that will be accessed by County roads, the cost to provide a County Road system to serve the public, including the oil field industry, is approximately \$432,140,000.00, or almost \$133,000 per well.


REFERENCES

1. **2012 Drilling Info Inc. 2012.** Eagle Ford News & Analysis from DI Energy Strategy Partners. *Drilling Info*. [Online] 2012 Drilling Info Inc., 2012. [Cited: June 5, 2012.] <http://info.drillinginfo.com/urb/eagleford/>.
2. **American Association of State Highway and Transportation Officials. 1993.** *AASHTO Guide for Design of Pavement Structures, 1993*. Washington, D.C. : American Association of State Highway and Transportation Officials, 1993. 1-56051-055-2.
3. **Chesapeake Energy Corporation. 2012.** chk.com. *Hydraulic Fracturing Facts*. [Online] 05 14, 2012. [Cited: 06 11, 2012.] http://www.chk.com/Media/Educational-Library/Fact-Sheets/EagleFord/EagleFord_Hydraulic_Fracturing_Fact_Sheet.pdf.
4. **County of DeWitt Texas. 2011.** Financial. *Welcome to DeWitt County, Texas*. [Online] September 19, 2011. [Cited: May 07, 2012.] http://www.co.dewitt.tx.us/ips/export/sites/dewitt/downloads/2011_budget.pdf.
5. **Drakos, Dr. Christos. 2005.** ufl.edu. *University of Florida*. [Online] 9 23, 2005. [Cited: 05 25, 2012.] <http://www.ce.ufl.edu/~rroqu/Class%20Notes%20TTE4811/Topic%204%20-%20Traffic%20Characterization.pdf>.
6. **Eagle Ford Shale. 2012.** DeWitt County, Tx and the Eagle Ford Shale Play. *Eagle Ford Shale.com*. [Online] May 3, 2012. <http://www.eaglefordshale.com/counties/dewitt-county-tx/>.
7. **EOG Resources. 2012.** Eagle Ford Shale. [Online] May 4, 2012. <http://www.eaglefordshale.com/companies/eog-resources/>.
8. **Mason, J.M. and Stampely, B. E. 1984.** *Statewide Variability of Oil and Gas Drilling and Production Activity - Research Report 299-4*. College Station, Texas : Texas Transportation Institute, The Texas A&M University System, 1984. Research Report.
9. **Mason, John M., Metyko, Mark J. and Rowan, N. J. 1982.** *The Effects of Oil Field Development on Rural Highways - Research Report 299-1*. College Station, Texas : Texas Transportation Institute, The Texas A&M University System, 1982.
10. **Railroad Commission of Texas. 2012.** Well Distribution by County - Well Counts. *Railroad Commission of Texas*. [Online] 04 27, 2012. [Cited: 05 16, 2012.] <http://www.rrc.state.tx.us/data/wells/wellcount/index.php>.
11. **Shale, Eagle Ford. 2012.** Eagle Ford Shale. *Eagle Ford Shale Drilling and Rig Count*. [Online] 06 08, 2012. [Cited: 6 11, 2012.] <http://www.eaglefordshale.com/drilling-rig-count/>.
12. **Texas Natural Resources Information System. 2012.** Maps & Data. *Texas Natural Resources Information System*. [Online] 2012. [Cited: 03 19 & 28, 2012.] <http://www.tnris.org/get-data>.

13. **The Energy Institute. 2012.** *Fact-Based Regulation for Environmental Protection in Shale Gas Development*. The University of Texas at Austin. Austin, Texas : The University of Texas at Austin, 2012.
14. **The Railroad Commission of Texas. 2007.** About the Oil and Gas Division. *The Railroad Commission of Texas*. [Online] August 02, 2007. [Cited: May 07, 2012.]
<http://www.rrc.state.tx.us/about/divisions/aboutog.php>.
15. **U.S. Energy Information Administration. 2010.** Eagle Ford Shale Play, Western Gulf Basin, South Texas. *U.S. Energy Information Administration*. [Online] May 29, 2010. [Cited: May 03, 2012.]
http://www.eia.gov/oil_gas/rpd/shaleusa9.pdf.
16. **United States Census Bureau. 2012.** DeWitt County QuickFacts. *United States Census Bureau*. [Online] United States Census Bureau, January 31, 2012. [Cited: May 07, 2012.]
<http://quickfacts.census.gov/qfd/states/48/48123.html>.

APPENDIX A





NEI NaismithEngineering, Inc
 ARCHITECTURE ■ ENGINEERING ■ ENVIRONMENTAL ■ SURVEYING
 TBAE F-13553 ■ TBPE F-355 ■ TBPG F-50017 ■ TBPLS F-100395-00
 4501 GOLLIHAR ROAD, CORPUS CHRISTI, TX 78411
 PH: 800-677-2831 ■ PH: 361-814-9900 ■ FX: 361-814-4401 ■ NAISMITH-ENGINEERING.COM

DRAWN BY: TBT	CHECKED BY: TBT	APPROVED BY: DMU	SCALE: 1"=13,500'	DATE: 6/2012	PROJECT NUMBER: 8783	REVISION: -
------------------	--------------------	---------------------	----------------------	-----------------	-------------------------	----------------


FOR ILLUSTRATIVE PURPOSES ONLY

APPENDIX A-1
DEWITT COUNTY ROAD LOCATION AND CONTRIBUTION AREA
NORTHWEST DEWITT COUNTY

DEWITT COUNTY, TEXAS

FIGURE
A-1
 SHEET
 1 OF 4

Z:\9783 - DEWITT ROAD DAMAGE STUDY\REPORTS\CONTRIBUTION AREA\CONTRIBUTION AREAS\20120627.DWG



NORTHWEST DEWITT

SOUTHEAST DEWITT

NaismithEngineering, Inc

ARCHITECTURE ■ ENGINEERING ■ ENVIRONMENTAL ■ SURVEYING

TBAE F-13553 ■ TBPE F-355 ■ TBPG F-50017 ■ TBPLS F-100395-00

4501 GOLLIHAR ROAD, CORPUS CHRISTI, TX 78411

PH: 800-677-2831 ■ PH: 361-814-9900 ■ FX: 361-814-4401 ■ NAISMITH-ENGINEERING.COM

DRAWN BY: TBT	CHECKED BY: TBT	APPROVED BY: DMU	SCALE: 1"=13,500'	DATE: 6/2012	PROJECT NUMBER: 8783	REVISION: -
------------------	--------------------	---------------------	----------------------	-----------------	-------------------------	----------------

FOR ILLUSTRATIVE PURPOSES ONLY

APPENDIX A-2

DEWITT COUNTY ROAD LOCATION AND CONTRIBUTION AREA

NORTHEAST DEWITT COUNTY

DEWITT COUNTY, TEXAS

Z:\8783 - DEWITT ROAD DAMAGE STUDY\REPORT\CONTRIBUTION AREA\CONTRIBUTION AREA A-2.DWG

NORTHWEST DEWITT

SOUTHEAST DEWITT



GONZALES COUNTY

KARNES COUNTY

KARNES COUNTY

YORKTOWN

LEGEND

- COUNTY ROAD CONTRIBUTION AREA
- PAVED DEWITT COUNTY ROAD
- AGGREGATE DEWITT COUNTY ROAD
- NON-COUNTY ROAD



NaismithEngineering, Inc
ARCHITECTURE ■ ENGINEERING ■ ENVIRONMENTAL ■ SURVEYING

TBAE F-13553 ■ TBPE F-355 ■ TBPG F-50017 ■ TBPLS F-100395-00
4501 GOLLIHAR ROAD, CORPUS CHRISTI, TX 78411

PH: 800-677-2831 ■ PH: 361-814-9900 ■ FX: 361-814-4401 ■ NAISMITH-ENGINEERING.COM

DRAWN BY: TBT	CHECKED BY: TBT	APPROVED BY: DMU	SCALE: 1"=13,500'	DATE: 6/2012	PROJECT NUMBER: 8783	REVISION: -
------------------	--------------------	---------------------	----------------------	-----------------	-------------------------	----------------

FOR ILLUSTRATIVE PURPOSES ONLY


APPENDIX A-3

DEWITT COUNTY ROAD LOCATION AND CONTRIBUTION AREA

SOUTHWEST DEWITT COUNTY

DEWITT COUNTY, TEXAS

FIGURE
A-3
SHEET
3 OF 4



NEI NaismithEngineering, Inc
 ARCHITECTURE ■ ENGINEERING ■ ENVIRONMENTAL ■ SURVEYING
 TBAE F-13553 ■ TBPE F-355 ■ TBPG F-50017 ■ TBPLS F-100395-00
 4501 GOLLIHAR ROAD, CORPUS CHRISTI, TX 78411
 PH: 800-677-2831 ■ PH: 361-814-9900 ■ FX: 361-814-4401 ■ NAISMITH-ENGINEERING.COM

APPENDIX A-4
DEWITT COUNTY ROAD LOCATION AND
CONTRIBUTION AREA
SOUTHEAST DEWITT COUNTY

DRAWN BY: TBT	CHECKED BY: TBT	APPROVED BY: DMU	SCALE: 1"=13,500'	DATE: 6/2012	PROJECT NUMBER: 8783	REVISION: -
FOR ILLUSTRATIVE PURPOSES ONLY						

DEWITT COUNTY, TEXAS

FIGURE
A-4
 SHEET
 4 OF 4

Z:\9783 - DEWITT ROAD DAMAGE STUDY\REPORTING\CONTRIBUTION AREA\CONTRIBUTION AREA\A-4-20120627.DWG

APPENDIX B



APPENDIX B

DeWitt County Road Information

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
6th Street	314	0.674		2	X			
7th Street	-	0.130		2	X			
8th Street	315	0.681		2	X			
8th Street	3462	0.248		2	X			
A A Hahn Road	263		0.577	2		X	24,155,121	554.53
A Metting Road	3006		2.073	2		X	26,143,190	600.17
Adams Leesville Road	275	2.433		2		X	81,452,317	1,869.89
Alfred Blaschke Road	374		4.935	2		X	89,223,238	2,048.28
Allen Lane	204		0.450	2		X	15,956,537	366.31
Anderson Avenue	-	0.338		2		X	3,169,425	72.76
Anderson Road	169	0.506		2		X	3,169,425	72.76
Arndt Bypass Road	-		0.236	2		X	1,185,754	27.22
Arndt Road	139		1.244	2		X	72,926,455	1,674.16
Arneckeville Center Road	413	0.303		2		X	1,458,664	33.49
Arneckeville Road	412	2.646		2		X	30,107,062	691.16
Atzenhoffer Road	428		2.887	2		X	58,121,205	1,334.28
Auction Ring Road	171	0.037	0.113	2		X	256,223	5.88
Avenue B	-		0.069	2	X			
Baker Road	3001		0.576	2		X	34,663,348	795.76
Barnhart Ranch Road	165	0.935	0.027	2		X	107,517,118	2,468.25
Bell Road	468	1.210		2		X	20,452,735	469.53
Bellevue Cemetery Road	147	6.702		2		X	329,238,785	7,558.28
Ben Meischen Road	338		0.747	2		X	14,790,457	339.54
Benbow Road	277	0.806		2		X	9,086,278	208.59
Berkenhoff Road	340		0.780	2		X	30,704,793	704.89
Bernhart Weise Road	384		1.243	2		X	23,376,763	536.66
Bialek Road	114		3.077	2		X	131,541,519	3,019.78
Biemer Road	463		3.141	2		X	110,643,411	2,540.02
Bill Lemke Road	334		1.180	2		X	38,022,719	872.88
Blackwell Lane	121	1.223		2		X	10,578,727	242.85
Blake Road	307		0.380	2		X	6,421,937	147.43
Bluebonnet Lane	217	1.101		2		X	2,581,249	59.26
Boehm Road	156	1.143		2		X	13,932,316	319.84
Boldt Road	129	5.341		2		X	143,926,890	3,304.11
Bootlegger Road	202	2.641		2		X	50,672,667	1,163.28
Boysen Road	253	0.450		2		X	2,752,836	63.20
Braden Road	168		0.563	2		X	112,471,999	2,582.00
Bramlette Road	244	1.614		2		X	34,115,277	783.18
Brandt Road	448		0.746	2		X	39,385,301	904.16
Brown Road	245		3.060	2		X	73,057,948	1,677.18
Bubba Palmer Road	438	0.617		2		X	6,539,986	150.14
Buckhorn Road	371		0.146	2		X	3,606,450	82.79
Bud Haun Road	404	0.134	1.166	2		X	61,137,486	1,403.52
Buenger Road	441	2.109		2		X	33,027,621	758.21

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Bunjus Road	-	0.413		2	X			
Burger Addition Road	-	0.103		2	X			
Burns Road	254	0.164		2		X	691,383	15.87
Bursh Road	3453		1.177	2		X	19,710,596	452.49
C W Gabler Road	345		0.611	2		X	159,703,853	3,666.30
Cabeza Highway	324	8.583	1.280	2		X	165,679,026	3,803.47
Callahan Road	3472	5.408		2		X	119,293,166	2,738.59
Carter Road	-	0.126		2	X			
Catholic Church Lane	138		2.476	2		X	177,646,668	4,078.21
Cattle Guard Road	268	6.449		2		X	299,518,194	6,875.99
Cemetery Road	329	3.125		2		X	75,947,356	1,743.51
Center School Road	287		0.276	2		X	11,166,399	256.35
Center Street	-		0.168	2	X			
Chaddock Road	131		0.910	2		X	11,426,560	262.32
Charco Road	3035	1.010	3.449	2		X	227,222,259	5,216.31
Cheapside Road	148	6.090		2		X	295,593,638	6,785.90
Cheatham Road	-	0.326		2		X	1,217,492	27.95
Chilek Road	232	0.646		2		X	4,887,788	112.21
Christian Road	257	0.336		2		X	1,568,597	36.01
City of Hochheim Road	234	0.966		2		X	15,745,115	361.46
City Water Works Road	249	0.277		2		X	1,465,946	33.65
Ckodre Road	352		1.604	2		X	30,203,460	693.38
Clinton Cemetery Road	407	0.550		2		X	2,984,111	68.51
Clinton Road	410	0.561		2		X	2,857,328	65.60
Community Hall Road	3456	0.448	0.708	2		X	9,557,021	219.40
Concrete & Edgar Road	242	5.257		2		X	128,221,991	2,943.57
Cook Road	-	0.318		2	X			
Coskey Ranch Road	377		1.870	2		X	52,552,011	1,206.43
Cottonpatch Road	341	1.588	1.333	2		X	88,620,430	2,034.45
Cottonwood Road	-	0.281		2	X			
Crabtree Road	-		0.780	2		X	20,373,701	467.72
Crain Road	-	0.177	0.159	2	X			
Crestview Drive	-	0.827		2	X			
Crestview Road	301	0.543		2		X	4,545,129	104.34
Cypress Valley Road	123	0.821		2		X	11,962,138	274.61
Czaja Bros Road	3018		2.163	2		X	48,102,363	1,104.28
Dagg Road	219	2.211		2		X	87,568,548	2,010.30
Dahse Road	331	2.406		2		X	42,852,917	983.77
Davy Road	-	2.110		2		X	35,251,454	809.26
Dentler Road	424	1.117	1.704	2		X	192,884,006	4,428.01
Dickenson Road	261	0.632	0.077	2		X	60,118,199	1,380.12
Dieringer Road	290		0.176	2		X	4,432,307	101.75
Dlugosh Boldt	470		3.313	2		X	92,666,213	2,127.32
Dreier Road	423		1.393	2		X	20,549,676	471.76
Dreyer-Turkey Bottom Road	230	2.336		2		X	68,075,813	1,562.81
Dubose Ranch Road	399		6.614	2		X	147,395,138	3,383.73
E. Swartz Road	3457	1.464		2		X	66,826,714	1,534.13

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Earl Williams Road	469		2.494	2		X	48,032,832	1,102.68
Eckhardt Road	3039		4.358	2		X	138,106,084	3,170.48
Ed Blackwell Road	124	1.358		2		X	26,971,589	619.18
Edgar Leesville Road	256	0.780	4.455	2		X	225,006,169	5,165.43
Edmund Mueller Road	359		1.003	2		X	13,565,179	311.41
Edna Hattenbach Road	135		0.500	2		X	13,522,440	310.43
Edwin Schroeder Road	390		0.583	2		X	4,056,291	93.12
Elder Road	116	2.221		2		X	92,585,077	2,125.46
Elizabeth Street	-	0.161	0.099	2	X			
Elroyce Helmers Road	356		1.688	2		X	38,856,832	892.03
Emil Blank Road	205	3.418		2		X	63,243,324	1,451.87
Emil Meyer Road	3020		1.216	2		X	28,793,538	661.01
Emil Zielonka Road	449		2.522	2		X	81,937,816	1,881.03
Ernest Lemke Road	3452	1.244		2		X	19,837,561	455.41
Evans Road	270		0.790	2		X	118,192,841	2,713.33
Fay Avenue	-		0.068	2	X			
Five Mile Road	443	4.270		2		X	83,679,880	1,921.03
Flato Street	-	0.360		2	X			
Fordtran Road	107	0.275	2.147	2		X	504,353,090	11,578.35
Fox Crossing Road	421		1.910	2		X	126,007,662	2,892.74
Frank Hinojosa Road	355		1.563	2		X	24,454,494	561.40
Frank Kozielski Road	318	1.973		2		X	52,176,091	1,197.80
Frels Road	241	0.439		2		X	52,931,460	1,215.14
Friar Cliff Road	-	0.266		2		X	5,877,353	134.93
Friar Road	100	3.309	8.818	2		X	692,679,846	15,901.74
Gaebler Road	-		0.071	2	X			
Garfield Road	317	6.386		2		X	155,625,867	3,572.68
Garrett Road	272	0.538	3.726	2		X	236,619,664	5,432.04
Gentsch Street	-		0.056	2	X			
George Klein Road	344	0.181	2.511	2		X	74,934,955	1,720.27
Gerdes Road	226	1.580		2		X	26,950,752	618.70
Gerhold Road	427		1.399	2		X	25,335,254	581.62
Gerhold Road	289		0.766	2		X	18,039,733	414.14
Gilbert Mueller Road	327	2.561		2		X	68,000,827	1,561.08
Giles Road	211	0.383		2		X	525,814	12.07
Glen Oaks	-	0.619	0.020	2	X			
Goehring Road	3451	1.484		2		X	29,908,965	686.62
Gohlke Road	-	0.054		2	X			
Gohlke School Road	393	2.951		2		X	66,547,966	1,527.73
Gohmert Road	426	1.567		2		X	32,631,390	749.11
Golly Road	419	5.953		2		X	100,612,969	2,309.76
Granger Street	-	0.085	0.033	2	X			
Green Acres Road	3476	0.854		2		X	10,783,974	247.57
Green Cemetery Road	247		0.483	2		X	18,731,709	430.02
Green Dewitt Road	-	3.752		2		X	121,160,492	2,781.46
Gruenau Road	305	3.693		2		X	67,116,872	1,540.79
Guilford School Road	-		0.201	2		X	15,530,230	356.53

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Gus Meyer Road	3012		1.776	2		X	26,871,724	616.89
Gus Mueller Road	385		1.636	2		X	27,451,740	630.21
H Harms Road	378		1.000	2		X	16,139,361	370.51
H Haun Road	404	1.116		2		X	20,027,726	459.77
Haase Brothers Road	394		1.051	2		X	15,860,714	364.11
Hahn Road	262	3.061		2		X	45,367,703	1,041.50
A. Hahn Road	144		2.521	2		X	92,453,204	2,122.43
Hample Road	251	1.237		2		X	20,562,114	472.04
Hannessee	246	3.190		2		X	69,860,882	1,603.79
Hanson Road	3028	0.391	0.376	2		X	24,636,739	565.58
Hartman Road	130		4.417	2		X	157,676,116	3,619.75
Harvest	-		0.218	2		X	6,523,691	149.76
Harvey Hahn Road	3041	0.538	1.639	2		X	35,077,221	805.26
Hattenbach Road	3009		0.364	2		X	66,279,532	1,521.57
Hausman	-		0.607	2		X	31,925,901	732.92
Hebron Church Road	267	1.475	0.158	2		X	82,853,525	1,902.06
Hefner Road	-	0.544		2		X	15,479,349	355.36
Heider Road	-		0.180	2		X	27,586,373	633.30
Heinie Bade Road	444	0.700		2		X	54,685,864	1,255.41
Heinzville Road	3025		0.668	2		X	26,068,957	598.46
Hells Gate Road	167		0.400	2		X	3,881,135	89.10
Henneke Road	414		1.793	2		X	40,114,743	920.91
Hennessey Road	101		0.220	2		X	15,954,577	366.27
Henry Blank Road	231	1.287		2		X	43,020,174	987.61
Herder Road	212	2.140		2		X	44,458,927	1,020.64
Herman Migura Lane	446		1.211	2		X	69,478,850	1,595.01
Herman Road	237		0.637	2		X	70,035,849	1,607.80
Hickey Road	258	2.640		2		X	47,682,000	1,094.63
Hilbrich Bypass Road	-	0.200		2		X	1,676,506	38.49
Hilbrich Road	145	0.986		2		X	99,035,765	2,273.55
Hiller Road	415		0.660	2	X			
Hillside Drive	-		0.083	2		X	7,090,005	162.76
Hix Green Road	3029		2.707	2		X	85,739,316	1,968.30
Hochheim Cemetery Road	-	0.164		2	X			
Hoehne Road	166		1.466	2		X	42,521,537	976.16
Hogan & Mott Road	260		0.853	2		X	33,963,852	779.70
Hohn Road	311 / 3040	3.278		2		X	75,597,620	1,735.48
Hollan Road	269		0.491	2		X	20,924,620	480.36
Hopkinsville Road	429	2.340	2.120	2		X	88,203,272	2,024.87
Horseshoe Road	271	0.696	3.035	2		X	109,700,700	2,518.38
Hotz Road	150	2.211		2		X	44,364,646	1,018.47
Houston Street	-	0.084		2	X			
Howard Road	3474	0.594	2.158	2		X	73,781,234	1,693.78
Howard Weise Road	335		0.310	2		X	9,689,998	222.45
Hrabovsky Road	215	2.773		2		X	67,344,280	1,546.01
Hules Road	208	1.806		2		X	44,813,831	1,028.78
Huth Road	284		0.574	2		X	57,100,129	1,310.84

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Hy Koopmann Road	3019		2.153	2		X	58,610,012	1,345.50
Ideus	-		0.113	2		X	4,386,154	100.69
Immenhauser Road	207	2.213		2		X	60,530,031	1,389.58
Industrial Drive	-		0.294	2		X	1,440,216	33.06
Interstate 13 Road	3013		1.010	2		X	14,154,663	324.95
Isdale Road	216	0.960		2	X			
Jackson Road	395		1.753	2		X	30,906,855	709.52
Jaeger Road	3011		1.640	2		X	127,191,311	2,919.91
Jimmy Hurst Road	3030	0.850		2		X	17,692,971	406.17
Joe Pokluda Road	3033		2.170	2		X	96,758,508	2,221.27
Johnny Pokluda Road	321	0.677		2		X	8,834,088	202.80
Jutz Road	420		0.881	2		X	14,383,771	330.21
K Thiele Road	220	1.003		2		X	13,520,724	310.39
Kaiser & Adams Road	274	3.996		2		X	96,490,759	2,215.12
Kaiser Road	273		4.732	2		X	163,540,872	3,754.38
Kalawik Road	3450	0.299	3.687	2		X	110,274,574	2,531.56
Kenne Road	422		0.480	2		X	14,631,340	335.89
Koenig-McCrabb Road	416	0.120	3.392	2		X	115,008,502	2,640.23
Kolodziejcyk Road	3022		1.318	2		X	49,638,983	1,139.55
Kozelski Road	112		3.243	2		X	93,841,011	2,154.29
Kubala Store Road	397		4.903	2		X	103,454,288	2,374.98
Kvinta Schneider Road	291		0.403	2		X	12,066,884	277.02
Lackey Lane	125		0.984	2		X	84,173,574	1,932.36
Lackey Ranch Road	343		1.163	2		X	16,904,507	388.07
Ladner Road	-		0.423	2		X	33,634,677	772.15
Lakeside	-	0.390		2		X	7,107,184	163.16
Lakeside Road	169	1.364		2		X	56,191,011	1,289.97
Lane Avenue	-	0.805		2	X			
Larry Vasbinder Road	320	0.453	1.565	2			41,178,691	945.33
Lee Alvis Road	3024		1.213	2			84,138,663	1,931.56
Lee Avenue	-	0.207		2	X			
Leo Nelson Road	3017		2.294	2		X	42,290,325	970.85
Lincke Road	396		2.264	2		X	29,310,033	672.87
Lindenau Road	157	2.490		2		X	97,248,301	2,232.51
Little McGehee Road	243		1.903	2		X	43,142,734	990.42
Live Oak Road	-	3.177		2		X	92,540,138	2,124.43
Lockhart Cemetery Road	160	1.935		2		X	22,646,213	519.89
Lone Tree Road	224	3.642		2		X	59,019,366	1,354.90
Luehr Road	-	0.064		2		X	44,301,106	1,017.01
Lutheren Cemetary Rd	3459	0.235		2	X			
Lynch Road	-	0.260		2	X			
Main Street	-		0.138	2	X			
Mann Road	332	0.174		2		X	2,427,264	55.72
Maron Road	361		1.947	2		X	35,467,703	814.23
Martinez Road	227	3.056		2		X	56,540,698	1,298.00
Matejek Road	398		2.030	2		X	47,005,362	1,079.09
Matthew & Adams Road	276	3.150		2		X	63,266,025	1,452.39

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
McCurdy Road	154	3.746		2		X	119,371,579	2,740.39
McElroy Road	239	1.158		2		X	8,860,125	203.40
Mertins Street	-	0.256		2	X			
Mesquite Lane	-	0.243		2	X			
Metting School Road	3464	4.207		2		X	107,617,084	2,470.55
Meyer Road	142	1.419	0.678	2		X	44,316,955	1,017.38
Meyersville Road	405	2.238		2		X	30,080,884	690.56
Mission Valley Road	400	3.535	1.918	2		X	35,793,361	821.70
Mockingbird	-	0.227		2	X			
Morgan Road	-	0.930		2		X	30,878,143	708.86
Morris Community Road	200	4.370		2		X	80,604,941	1,850.43
Morris School Road	201	1.426		2		X	25,198,627	578.48
Mueller Lang Road	445	3.263		2		X	115,459,224	2,650.58
Mueller Road	106	1.680		2		X	30,794,084	706.93
Mulberry Road	-	0.620		2	X			
Muschalek Road	347		0.920	2		X	13,761,265	315.92
Musselman Road	235		0.751	2		X	8,246,294	189.31
Naranjo Road	-		0.245	2	X			
Nathan Mueller Road	337		0.911	2		X	46,250,813	1,061.77
Neal Road	282		0.476	2		X	4,521,181	103.79
Nelson Road	222	0.691		2		X	18,560,536	426.09
Nesloney Road	-		0.210	2	X			
Nessel Road	164	1.096	1.127	2		X	35,681,672	819.14
Nobhill Road	2026		0.118	2		X	4,854,880	111.45
Noe Hinojosa Road	351		2.071	2		X	55,719,638	1,279.15
Nolte-Boehl Road	132	0.319	1.660	2		X	45,022,464	1,033.57
Nordheim Cemetery Road	328	0.326		2		X	1,164,396	26.73
Nordheim Slickfield Road	309	5.242		2		X	206,836,912	4,748.32
North Street	-		0.127	2		X	3,798,158	87.19
Old 237 Road	3455	2.864		2		X	8,097,224	185.89
Old Charco Road	312	0.760		2		X	7,192,842	165.12
Old Cheapside Road	163	0.764		2		X	35,068,545	805.06
Old Clinton Road	439	1.377		2		X	13,004,376	298.54
Old Cuero Road	248	3.252	3.865	2		X	146,369,672	3,360.19
Old Davy Road	3015		1.157	2		X	62,256,202	1,429.21
Old Fechner Road	3021	0.391		2		X	8,361,157	191.95
Old Goliad Road	411	2.090	0.200	2		X	45,028,797	1,033.72
Old Gonzales Road	108	3.480		2		X	73,607,323	1,689.79
Old Nordheim Road	3038		1.570	2		X	33,393,235	766.60
Old San Antonio Road	-	0.980		2		X	9,995,596	229.47
Old Victoria Road	102	0.154		2		X	406,368	9.33
Old Weesatch Road	3463	0.165	0.138	2		X	1,209,484	27.77
Old Yoakum Road	113	6.720		2		X	165,362,608	3,796.20
Old Yorktown Road	467	2.823	2.638	2		X	148,107,454	3,400.08
Old Yorktown Road	302	0.956		2		X	9,854,815	226.24
Oliver Road	-	0.363		2	X			
Oliver Road	-		2.261	2	X			

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Onken Road	375		0.574	2		X	4,834,475	110.98
Otto Bolting Road	383		1.063	2		X	14,454,923	331.84
Otto Fuhrken Road	3034	3.040	0.895	2		X	75,624,460	1,736.10
Pargmann Road	203	3.018		2		X	74,808,972	1,717.38
Pete Jablonski Road	3465	0.926		2		X	11,834,490	271.68
Petru Road	218	0.130		2	X			
Plasczyk Road	3016		1.276	2		X	15,625,604	358.71
Post Oak Way	-	0.273		2	X			
Pridgen Road	-		0.569	2		X	832,453	19.11
Primitive Baptist Church Road	278	0.644		2		X	5,656,271	129.85
Procter Road	-	0.318	0.129	2	X			
Rabel Road	447		1.566	2		X	165,815,613	3,806.60
Radio Road	103	0.304		2		X	6,573,852	150.91
Railroad Street	-	0.220	0.308	2	X			
Rainbow Road	151	1.102	1.658	2		X	61,635,577	1,414.96
Rappold Road	252	1.871		2		X	40,901,024	938.96
Rathkamp Lane	225		0.753	2		X	29,354,449	673.89
Rau Road	3036	1.318		2		X	15,691,387	360.22
Rebecca Lane	-	0.270		2		X	2,908,788	66.78
Redies Road	-	0.371		2		X	49,600,908	1,138.68
Remmers Road	330	2.261		2		X	48,861,503	1,121.71
Respondek Road	-	1.428		2		X	16,139,273	370.51
Rice & Davis Road	259	1.686		2		X	27,157,317	623.45
Rice Road	265	2.544		2		X	62,600,338	1,437.11
Richter Road	209	1.673		2		X	31,950,773	733.49
River Oaks Road	-	0.413		2		X	5,580,893	128.12
River Ridge Road	-	0.351		2	X			
River Road	409	3.813		2		X	117,886,439	2,706.30
Robert Meischen Road	346	1.216		2		X	55,281,547	1,269.09
Robert Meischen Road	319	0.781		2		X	30,885,490	709.03
Roeder Ranch Road	342		0.854	2		X	34,466,706	791.25
Rogge-Seifert Road	358		5.263	2		X	132,213,067	3,035.19
Romeo Korth Road	349		0.750	2		X	47,821,033	1,097.82
Rosie Dunn Road	153	0.463		2		X	20,835,303	478.31
Rothkamp & Dreyer Road	223	2.127		2		X	40,721,106	934.83
Royal Oaks 1 Road	308	1.343		2	X			
Royal Oaks 2 Road	3023	0.423		2	X			
Ryan Ranch Road	376		1.727	2		X	104,816,119	2,406.25
S. A. Butler Road	322	0.788		2		X	13,870,399	318.42
Salt Creek Cemetery Road	3014		2.607	2		X	94,658,788	2,173.07
Sam Morris Road	127		0.716	2		X	20,079,701	460.97
Sandy Gate 2 Road	3007		0.807	2		X	9,441,869	216.76
Sandy Gate Road	3005		0.831	2		X	9,159,366	210.27
Sapp Road	279	2.119		2		X	50,189,245	1,152.19
Sauer Bade Road	406	2.506		2		X	70,200,011	1,611.57
Scheffler Road	325	1.065		2		X	16,661,849	382.50
Scheffler Road	357		2.903	2		X	49,492,894	1,136.20

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Schendel Road	350		2.508	2		X	95,541,522	2,193.33
Schleicher Road	-	0.384		2	X			
Schlenstedt Road	137	1.866		2		X	33,506,678	769.21
Schlinke Road	128	2.763		2		X	54,159,396	1,243.33
Schmidt Road	229	1.123		2		X	18,713,093	429.59
Schneider Ranch Road	365		1.681	2		X	26,079,409	598.70
Schorre Pieper Road	442	2.897		2		X	78,834,981	1,809.80
Schuenemann Road	379		0.671	2		X	6,025,147	138.32
Schulle Road	143	1.699	1.377	2		X	59,713,050	1,370.82
Schultz Road	304	1.228		2		X	18,882,343	433.48
Seidel Road	141		1.408	2		X	25,228,200	579.16
Seiler Road	362		1.036	2		X	18,741,679	430.25
Shirley Ross Road	436		1.016	2		X	6,396,335	146.84
Shows Brothers Road	353		0.880	2		X	36,366,668	834.86
Sievert Pit Road	146		1.826	2		X	28,283,362	649.30
Simecek Road	392		4.433	2		X	104,745,846	2,404.63
Simpson Ranch Road	323	2.527		2		X	84,875,862	1,948.48
Sinclair Road	158		1.060	2		X	35,631,273	817.98
Slickfield Road	3027	1.757	2.539	2		X	149,208,376	3,425.35
Smith Ranch Road	122	3.769	2.050	2		X	192,216,880	4,412.69
Sonneborn Road	381		0.790	2		X	20,762,176	476.63
South Golly Road	-	1.672	0.349	2		X	39,146,879	898.69
South River Road	401	4.080		2		X	148,345,620	3,405.55
Spies Road	388		2.293	2		X	81,229,326	1,864.77
St. John School Road	126	1.064		2		X	9,613,976	220.71
Stanchos Road	391		1.141	2		X	44,421,622	1,019.78
Stanley Dworaczyk Road	339		3.540	2		X	91,582,303	2,102.44
Steen Road	155	1.424		2		X	37,276,469	855.75
Steinmann Road	264		1.927	2		X	42,099,572	966.47
Stockdale Road	-	0.161		2		X	11,862,501	272.33
Stratton Road	283	2.434		2		X	46,270,929	1,062.23
Suhr Road	210	0.814		2		X	6,835,229	156.92
Sunday Lane	336	1.528		2		X	32,545,766	747.15
Swartz	-		0.080	2	X			
Sweet Potato Road	364		0.292	2		X	7,749,111	177.90
Sycamore Lane	-		0.190	2	X			
Talk Ranch Road	310	1.160		2		X	16,449,245	377.62
Talk Road	3031		0.895	2		X	63,557,123	1,459.07
Tamm Road	3475	1.118	1.576	2		X	49,850,324	1,144.41
Taylor Road	430	0.749	0.974	2		X	60,822,290	1,396.29
Terryville Church Road	266		0.706	2		X	47,666,680	1,094.28
Thiele Road	-	0.243		2		X	32,575,577	747.83
Thieme Road	360		1.636	2		X	35,617,252	817.66
Thomaston River Road	104	2.269		2		X	49,102,571	1,127.24
Thomaston River Road	418	3.626		2		X	107,721,376	2,472.94
Tully Road	435	1.327	0.236	2		X	30,012,794	689.00
Vahalik Road	221	0.461		2		X	25,675,598	589.43

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Van Vleck	-		0.271	2	X			
Verhelle Road	104	1.630	4.440	2		X	340,779,866	7,823.23
VFW Road	303	2.310		2		X	32,141,255	737.86
Von Haefen Road	119	2.104	0.334	2		X	64,602,314	1,483.07
W. Egg Road	425		1.012	2		X	31,449,430	721.98
Walicek Road	250	1.298		2		X	14,297,123	328.22
Walter Mueller Road	3002		1.461	2		X	26,673,879	612.35
Ward Road	238		0.163	2		X	8,177,401	187.73
Warzecha Lane	-		0.446	2		X	2,817,317	64.68
Wendel Road	403	2.614		2		X	45,906,775	1,053.87
Westhoff Cemetery Road	136	0.124	1.441	2		X	28,145,393	646.13
Westside Cemetery Road	316	0.692		2	X			
Whitley Road	236		0.826	2		X	31,578,922	724.95
Wied Road	380		1.426	2		X	19,708,935	452.45
Wild Road	159		1.290	2		X	33,115,751	760.23
Williams	-		0.160	2		X	52,540,625	1,206.17
Willie Blank Road	205	0.667		2		X	12,232,432	280.82
Willie Buesing Road	386		0.508	2		X	12,307,062	282.53
Wilson Wagner	-	0.141		2	X			
Wischkaemper Road	3010		2.957	2		X	50,545,535	1,160.37
Wofford Lane	162		0.640	2		X	67,721,492	1,554.67
Wolf & Hartman Road	402	0.886		2		X	74,629,763	1,713.26
Wolf Hollow Road	110		5.639	2		X	284,170,768	6,523.66
Woodman Cemetery Road	437		0.264	2		X	3,642,517	83.62
Woods Cemetery Road	3478		0.668	2		X	21,576,638	495.33
Woods Road	3477	1.959		2		X	51,239,918	1,176.31
Wuench Road	389		2.211	2		X	47,386,542	1,087.85
Y Ochoa Road	3032		1.356	2		X	115,326,619	2,647.53
York Cemetery Road	447		1.070	2		X	54,950,187	1,261.48
Yorktown Heights	313	0.198		2	X			
Yorktown Slickfield Road	3042	2.834		2		X	122,245,697	2,806.38
Zengerle Road	161	0.882	0.533	2		X	111,209,305	2,553.01
Zimmerman Road	117	0.606		2		X	25,234,133	579.30
Zion Cemetery Road	-	0.510		2		X	11,289,480	259.17
Zorn Road	3454	1.929		2		X	55,530,580	1,274.81
TOTAL		379.840	305.078		52	354	20,000,982,164	459,159.37
OVERALL TOTAL		684.918			406			

¹ The usage of an area was determined to be residential if the area consisted of multiple homesites or near cities and townsites, as these areas would likely not support drilling activities, usage of other .

² The service area was not determined for the areas that were deemed residential as oil field drilling activities are not likely to occur in the area.

APPENDIX C



APPENDIX C
Western DeWitt County Road Information
for the Eagle Ford Shale Play
West of US Highway 77A and West of State Highway 72

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Bellevue Cemetery Road	147	6.702		2		X	329,238,785	7,558.28
Cheapside Road	148	6.090		2		X	295,593,638	6,785.90
Smith Ranch Road	122	3.769	2.050	2		X	192,216,880	4,412.69
Catholic Church Lane	138		2.476	2		X	177,646,668	4,078.21
Cabeza Highway	324	8.583	1.280	2		X	165,679,026	3,803.47
C W Gabler Road	345		0.611	2		X	159,703,853	3,666.30
Hartman Road	130		4.417	2		X	157,676,116	3,619.75
Garfield Road	317	6.386		2		X	155,625,867	3,572.68
Dubose Ranch Road	399		6.614	2		X	147,395,138	3,383.73
Boldt Road	129	5.341		2		X	143,926,890	3,304.11
Rogge-Seifert Road	358		5.263	2		X	132,213,067	3,035.19
Concrete & Edgar Road	242	5.257		2		X	128,221,991	2,943.57
Jaeger Road	3011		1.640	2		X	127,191,311	2,919.91
McCurdy Road	154	3.746		2		X	119,371,579	2,740.39
Braden Road	168		0.563	2		X	112,471,999	2,582.00
Biemer Road	463		3.141	2		X	110,643,411	2,540.02
Metting School Road	3464	4.207		2		X	107,617,084	2,470.55
Barnhart Ranch Road	165	0.935	0.027	2		X	107,517,118	2,468.25
Ryan Ranch Road	376		1.727	2		X	104,816,119	2,406.25
Simecek Road	392		4.433	2		X	104,745,846	2,404.63
Kubala Store Road	397		4.903	2		X	103,454,288	2,374.98
Hilbrich Road	145	0.986		2		X	99,035,765	2,273.55
Lindenau Road	157	2.490		2		X	97,248,301	2,232.51
Schendel Road	350		2.508	2		X	95,541,522	2,193.33
Salt Creek Cemetery Road	3014		2.607	2		X	94,658,788	2,173.07
Kozelski Road	112		3.243	2		X	93,841,011	2,154.29
Elder Road	116	2.221		2		X	92,585,077	2,125.46
A. Hahn Road	144		2.521	2		X	92,453,204	2,122.43
Stanley Dworaczyk Road	339		3.540	2		X	91,582,303	2,102.44
Alfred Blaschke Road	374		4.935	2		X	89,223,238	2,048.28
Cottonpatch Road	341	1.588	1.333	2		X	88,620,430	2,034.45
Dagg Road	219	2.211		2		X	87,568,548	2,010.30
Simpson Ranch Road	323	2.527		2		X	84,875,862	1,948.48
Lackey Lane	125		0.984	2		X	84,173,574	1,932.36
Spies Road	388		2.293	2		X	81,229,326	1,864.77
Morris Community Road	200	4.370		2		X	80,604,941	1,850.43
George Klein Road	344	0.181	2.511	2		X	74,934,955	1,720.27
Pargmann Road	203	3.018		2		X	74,808,972	1,717.38
Old Gonzales Road	108	3.480		2		X	73,607,323	1,689.79
Brown Road	245		3.060	2		X	73,057,948	1,677.18
Arndt Road	139		1.244	2		X	72,926,455	1,674.16

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Herman Road	237		0.637	2		X	70,035,849	1,607.80
Hannessee	246	3.190		2		X	69,860,882	1,603.79
Dreyer-Turkey Bottom Road	230	2.336		2		X	68,075,813	1,562.81
Wofford Lane	162		0.640	2		X	67,721,492	1,554.67
Hrabovsky Road	215	2.773		2		X	67,344,280	1,546.01
Gruenau Road	305	3.693		2		X	67,116,872	1,540.79
E. Swartz Road	3457	1.464		2		X	66,826,714	1,534.13
Gohlke School Road	393	2.951		2		X	66,547,966	1,527.73
Hattenbach Road	3009		0.364	2		X	66,279,532	1,521.57
Von Haefen Road	119	2.104	0.334	2		X	64,602,314	1,483.07
Emil Blank Road	205	3.418		2		X	63,243,324	1,451.87
Old Davy Road	3015		1.157	2		X	62,256,202	1,429.21
Immenhauser Road	207	2.213		2		X	60,530,031	1,389.58
Schulle Road	143	1.699	1.377	2		X	59,713,050	1,370.82
Lone Tree Road	224	3.642		2		X	59,019,366	1,354.90
Hy Koopmann Road	3019		2.153	2		X	58,610,012	1,345.50
Martinez Road	227	3.056		2		X	56,540,698	1,298.00
Noe Hinojosa Road	351		2.071	2		X	55,719,638	1,279.15
Robert Meischen Road	346	1.216		2		X	55,281,547	1,269.09
Frels Road	241	0.439		2		X	52,931,460	1,215.14
Coskey Ranch Road	377		1.870	2		X	52,552,011	1,206.43
Williams Road	-		0.160	2		X	52,540,625	1,206.17
Frank Kozielski Road	318	1.973		2		X	52,176,091	1,197.80
Bootlegger Road	202	2.641		2		X	50,672,667	1,163.28
Wischkaemper Road	3010		2.957	2		X	50,545,535	1,160.37
Scheffler Road	357		2.903	2		X	49,492,894	1,136.20
Czaja Bros Road	3018		2.163	2		X	48,102,363	1,104.28
Romeo Korth Road	349		0.750	2		X	47,821,033	1,097.82
Wuench Road	389		2.211	2		X	47,386,542	1,087.85
Matejek Road	398		2.030	2		X	47,005,362	1,079.09
Nathan Mueller Road	337		0.911	2		X	46,250,813	1,061.77
Nolte-Boehl Road	132	0.319	1.660	2		X	45,022,464	1,033.57
Hules Road	208	1.806		2		X	44,813,831	1,028.78
Herder Road	212	2.140		2		X	44,458,927	1,020.64
Stanchos Road	391		1.141	2		X	44,421,622	1,019.78
Meyer Road	142	1.419	0.678	2		X	44,316,955	1,017.38
Little McGehee Road	243		1.903	2		X	43,142,734	990.42
Henry Blank Road	231	1.287		2		X	43,020,174	987.61
Hoehne Road	166		1.466	2		X	42,521,537	976.16
Leo Nelson Road	3017		2.294	2		X	42,290,325	970.85
Larry Vasbinder Road	320	0.453	1.565	2			41,178,691	945.33
Rothkamp & Dreyer Road	223	2.127		2		X	40,721,106	934.83
Elroyce Helmers Road	356		1.688	2		X	38,856,832	892.03
Bill Lemke Road	334		1.180	2		X	38,022,719	872.88
Steen Road	155	1.424		2		X	37,276,469	855.75
Shows Brothers Road	353		0.880	2		X	36,366,668	834.86
Nessel Road	164	1.096	1.127	2		X	35,681,672	819.14

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Sinclair Road	158		1.060	2		X	35,631,273	817.98
Thieme Road	360		1.636	2		X	35,617,252	817.66
Maron Road	361		1.947	2		X	35,467,703	814.23
Davy Road	-	2.110		2		X	35,251,454	809.26
Harvey Hahn Road	3041	0.538	1.639	2		X	35,077,221	805.26
Old Cheapside Road	163	0.764		2		X	35,068,545	805.06
Baker Road	3001		0.576	2		X	34,663,348	795.76
Roeder Ranch Road	342		0.854	2		X	34,466,706	791.25
Bramlette Road	244	1.614		2		X	34,115,277	783.18
Schlenstedt Road	137	1.866		2		X	33,506,678	769.21
Wild Road	159		1.290	2		X	33,115,751	760.23
Thiele Road	-	0.243		2		X	32,575,577	747.83
Sunday Lane	336	1.528		2		X	32,545,766	747.15
VFW Road	303	2.310		2		X	32,141,255	737.86
Richter Road	209	1.673		2		X	31,950,773	733.49
Whitley Road	236		0.826	2		X	31,578,922	724.95
Jackson Road	395		1.753	2		X	30,906,855	709.52
Robert Meischen Road	319	0.781		2		X	30,885,490	709.03
Morgan Road	-	0.930		2		X	30,878,143	708.86
Mueller Road	106	1.680		2		X	30,794,084	706.93
Berkenhoff Road	340		0.780	2		X	30,704,793	704.89
Ckudre Road	352		1.604	2		X	30,203,460	693.38
Rathkamp Lane	225		0.753	2		X	29,354,449	673.89
Lincke Road	396		2.264	2		X	29,310,033	672.87
Emil Meyer Road	3020		1.216	2		X	28,793,538	661.01
Sievert Pit Road	146		1.826	2		X	28,283,362	649.30
Westhoff Cemetery Road	136	0.124	1.441	2		X	28,145,393	646.13
Heider Road	-		0.180	2		X	27,586,373	633.30
Ed Blackwell Road	124	1.358		2		X	26,971,589	619.18
Gerdes Road	226	1.580		2		X	26,950,752	618.70
Gus Meyer Road	3012		1.776	2		X	26,871,724	616.89
Walter Mueller Road	3002		1.461	2		X	26,673,879	612.35
A Metting Road	3006		2.073	2		X	26,143,190	600.17
Schneider Ranch Road	365		1.681	2		X	26,079,409	598.70
Vahalik Road	221	0.461		2		X	25,675,598	589.43
Zimmerman Road	117	0.606		2		X	25,234,133	579.30
Seidel Road	141		1.408	2		X	25,228,200	579.16
Morris School Road	201	1.426		2		X	25,198,627	578.48
Frank Hinojosa Road	355		1.563	2		X	24,454,494	561.40
Lockhart Cemetery Road	160	1.935		2		X	22,646,213	519.89
Woods Cemetery Road	3478		0.668	2		X	21,576,638	495.33
Rosie Dunn Road	153	0.463		2		X	20,835,303	478.31
Sam Morris Road	127		0.716	2		X	20,079,701	460.97
Schultz Road	304	1.228		2		X	18,882,343	433.48
Seiler Road	362		1.036	2		X	18,741,679	430.25
Green Cemetery Road	247		0.483	2		X	18,731,709	430.02
Schmidt Road	229	1.123		2		X	18,713,093	429.59

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Nelson Road	222	0.691		2		X	18,560,536	426.09
Gerhold Road	289		0.766	2		X	18,039,733	414.14
Lackey Ranch Road	343		1.163	2		X	16,904,507	388.07
Scheffler Road	325	1.065		2		X	16,661,849	382.50
H Harms Road	378		1.000	2		X	16,139,361	370.51
Respondek Road	-	1.428		2		X	16,139,273	370.51
Allen Lane	204		0.450	2		X	15,956,537	366.31
Haase Brothers Road	394		1.051	2		X	15,860,714	364.11
City of Hochheim Road	234	0.966		2		X	15,745,115	361.46
Plasczyk Road	3016		1.276	2		X	15,625,604	358.71
Guilford School Road	-		0.201	2		X	15,530,230	356.53
Ben Meischen Road	338		0.747	2		X	14,790,457	339.54
Interstate 13 Road	3013		1.010	2		X	14,154,663	324.95
Boehm Road	156	1.143		2		X	13,932,316	319.84
S. A. Butler Road	322	0.788		2		X	13,870,399	318.42
Muschalek Road	347		0.920	2		X	13,761,265	315.92
Edmund Mueller Road	359		1.003	2		X	13,565,179	311.41
Edna Hattenbach Road	135		0.500	2		X	13,522,440	310.43
K Thiele Road	220	1.003		2		X	13,520,724	310.39
Willie Blank Road	205	0.667		2		X	12,232,432	280.82
Pete Jablonski Road	3465	0.926		2		X	11,834,490	271.68
Chaddock Road	131		0.910	2		X	11,426,560	262.32
Center School Road	287		0.276	2		X	11,166,399	256.35
Blackwell Lane	121	1.223		2		X	10,578,727	242.85
Old San Antonio Road	-	0.980		2		X	9,995,596	229.47
Howard Weise Road	335		0.310	2		X	9,689,998	222.45
St. John School Road	126	1.064		2		X	9,613,976	220.71
Sandy Gate 2 Road	3007		0.807	2		X	9,441,869	216.76
Sandy Gate Road	3005		0.831	2		X	9,159,366	210.27
McElroy Road	239	1.158		2		X	8,860,125	203.40
Johnny Pokluda Road	321	0.677		2		X	8,834,088	202.80
Musselman Road	235		0.751	2		X	8,246,294	189.31
Ward Road	238		0.163	2		X	8,177,401	187.73
Sweet Potato Road	364		0.292	2		X	7,749,111	177.90
Blake Road	307		0.380	2		X	6,421,937	147.43
Schuenemann Road	379		0.671	2		X	6,025,147	138.32
Chilek Road	232	0.646		2		X	4,887,788	112.21
Onken Road	375		0.574	2		X	4,834,475	110.98
Crestview Road	301	0.543		2		X	4,545,129	104.34
Dieringer Road	290		0.176	2		X	4,432,307	101.75
Edwin Schroeder Road	390		0.583	2		X	4,056,291	93.12
Hells Gate Road	167		0.400	2		X	3,881,135	89.10
Buckhorn Road	371		0.146	2		X	3,606,450	82.79
Anderson Avenue	-	0.338		2		X	3,169,425	72.76
Warzecha Lane	-		0.446	2		X	2,817,317	64.68
Bluebonnet Lane	217	1.101		2		X	2,581,249	59.26
Mann Road	332	0.174		2		X	2,427,264	55.72

Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²	
		Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage
Arndt Bypass Road	-		0.236	2		X	1,185,754	27.22
Auction Ring Road	171	0.037	0.113	2		X	256,223	5.88
6th Street	314	0.674		2	X		-	-
7th Street	-	0.130		2	X		-	-
8th Street	315	0.681		2	X		-	-
8th Street	3462	0.248		2	X		-	-
Bunjus Road	-	0.413		2	X		-	-
Carter Road	-	0.126		2	X		-	-
Cook Road	-	0.318		2	X		-	-
Cottonwood Road	-	0.281		2	X		-	-
Crain Road	-	0.177	0.159	2	X		-	-
Elizabeth Street	-	0.161	0.099	2	X		-	-
Fay Avenue	-		0.068	2	X		-	-
Flato Street	-	0.360		2	X		-	-
Hochheim Cemetery Road	-	0.164		2	X		-	-
Houston Street	-	0.084		2	X		-	-
Isdale Road	216	0.960		2	X		-	-
Lane Avenue	-	0.805		2	X		-	-
Lee Avenue	-	0.207		2	X		-	-
Lynch Road	-	0.260		2	X		-	-
Main Street	-		0.138	2	X		-	-
Mesquite Lane	-	0.243		2	X		-	-
Mockingbird	-	0.227		2	X		-	-
Mulberry Road	-	0.620		2	X		-	-
Naranjo Road	-		0.245	2	X		-	-
Oliver Road	-	0.363		2	X		-	-
Petru Road	218	0.130		2	X		-	-
Procter Road	-	0.318	0.129	2	X		-	-
Railroad Street	-	0.220	0.308	2	X		-	-
River Ridge Road	-	0.351		2	X		-	-
Schleicher Road	-	0.384		2	X		-	-
Van Vleck	-		0.271	2	X		-	-
Westside Cemetery Road	316	0.692		2	X		-	-
Yorktown Heights	313	0.198		2	X		-	-
TOTAL		177.721	164.273		32	183	9,209,182,894	211,413.75
OVERALL TOTAL		341.994			215			

¹ The usage of an area was determined to be unfavorable if the area consisted of multiple homesites or near cities and townsites, as these areas would likely not support drilling activities, usage of other .

² The service area was not determined for the areas that were deemed residential as oil field drilling activities are not likely to occur in the area.

APPENDIX D



APPENDIX D
Well Development Assignment by Roadway
for the Eagle Ford Shale Play
West of US Highway 77A and West of State Highway 72

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W001	Bellevue Cemetery Road	147	6.702		2		X	329,238,785	7,558.28	116
W002	Cheapside Road	148	6.090		2		X	295,593,638	6,785.90	104
W003	Smith Ranch Road	122	3.769	2.050	2		X	192,216,880	4,412.69	68
W004	Catholic Church Lane	138		2.476	2		X	177,646,668	4,078.21	63
W005	Cabeza Highway	324	8.583	1.280	2		X	165,679,026	3,803.47	59
W006	C W Gabler Road	345		0.611	2		X	159,703,853	3,666.30	56
W007	Hartman Road	130		4.417	2		X	157,676,116	3,619.75	56
W008	Garfield Road	317	6.386		2		X	155,625,867	3,572.68	55
W009	Dubose Ranch Road	399		6.614	2		X	147,395,138	3,383.73	52
W010	Boldt Road	129	5.341		2		X	143,926,890	3,304.11	51
W011	Rogge-Seifert Road	358		5.263	2		X	132,213,067	3,035.19	47
W012	Concrete & Edgar Road	242	5.257		2		X	128,221,991	2,943.57	45
W013	Jaeger Road	3011		1.640	2		X	127,191,311	2,919.91	45
W014	McCurdy Road	154	3.746		2		X	119,371,579	2,740.39	42
W016	Braden Road	168		0.563	2		X	112,471,999	2,582.00	40
W015	Biemer Road	463		3.141	2		X	110,643,411	2,540.02	39
W017	Metting School Road	3464	4.207		2		X	107,617,084	2,470.55	38
W018	Barnhart Ranch Road	165	0.935	0.027	2		X	107,517,118	2,468.25	38
W019	Ryan Ranch Road	376		1.727	2		X	104,816,119	2,406.25	37
W020	Simecek Road	392		4.433	2		X	104,745,846	2,404.63	37
W021	Kubala Store Road	397		4.903	2		X	103,454,288	2,374.98	37
W022	Hilbrich Road	145	0.986		2		X	99,035,765	2,273.55	35
W023	Lindenau Road	157	2.490		2		X	97,248,301	2,232.51	34
W024	Schendel Road	350		2.508	2		X	95,541,522	2,193.33	34
W025	Salt Creek Cemetery Road	3014		2.607	2		X	94,658,788	2,173.07	33
W026	Kozelski Road	112		3.243	2		X	93,841,011	2,154.29	33
W027	Elder Road	116	2.221		2		X	92,585,077	2,125.46	33

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W028	A. Hahn Road	144		2.521	2		X	92,453,204	2,122.43	33
W029	Stanley Dworaczyk Road	339		3.540	2		X	91,582,303	2,102.44	32
W030	Alfred Blaschke Road	374		4.935	2		X	89,223,238	2,048.28	32
W031	Cottonpatch Road	341	1.588	1.333	2		X	88,620,430	2,034.45	31
W032	Dagg Road	219	2.211		2		X	87,568,548	2,010.30	31
W033	Simpson Ranch Road	323	2.527		2		X	84,875,862	1,948.48	30
W034	Lackey Lane	125		0.984	2		X	84,173,574	1,932.36	30
W035	Spies Road	388		2.293	2		X	81,229,326	1,864.77	29
W036	Morris Community Road	200	4.370		2		X	80,604,941	1,850.43	28
W037	George Klein Road	344	0.181	2.511	2		X	74,934,955	1,720.27	26
W038	Pargmann Road	203	3.018		2		X	74,808,972	1,717.38	26
W039	Old Gonzales Road	108	3.480		2		X	73,607,323	1,689.79	26
W040	Brown Road	245		3.060	2		X	73,057,948	1,677.18	26
W041	Arndt Road	139		1.244	2		X	72,926,455	1,674.16	26
W042	Herman Road	237		0.637	2		X	70,035,849	1,607.80	25
W043	Hannessee	246	3.190		2		X	69,860,882	1,603.79	25
W044	Dreyer-Turkey Bottom Road	230	2.336		2		X	68,075,813	1,562.81	24
W045	Wofford Lane	162		0.640	2		X	67,721,492	1,554.67	24
W046	Hrabovsky Road	215	2.773		2		X	67,344,280	1,546.01	24
W047	Gruenau Road	305	3.693		2		X	67,116,872	1,540.79	24
W048	E. Swartz Road	3457	1.464		2		X	66,826,714	1,534.13	24
W049	Gohlke School Road	393	2.951		2		X	66,547,966	1,527.73	24
W050	Hattenbach Road	3009		0.364	2		X	66,279,532	1,521.57	23
W051	Von Haefen Road	119	2.104	0.334	2		X	64,602,314	1,483.07	23
W052	Emil Blank Road	205	3.418		2		X	63,243,324	1,451.87	22
W053	Old Davy Road	3015		1.157	2		X	62,256,202	1,429.21	22
W054	Immenhauser Road	207	2.213		2		X	60,530,031	1,389.58	21
W055	Schulle Road	143	1.699	1.377	2		X	59,713,050	1,370.82	21
W056	Lone Tree Road	224	3.642		2		X	59,019,366	1,354.90	21
W057	Hy Koopmann Road	3019		2.153	2		X	58,610,012	1,345.50	21
W058	Martinez Road	227	3.056		2		X	56,540,698	1,298.00	20
W059	Noe Hinojosa Road	351		2.071	2		X	55,719,638	1,279.15	20
W060	Robert Meischen Road	346	1.216		2		X	55,281,547	1,269.09	20

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W061	Frels Road	241	0.439		2		X	52,931,460	1,215.14	19
W062	Coskey Ranch Road	377		1.870	2		X	52,552,011	1,206.43	19
W063	Williams Road	-		0.160	2		X	52,540,625	1,206.17	19
W064	Frank Kozielski Road	318	1.973		2		X	52,176,091	1,197.80	18
W065	Bootlegger Road	202	2.641		2		X	50,672,667	1,163.28	18
W066	Wischkaemper Road	3010		2.957	2		X	50,545,535	1,160.37	18
W067	Scheffler Road	357		2.903	2		X	49,492,894	1,136.20	17
W068	Czaja Bros Road	3018		2.163	2		X	48,102,363	1,104.28	17
W069	Romeo Korth Road	349		0.750	2		X	47,821,033	1,097.82	17
W070	Wuench Road	389		2.211	2		X	47,386,542	1,087.85	17
W071	Matejek Road	398		2.030	2		X	47,005,362	1,079.09	17
W072	Nathan Mueller Road	337		0.911	2		X	46,250,813	1,061.77	16
W073	Nolte-Boehl Road	132	0.319	1.660	2		X	45,022,464	1,033.57	16
W074	Hules Road	208	1.806		2		X	44,813,831	1,028.78	16
W075	Herder Road	212	2.140		2		X	44,458,927	1,020.64	16
W076	Stanchos Road	391		1.141	2		X	44,421,622	1,019.78	16
W077	Meyer Road	142	1.419	0.678	2		X	44,316,955	1,017.38	16
W078	Little McGehee Road	243		1.903	2		X	43,142,734	990.42	15
W079	Henry Blank Road	231	1.287		2		X	43,020,174	987.61	15
W080	Hoehne Road	166		1.466	2		X	42,521,537	976.16	15
W081	Leo Nelson Road	3017		2.294	2		X	42,290,325	970.85	15
W082	Larry Vasbinder Road	320	0.453	1.565	2			41,178,691	945.33	15
W083	Rothkamp & Dreyer Road	223	2.127		2		X	40,721,106	934.83	14
W084	Elroyce Helmers Road	356		1.688	2		X	38,856,832	892.03	14
W085	Bill Lemke Road	334		1.180	2		X	38,022,719	872.88	13
W086	Steen Road	155	1.424		2		X	37,276,469	855.75	13
W087	Shows Brothers Road	353		0.880	2		X	36,366,668	834.86	13
W088	Nessel Road	164	1.096	1.127	2		X	35,681,672	819.14	13
W089	Sinclair Road	158		1.060	2		X	35,631,273	817.98	13
W090	Thieme Road	360		1.636	2		X	35,617,252	817.66	13
W091	Maron Road	361		1.947	2		X	35,467,703	814.23	13
W092	Davy Road	-	2.110		2		X	35,251,454	809.26	12
W093	Harvey Hahn Road	3041	0.538	1.639	2		X	35,077,221	805.26	12

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W094	Old Cheapside Road	163	0.764		2		X	35,068,545	805.06	12
W095	Baker Road	3001		0.576	2		X	34,663,348	795.76	12
W096	Roeder Ranch Road	342		0.854	2		X	34,466,706	791.25	12
W097	Bramlette Road	244	1.614		2		X	34,115,277	783.18	12
W098	Schlenstedt Road	137	1.866		2		X	33,506,678	769.21	12
W099	Wild Road	159		1.290	2		X	33,115,751	760.23	12
W100	Thiele Road	-	0.243		2		X	32,575,577	747.83	12
W101	Sunday Lane	336	1.528		2		X	32,545,766	747.15	11
W102	VFW Road	303	2.310		2		X	32,141,255	737.86	11
W103	Richter Road	209	1.673		2		X	31,950,773	733.49	11
W104	Whitley Road	236		0.826	2		X	31,578,922	724.95	11
W105	Jackson Road	395		1.753	2		X	30,906,855	709.52	11
W106	Robert Meischen Road	319	0.781		2		X	30,885,490	709.03	11
W107	Morgan Road	-	0.930		2		X	30,878,143	708.86	11
W108	Mueller Road	106	1.680		2		X	30,794,084	706.93	11
W109	Berkenhoff Road	340		0.780	2		X	30,704,793	704.89	11
W110	Ckudre Road	352		1.604	2		X	30,203,460	693.38	11
W111	Rathkamp Lane	225		0.753	2		X	29,354,449	673.89	10
W112	Lincke Road	396		2.264	2		X	29,310,033	672.87	10
W113	Emil Meyer Road	3020		1.216	2		X	28,793,538	661.01	10
W114	Sievert Pit Road	146		1.826	2		X	28,283,362	649.30	10
W115	Westhoff Cemetery Road	136	0.124	1.441	2		X	28,145,393	646.13	10
W116	Heider Road	-		0.180	2		X	27,586,373	633.30	10
W117	Ed Blackwell Road	124	1.358		2		X	26,971,589	619.18	10
W118	Gerdes Road	226	1.580		2		X	26,950,752	618.70	10
W119	Gus Meyer Road	3012		1.776	2		X	26,871,724	616.89	9
W120	Walter Mueller Road	3002		1.461	2		X	26,673,879	612.35	9
W121	A Metting Road	3006		2.073	2		X	26,143,190	600.17	9
W122	Schneider Ranch Road	365		1.681	2		X	26,079,409	598.70	9
W123	Vahalik Road	221	0.461		2		X	25,675,598	589.43	9
W124	Zimmerman Road	117	0.606		2		X	25,234,133	579.30	9
W125	Seidel Road	141		1.408	2		X	25,228,200	579.16	9
W126	Morris School Road	201	1.426		2		X	25,198,627	578.48	9

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W127	Frank Hinojosa Road	355		1.563	2		X	24,454,494	561.40	9
W128	Lockhart Cemetery Road	160	1.935		2		X	22,646,213	519.89	8
W129	Woods Cemetery Road	3478		0.668	2		X	21,576,638	495.33	8
W130	Rosie Dunn Road	153	0.463		2		X	20,835,303	478.31	7
W131	Sam Morris Road	127		0.716	2		X	20,079,701	460.97	7
W132	Schultz Road	304	1.228		2		X	18,882,343	433.48	7
W133	Seiler Road	362		1.036	2		X	18,741,679	430.25	7
W134	Green Cemetery Road	247		0.483	2		X	18,731,709	430.02	7
W135	Schmidt Road	229	1.123		2		X	18,713,093	429.59	7
W136	Nelson Road	222	0.691		2		X	18,560,536	426.09	7
W137	Gerhold Road	289		0.766	2		X	18,039,733	414.14	6
W138	Lackey Ranch Road	343		1.163	2		X	16,904,507	388.07	6
W139	Scheffler Road	325	1.065		2		X	16,661,849	382.50	6
W140	H Harms Road	378		1.000	2		X	16,139,361	370.51	6
W141	Respondek Road	-	1.428		2		X	16,139,273	370.51	6
W142	Allen Lane	204		0.450	2		X	15,956,537	366.31	6
W143	Haase Brothers Road	394		1.051	2		X	15,860,714	364.11	6
W144	City of Hochheim Road	234	0.966		2		X	15,745,115	361.46	6
W145	Plasczyk Road	3016		1.276	2		X	15,625,604	358.71	6
W146	Guilford School Road	-		0.201	2		X	15,530,230	356.53	5
W147	Ben Meischen Road	338		0.747	2		X	14,790,457	339.54	5
W148	Interstate 13 Road	3013		1.010	2		X	14,154,663	324.95	5
W149	Boehm Road	156	1.143		2		X	13,932,316	319.84	5
W150	S. A. Butler Road	322	0.788		2		X	13,870,399	318.42	5
W151	Muschalek Road	347		0.920	2		X	13,761,265	315.92	5
W152	Edmund Mueller Road	359		1.003	2		X	13,565,179	311.41	5
W153	Edna Hattenbach Road	135		0.500	2		X	13,522,440	310.43	5
W154	K Thiele Road	220	1.003		2		X	13,520,724	310.39	5
W155	Willie Blank Road	205	0.667		2		X	12,232,432	280.82	4
W156	Pete Jablonski Road	3465	0.926		2		X	11,834,490	271.68	4
W157	Chaddock Road	131		0.910	2		X	11,426,560	262.32	4
W158	Center School Road	287		0.276	2		X	11,166,399	256.35	4
W159	Blackwell Lane	121	1.223		2		X	10,578,727	242.85	4

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W160	Old San Antonio Road	-	0.980		2		X	9,995,596	229.47	4
W161	Howard Weise Road	335		0.310	2		X	9,689,998	222.45	3
W162	St. John School Road	126	1.064		2		X	9,613,976	220.71	3
W163	Sandy Gate 2 Road	3007		0.807	2		X	9,441,869	216.76	3
W164	Sandy Gate Road	3005		0.831	2		X	9,159,366	210.27	3
W165	McElroy Road	239	1.158		2		X	8,860,125	203.40	3
W166	Johnny Pokluda Road	321	0.677		2		X	8,834,088	202.80	3
W167	Musselman Road	235		0.751	2		X	8,246,294	189.31	3
W168	Ward Road	238		0.163	2		X	8,177,401	187.73	3
W169	Sweet Potato Road	364		0.292	2		X	7,749,111	177.90	3
W170	Blake Road	307		0.380	2		X	6,421,937	147.43	2
W171	Schuenemann Road	379		0.671	2		X	6,025,147	138.32	2
W172	Chilek Road	232	0.646		2		X	4,887,788	112.21	2
W173	Onken Road	375		0.574	2		X	4,834,475	110.98	2
W174	Crestview Road	301	0.543		2		X	4,545,129	104.34	2
W175	Dieringer Road	290		0.176	2		X	4,432,307	101.75	2
W176	Edwin Schroeder Road	390		0.583	2		X	4,056,291	93.12	1
W177	Hells Gate Road	167		0.400	2		X	3,881,135	89.10	1
W178	Buckhorn Road	371		0.146	2		X	3,606,450	82.79	1
W179	Anderson Avenue	-	0.338		2		X	3,169,425	72.76	1
W180	Warzecha Lane	-		0.446	2		X	2,817,317	64.68	1
W181	Bluebonnet Lane	217	1.101		2		X	2,581,249	59.26	1
W182	Mann Road	332	0.174		2		X	2,427,264	55.72	1
W183	Arndt Bypass Road	-		0.236	2		X	1,185,754	27.22	0
W184	Auction Ring Road	171	0.037	0.113	2		X	256,223	5.88	0
W185	6th Street	314	0.674		2	X		-	-	0
W186	7th Street	-	0.130		2	X		-	-	0
W187	8th Street	315	0.681		2	X		-	-	0
W188	8th Street	3462	0.248		2	X		-	-	0
W189	Bunjus Road	-	0.413		2	X		-	-	0
W190	Carter Road	-	0.126		2	X		-	-	0
W191	Cook Road	-	0.318		2	X		-	-	0
W192	Cottonwood Road	-	0.281		2	X		-	-	0

Road Rank	Road Name	County Road Number	Current Surface and Length (miles)		Travel Lanes	Adjacent Land Use ¹		Service Area ²		Well Quantity (Spacing at 65 acre)
			Paved	Improved		Unfavorable	Favorable	Square Feet	Acreage	
W193	Crain Road	-	0.177	0.159	2	X		-	-	0
W194	Elizabeth Street	-	0.161	0.099	2	X		-	-	0
W195	Fay Avenue	-		0.068	2	X		-	-	0
W196	Flato Street	-	0.360		2	X		-	-	0
W197	Hochheim Cemetery Road	-	0.164		2	X		-	-	0
W198	Houston Street	-	0.084		2	X		-	-	0
W199	Isdale Road	216	0.960		2	X		-	-	0
W200	Lane Avenue	-	0.805		2	X		-	-	0
W201	Lee Avenue	-	0.207		2	X		-	-	0
W202	Lynch Road	-	0.260		2	X		-	-	0
W203	Main Street	-		0.138	2	X		-	-	0
W204	Mesquite Lane	-	0.243		2	X		-	-	0
W205	Mockingbird	-	0.227		2	X		-	-	0
W206	Mulberry Road	-	0.620		2	X		-	-	0
W207	Naranjo Road	-		0.245	2	X		-	-	0
W208	Oliver Road	-	0.363		2	X		-	-	0
W209	Petru Road	218	0.130		2	X		-	-	0
W210	Procter Road	-	0.318	0.129	2	X		-	-	0
W211	Railroad Street	-	0.220	0.308	2	X		-	-	0
W212	River Ridge Road	-	0.351		2	X		-	-	0
W213	Schleicher Road	-	0.384		2	X		-	-	0
W214	Van Vleck	-		0.271	2	X		-	-	0
W215	Westside Cemetery Road	316	0.692		2	X		-	-	0
W216	Yorktown Heights	313	0.198		2	X		-	-	0
TOTAL			177.721	164.273		32	183	9,209,182,894	211,413.75	3,253
OVERALL TOTAL			341.994			215				

¹ The usage of an area was determined to be unfavorable if the area consisted of multiple homesites or near cities and townsites, as these areas would likely not support drilling activities, usage of other .

² The service area was not determined for the areas that were deemed residential as oil field drilling activities are not likely to occur in the area.

APPENDIX E



APPENDIX E-1

Equivlaent Axle Load Factors (EALF) for Flexible Pavement

$L_{18} = 18.00$

$L_X = \text{Weight (kips)}$

$L_{A18} = 1.00$

$L_{AX} = 1.00$

$SN = 1.00$

$P_t = 2.00$

$$EALF = \left[\left(\frac{L_{18} + L_{A18}}{L_X + L_{AX}} \right)^{4.79} \left(\frac{10^{\frac{G}{B_X}}}{10^{\frac{G}{B_{18}}}} \right) (L_{AX})^{4.33} \right]^{-1}$$

Weight (kips)	EALF	Weight (kips)	EALF	Weight (kips)	EALF
2.00	0.0002	22.50	2.7589	43.00	55.4850
2.50	0.0004	23.00	3.0510	43.50	58.5699
3.00	0.0008	23.50	3.3670	44.00	61.7891
3.50	0.0014	24.00	3.7084	44.50	65.1466
4.00	0.0021	24.50	4.0767	45.00	68.6469
4.50	0.0033	25.00	4.4734	45.50	72.2944
5.00	0.0048	25.50	4.9000	46.00	76.0936
5.50	0.0068	26.00	5.3583	46.50	80.0491
6.00	0.0095	26.50	5.8498	47.00	84.1656
6.50	0.0129	27.00	6.3764	47.50	88.4478
7.00	0.0173	27.50	6.9398	48.00	92.9007
7.50	0.0228	28.00	7.5419	48.50	97.5291
8.00	0.0296	28.50	8.1847	49.00	102.3381
8.50	0.0380	29.00	8.8701	49.50	107.3328
9.00	0.0482	29.50	9.6002	50.00	112.5185
9.50	0.0605	30.00	10.3770	50.50	117.9005
10.00	0.0752	30.50	11.2028	51.00	123.4842
10.50	0.0926	31.00	12.0798	51.50	129.2751
11.00	0.1131	31.50	13.0102	52.00	135.2789
11.50	0.1371	32.00	13.9965	52.50	141.5011
12.00	0.1649	32.50	15.0411	53.00	147.9477
12.50	0.1971	33.00	16.1464	53.50	154.6245
13.00	0.2341	33.50	17.3151	54.00	161.5376
13.50	0.2765	34.00	18.5498	54.50	168.6930
14.00	0.3247	34.50	19.8531	55.00	176.0968
14.50	0.3794	35.00	21.2278	55.50	183.7555
15.00	0.4412	35.50	22.6769	56.00	191.6754
15.50	0.5107	36.00	24.2031	56.50	199.8630
16.00	0.5887	36.50	25.8095	57.00	208.3250
16.50	0.6758	37.00	27.4992	57.50	217.0679
17.00	0.7728	37.50	29.2752	58.00	226.0987
17.50	0.8806	38.00	31.1409	58.50	235.4242
18.00	1.0000	38.50	33.0994	59.00	245.0515
18.50	1.1319	39.00	35.1541	59.50	254.9877
19.00	1.2772	39.50	37.3085	60.00	265.2400
19.50	1.4369	40.00	39.5660	60.50	275.8158
20.00	1.6121	40.50	41.9304	61.00	286.7225
20.50	1.8038	41.00	44.4052	61.50	297.9677
21.00	2.0132	41.50	46.9941	62.00	309.5591
21.50	2.2413	42.00	49.7012	62.50	321.5044
22.00	2.4895	42.50	52.5301	63.00	333.8115

Single Axle

APPENDIX E-2

Equivlaent Axle Load Factors (EALF) for Flexible Pavement

$L_{18} = 18.00$ $L_X = \text{Weight (kips)}$
 $L_{A18} = 1.00$ $L_{AX} = 2.00$
 $SN = 1.00$ $P_t = 2.00$

$$EALF = \left[\left(\frac{L_{18} + L_{A18}}{L_X + L_{AX}} \right)^{4.79} \left(\frac{10^{\frac{G}{B_X}}}{10^{\frac{G}{B_{18}}}} \right) (L_{AX})^{4.33} \right]^{-1}$$

Weight (kips)	EALF	Weight (kips)	EALF	Weight (kips)	EALF
2.00	0.0000	22.50	0.1714	43.00	3.0830
2.50	0.0001	23.00	0.1886	43.50	3.2501
3.00	0.0001	23.50	0.2070	44.00	3.4244
3.50	0.0002	24.00	0.2269	44.50	3.6059
4.00	0.0003	24.50	0.2482	45.00	3.7950
4.50	0.0004	25.00	0.2712	45.50	3.9919
5.00	0.0006	25.50	0.2957	46.00	4.1968
5.50	0.0008	26.00	0.3221	46.50	4.4099
6.00	0.0011	26.50	0.3502	47.00	4.6315
6.50	0.0014	27.00	0.3803	47.50	4.8618
7.00	0.0019	27.50	0.4124	48.00	5.1011
7.50	0.0024	28.00	0.4467	48.50	5.3496
8.00	0.0029	28.50	0.4831	49.00	5.6077
8.50	0.0036	29.00	0.5219	49.50	5.8755
9.00	0.0045	29.50	0.5631	50.00	6.1533
9.50	0.0054	30.00	0.6069	50.50	6.4415
10.00	0.0066	30.50	0.6533	51.00	6.7402
10.50	0.0079	31.00	0.7025	51.50	7.0498
11.00	0.0093	31.50	0.7546	52.00	7.3705
11.50	0.0111	32.00	0.8097	52.50	7.7027
12.00	0.0130	32.50	0.8680	53.00	8.0466
12.50	0.0152	33.00	0.9295	53.50	8.4026
13.00	0.0177	33.50	0.9945	54.00	8.7709
13.50	0.0206	34.00	1.0630	54.50	9.1520
14.00	0.0238	34.50	1.1353	55.00	9.5460
14.50	0.0273	35.00	1.2113	55.50	9.9533
15.00	0.0313	35.50	1.2914	56.00	10.3742
15.50	0.0358	36.00	1.3755	56.50	10.8092
16.00	0.0407	36.50	1.4640	57.00	11.2584
16.50	0.0462	37.00	1.5570	57.50	11.7223
17.00	0.0523	37.50	1.6545	58.00	12.2012
17.50	0.0590	38.00	1.7569	58.50	12.6954
18.00	0.0663	38.50	1.8641	59.00	13.2054
18.50	0.0744	39.00	1.9766	59.50	13.7315
19.00	0.0832	39.50	2.0943	60.00	14.2740
19.50	0.0929	40.00	2.2175	60.50	14.8334
20.00	0.1034	40.50	2.3465	61.00	15.4099
20.50	0.1149	41.00	2.4812	61.50	16.0041
21.00	0.1274	41.50	2.6221	62.00	16.6162
21.50	0.1409	42.00	2.7692	62.50	17.2468
22.00	0.1556	42.50	2.9228	63.00	17.8961

Tandem Axle

APPENDIX E-3 **Equivlaent Axle Load Factors (EALF) for Flexible Pavement**

$L_{18} = 18.00$ $L_X = \text{Weight (kips)}$
 $L_{A18} = 1.00$ $L_{AX} = 3.00$
 $SN = 1.00$ $P_t = 2.00$

$$EALF = \left[\left(\frac{L_{18} + L_{A18}}{L_X + L_{AX}} \right)^{4.79} \left(\frac{10^{\frac{G}{E_X}}}{10^{\frac{G}{E_{18}}}} \right) (L_{AX})^{4.33} \right]^{-1}$$

<i>Weight (kips)</i>	<i>EALF</i>	<i>Weight (kips)</i>	<i>EALF</i>	<i>Weight (kips)</i>	<i>EALF</i>
22.50	0.0378	43.00	0.5974	63.50	3.4595
23.00	0.0413	43.50	0.6289	64.00	3.5855
23.50	0.0450	44.00	0.6617	64.50	3.7152
24.00	0.0491	44.50	0.6958	65.00	3.8485
24.50	0.0534	45.00	0.7313	65.50	3.9856
25.00	0.0581	45.50	0.7682	66.00	4.1265
25.50	0.0630	46.00	0.8066	66.50	4.2714
26.00	0.0683	46.50	0.8465	67.00	4.4202
26.50	0.0739	47.00	0.8880	67.50	4.5732
27.00	0.0799	47.50	0.9311	68.00	4.7302
27.50	0.0863	48.00	0.9758	68.50	4.8916
28.00	0.0931	48.50	1.0221	69.00	5.0573
28.50	0.1003	49.00	1.0702	69.50	5.2273
29.00	0.1079	49.50	1.1201	70.00	5.4019
29.50	0.1161	50.00	1.1719	70.50	5.5811
30.00	0.1246	50.50	1.2255	71.00	5.7650
30.50	0.1337	51.00	1.2810	71.50	5.9536
31.00	0.1434	51.50	1.3385	72.00	6.1470
31.50	0.1535	52.00	1.3981	72.50	6.3455
32.00	0.1642	52.50	1.4597	73.00	6.5489
32.50	0.1756	53.00	1.5234	73.50	6.7575
33.00	0.1875	53.50	1.5894	74.00	6.9713
33.50	0.2001	54.00	1.6576	74.50	7.1904
34.00	0.2133	54.50	1.7281	75.00	7.4150
34.50	0.2272	55.00	1.8009	75.50	7.6451
35.00	0.2419	55.50	1.8762	76.00	7.8808
35.50	0.2572	56.00	1.9539	76.50	8.1222
36.00	0.2734	56.50	2.0342	77.00	8.3694
36.50	0.2903	57.00	2.1171	77.50	8.6226
37.00	0.3081	57.50	2.2026	78.00	8.8818
37.50	0.3268	58.00	2.2908	78.50	9.1471
38.00	0.3463	58.50	2.3819	79.00	9.4186
38.50	0.3667	59.00	2.4757	79.50	9.6965
39.00	0.3881	59.50	2.5725	80.00	9.9809
39.50	0.4105	60.00	2.6722	80.50	10.2718
40.00	0.4339	60.50	2.7750	81.00	10.5694
40.50	0.4583	61.00	2.8809	81.50	10.8737
41.00	0.4838	61.50	2.9900	82.00	11.1850
41.50	0.5105	62.00	3.1023	82.50	11.5033
42.00	0.5383	62.50	3.2180	83.00	11.8287
42.50	0.5672	63.00	3.3370	83.50	12.1613

Tri-Axle

APPENDIX E-4

Equivalent Axle Load Factors (EALF) for Flexible Pavement

$L_{18} = 18.00$ $L_X = \text{Weight (kips)}$
 $L_{A18} = 1.00$ $L_{AX} = 4.00$
 $SN = 1.00$ $P_t = 2.00$

$$EALF = \left[\left(\frac{L_{18} + L_{A18}}{L_X + L_{AX}} \right)^{4.79} \left(\frac{10^{\frac{G}{B_X}}}{10^{\frac{G}{B_{18}}}} \right) (L_{AX})^{4.33} \right]^{-1}$$

Weight (kips)	EALF	Weight (kips)	EALF	Weight (kips)	EALF
43.00	0.1938	63.50	1.0754	84.00	3.8091
43.50	0.2037	64.00	1.1138	84.50	3.9136
44.00	0.2140	64.50	1.1533	85.00	4.0204
44.50	0.2247	65.00	1.1940	85.50	4.1294
45.00	0.2358	65.50	1.2357	86.00	4.2408
45.50	0.2474	66.00	1.2786	86.50	4.3546
46.00	0.2594	66.50	1.3227	87.00	4.4707
46.50	0.2718	67.00	1.3680	87.50	4.5893
47.00	0.2847	67.50	1.4145	88.00	4.7104
47.50	0.2982	68.00	1.4623	88.50	4.8340
48.00	0.3121	68.50	1.5113	89.00	4.9601
48.50	0.3265	69.00	1.5616	89.50	5.0888
49.00	0.3414	69.50	1.6132	90.00	5.2202
49.50	0.3569	70.00	1.6662	90.50	5.3542
50.00	0.3730	70.50	1.7206	91.00	5.4910
50.50	0.3896	71.00	1.7763	91.50	5.6305
51.00	0.4068	71.50	1.8335	92.00	5.7728
51.50	0.4246	72.00	1.8921	92.50	5.9179
52.00	0.4430	72.50	1.9522	93.00	6.0660
52.50	0.4621	73.00	2.0138	93.50	6.2169
53.00	0.4818	73.50	2.0770	94.00	6.3708
53.50	0.5021	74.00	2.1417	94.50	6.5277
54.00	0.5232	74.50	2.2079	95.00	6.6876
54.50	0.5449	75.00	2.2759	95.50	6.8506
55.00	0.5673	75.50	2.3454	96.00	7.0168
55.50	0.5905	76.00	2.4166	96.50	7.1861
56.00	0.6144	76.50	2.4896	97.00	7.3587
56.50	0.6391	77.00	2.5642	97.50	7.5345
57.00	0.6646	77.50	2.6406	98.00	7.7136
57.50	0.6908	78.00	2.7189	98.50	7.8961
58.00	0.7179	78.50	2.7989	99.00	8.0820
58.50	0.7458	79.00	2.8808	99.50	8.2713
59.00	0.7746	79.50	2.9646	100.00	8.4641
59.50	0.8042	80.00	3.0503	100.50	8.6605
60.00	0.8348	80.50	3.1380	101.00	8.8605
60.50	0.8663	81.00	3.2277	101.50	9.0641
61.00	0.8986	81.50	3.3193	102.00	9.2714
61.50	0.9320	82.00	3.4130	102.50	9.4824
62.00	0.9663	82.50	3.5089	103.00	9.6972
62.50	1.0016	83.00	3.6068	103.50	9.9159
63.00	1.0380	83.50	3.7069	104.00	10.1384

Quad-Axle

APPENDIX E-5

Equivalent Axle Load Factors (EALF) for Flexible Pavement

$L_{18} = 18.00$ $L_X = \text{Weight (kips)}$
 $L_{A18} = 1.00$ $L_{AX} = 5.00$
 $SN = 1.00$ $P_t = 2.00$

$$EALF = \left[\left(\frac{L_{18} + L_{A18}}{L_X + L_{AX}} \right)^{4.79} \left(\frac{10^{\frac{G}{B_X}}}{10^{\frac{G}{B_{18}}}} \right) (L_{AX})^{4.33} \right]^{-1}$$

Weight (kips)	EALF	Weight (kips)	EALF	Weight (kips)	EALF
43.00	0.0837	63.50	0.4431	84.00	1.5363
43.50	0.0878	64.00	0.4586	84.50	1.5779
44.00	0.0920	64.50	0.4745	85.00	1.6203
44.50	0.0965	65.00	0.4909	85.50	1.6637
45.00	0.1011	65.50	0.5077	86.00	1.7079
45.50	0.1059	66.00	0.5250	86.50	1.7531
46.00	0.1108	66.50	0.5428	87.00	1.7992
46.50	0.1160	67.00	0.5610	87.50	1.8463
47.00	0.1213	67.50	0.5797	88.00	1.8944
47.50	0.1269	68.00	0.5989	88.50	1.9434
48.00	0.1326	68.50	0.6186	89.00	1.9935
48.50	0.1385	69.00	0.6388	89.50	2.0446
49.00	0.1447	69.50	0.6596	90.00	2.0967
49.50	0.1511	70.00	0.6808	90.50	2.1498
50.00	0.1577	70.50	0.7026	91.00	2.2040
50.50	0.1645	71.00	0.7250	91.50	2.2593
51.00	0.1715	71.50	0.7479	92.00	2.3157
51.50	0.1788	72.00	0.7714	92.50	2.3732
52.00	0.1864	72.50	0.7955	93.00	2.4318
52.50	0.1942	73.00	0.8202	93.50	2.4916
53.00	0.2022	73.50	0.8455	94.00	2.5525
53.50	0.2105	74.00	0.8714	94.50	2.6146
54.00	0.2191	74.50	0.8979	95.00	2.6779
54.50	0.2280	75.00	0.9250	95.50	2.7424
55.00	0.2371	75.50	0.9528	96.00	2.8081
55.50	0.2466	76.00	0.9813	96.50	2.8750
56.00	0.2563	76.50	1.0104	97.00	2.9433
56.50	0.2664	77.00	1.0403	97.50	3.0128
57.00	0.2767	77.50	1.0708	98.00	3.0836
57.50	0.2874	78.00	1.1020	98.50	3.1557
58.00	0.2984	78.50	1.1339	99.00	3.2291
58.50	0.3097	79.00	1.1666	99.50	3.3039
59.00	0.3214	79.50	1.2000	100.00	3.3801
59.50	0.3334	80.00	1.2342	100.50	3.4576
60.00	0.3458	80.50	1.2692	101.00	3.5366
60.50	0.3585	81.00	1.3049	101.50	3.6169
61.00	0.3717	81.50	1.3414	102.00	3.6987
61.50	0.3852	82.00	1.3787	102.50	3.7820
62.00	0.3990	82.50	1.4169	103.00	3.8667
62.50	0.4133	83.00	1.4558	103.50	3.9530
63.00	0.4280	83.50	1.4956	104.00	4.0407

Quint-Axle

APPENDIX F



APPENDIX F
Equivalent Single Axle Loads per Well Phase
Development Phase

Single Axle

Total Axle Load (pounds)	Representative Axle Load	Equivalency Factor	Estimated Number of Single Axles															Total EALF's
			SU-1	SU-2	2-S1	2-S2	3-S2	2-1	2-2	3-2	3-3	3-4	3-5	4-3	4-4	4-5		
> 3,000	2,000	0.0002	31	0	0	0	0	0	0	0	0	0	0	0	0	0	0.01	
3,000 to 6,999	5,000	0.0048	331	33	4	13	605	7	64	4	0	0	0	0	0	0	5.09	
7,000 to 7,999	7,500	0.0228	47	10	3	11	45	7	64	4	0	0	0	0	0	0	4.35	
8,000 to 11,999	10,000	0.0752	57	101	12	65	1,161	9	98	6	0	0	0	0	0	0	113.48	
12,000 to 15,999	14,000	0.3247	21	20	7	20	20	7	64	4	12	20	6	2	0	12	69.81	
16,000 to 18,000	17,000	0.7728	16	2	4	11	0	0	0	0	0	0	0	0	0	0	25.50	
18,001 to 18,500	18,000	1.0000	5	0	0	3	0	0	0	0	0	0	0	0	0	0	8.00	
18,501 to 20,000	19,000	1.2772	5	0	1	9	0	0	0	0	0	0	0	0	0	0	19.16	
20,001 to 21,999	21,000	2.0132	5	0	1	4	0	0	0	0	0	0	0	0	14	0	48.32	
22,000 to 23,999	23,000	3.0510	0	0	1	6	0	0	0	0	0	0	0	0	0	0	21.36	
24,000 to 25,999	25,000	4.4734	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
26,000 to 29,999	27,000	6.3764	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
30,000 +	-	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
Subtotal Total:																	315.08	

Tandem Axle

Total Axle Load (pounds)	Representative Axle Load	Equivalency Factor	Estimated Number of Tandem Axles															Total EALF's
			SU-1	SU-2	2-S1	2-S2	3-S2	2-1	2-2	3-2	3-3	3-4	3-5	4-3	4-4	4-5		
> 6,000	4,000	0.0003	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
6,000 to 11,999	9,000	0.0045	0	30	0	11	1,339	0	0	0	0	0	0	0	0	0	6.21	
12,000 to 17,999	15,000	0.0313	0	35	0	25	207	0	48	12	0	0	0	0	0	0	10.24	
18,000 to 23,999	21,000	0.1274	0	25	0	21	168	0	0	0	0	0	0	0	0	0	27.26	
24,000 to 29,999	27,000	0.3803	0	20	0	9	246	0	97	24	0	0	0	0	0	0	150.60	
30,000 to 32,000	31,000	0.7025	0	8	0	1	129	0	0	0	0	0	0	0	0	0	96.95	
32,001 to 32,500	32,000	0.8097	0	5	0	1	1,223	0	0	0	0	0	0	0	0	0	995.12	
32,501 to 33,999	33,000	0.9295	0	2	0	2	91	0	0	0	0	0	0	0	0	0	88.30	
34,000 to 35,999	35,000	1.2113	0	17	0	0	116	0	0	0	0	0	0	0	0	0	161.10	
36,000 to 37,999	37,000	1.5570	0	8	0	0	65	0	0	0	0	8	0	0	0	0	126.12	
38,000 to 39,999	39,000	1.9766	0	5	0	0	39	0	0	0	12	0	0	0	0	0	110.69	
40,000 to 41,999	41,000	2.4812	0	3	0	1	26	0	0	0	0	12	6	0	0	0	119.10	
42,000 to 43,999	43,000	3.0830	0	3	0	0	13	0	0	0	0	0	0	0	0	0	49.33	
44,000 to 45,999	45,000	3.7950	0	3	0	0	0	0	0	0	0	0	0	0	0	0	11.39	
46,000 to 49,999	48,000	5.1011	0	2	0	0	0	0	0	0	0	0	0	0	0	0	10.20	
50,000 +	-	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
Subtotal Total:																	1,962.60	

Tri-Axle

Total Axle Load (pounds)	Representative Axle Load	Equivalency Factor	Estimated Number of Tri-Axes														Total EALF's
			SU-1	SU-2	2-S1	2-S2	3-S2	2-1	2-2	3-2	3-3	3-4	3-5	4-3	4-4	4-5	
> 44,000	42,000	0.1246	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
44,000 to 47,999	46,000	0.8066	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
48,000 to 51,999	50,000	1.1719	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
52,000 to 55,999	54,000	1.6576	0	0	0	0	0	0	0	0	12	0	0	4	14	12	69.62
56,000 to 59,999	58,000	2.2908	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
60,000 to 63,999	62,000	3.1023	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
64,000 +	-	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
																Subtotal Total:	69.62

Quad-Axle

Total Axle Load (pounds)	Representative Axle Load	Equivalency Factor	Estimated Number of Quad-Axles														Total EALF's
			SU-1	SU-2	2-S1	2-S2	3-S2	2-1	2-2	3-2	3-3	3-4	3-5	4-3	4-4	4-5	
> 58,000	56,000	0.6144	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
58,000 to 61,999	60,000	0.8348	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
62,000 to 65,999	64,000	1.1138	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
66,000 to 69,999	68,000	1.4623	0	0	0	0	0	0	0	0	0	20	0	0	14	0	49.72
70,000 to 73,999	72,000	1.8921	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
74,000 to 77,999	76,000	2.4166	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
78,000 +	-	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00
Subtotal Total:																49.72	

Quint-Axle

Total Axle Load (pounds)	Representative Axle Load	Equivalency Factor	Estimated Number of Quint-Axles															Total EALF's
			SU-1	SU-2	2-S1	2-S2	3-S2	2-1	2-2	3-2	3-3	3-4	3-5	4-3	4-4	4-5		
> 68,000	64,000	0.4586	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
68,000 to 73,999	70,000	0.6808	0	0	0	0	0	0	0	0	0	0	12	0	0	0	8.17	
72,000 to 75,999	74,000	0.8714	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
76,000 to 79,999	78,000	1.1020	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
80,000 to 83,999	82,000	1.3787	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
84,000 to 87,999	86,000	1.7079	0	0	0	0	0	0	0	0	0	0	0	0	0	12	20.49	
88,000 +	-	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.00	
Subtotal Total:																	28.66	

Total EALF's per Well Phase During Development Phase: 2,425.68

Total EALF's per Well Phase to be Used During Well Development Phase: 2,430.00

Single Axle

Tandem Axle

Tri-Axle

Quad-Axle

Quad-Axis	
	Total Axes

Quint-Axle

Total EALF's per Well Phase to be Used During Annual Production Phase: 1,250.00

APPENDIX G



APPENDIX G

20-Year Projection of EALF Demand

	Normal EALF Demand	Well EALF Demand																				Annual EALF Demand	Cumulative EALF Demand
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20		
Year 1	500	2,430	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2,930	2,930	
Year 2	500	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4,180	7,110	
Year 3	500	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5,430	12,540	
Year 4	500	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	6,680	19,220	
Year 5	500	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	-	-	-	7,930	27,150	
Year 6	500	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	-	-	9,180	36,330	
Year 7	500	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	-	10,430	46,760	
Year 8	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	-	11,680	58,440	
Year 9	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	-	12,930	71,370	
Year 10	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	-	14,180	85,550	
Year 11	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	-	15,430	100,980	
Year 12	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	-	16,680	117,660	
Year 13	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	-	17,930	135,590	
Year 14	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	-	19,180	154,770	
Year 15	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	-	20,430	175,200	
Year 16	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	-	21,680	196,880	
Year 17	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	-	22,930	219,810	
Year 18	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	-	24,180	243,990	
Year 19	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	25,430	269,420	
Year 20	500	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	1,250	2,430	26,680	296,100

APPENDIX H



APPENDIX H
Proposed Road Classification
for the Eagle Ford Shale Play
West of US Highway 77A and West of State Highway 72

Road Rank	Road Name	County Road Number	Road Type Classification *		
			A	B	C
W001	Bellevue Cemetery Road	147			X
W002	Cheapside Road	148			X
W003	Smith Ranch Road	122			X
W004	Catholic Church Lane	138			X
W005	Cabeza Highway	324			X
W006	C W Gabler Road	345			X
W007	Hartman Road	130			X
W008	Garfield Road	317			X
W009	Dubose Ranch Road	399			X
W010	Boldt Road	129			X
W011	Rogge-Seifert Road	358			X
W012	Concrete & Edgar Road	242			X
W013	Jaeger Road	3011			X
W014	McCurdy Road	154			X
W016	Braden Road	168			X
W015	Biemer Road	463			X
W017	Metting School Road	3464			X
W018	Barnhart Ranch Road	165		X	
W019	Ryan Ranch Road	376			X
W020	Simecek Road	392			X
W021	Kubala Store Road	397			X
W022	Hilbrich Road	145		X	
W023	Lindenau Road	157		X	
W024	Schendel Road	350		X	
W025	Salt Creek Cemetery Road	3014			X
W026	Kozelski Road	112		X	
W027	Elder Road	116		X	
W028	A. Hahn Road	144		X	
W029	Stanley Dworaczyk Road	339		X	
W030	Alfred Blaschke Road	374			X
W031	Cottonpatch Road	341		X	
W032	Dagg Road	219			X
W033	Simpson Ranch Road	323			X

Road Rank	Road Name	County Road Number	Road Type Classification *		
			A	B	C
W109	Berkenhoff Road	340		X	
W110	Ckodore Road	352		X	
W111	Rathkamp Lane	225		X	
W112	Lincke Road	396		X	
W113	Emil Meyer Road	3020		X	
W114	Sievert Pit Road	146		X	
W115	Westhoff Cemetery Road	136		X	
W116	Heider Road	-		X	
W117	Ed Blackwell Road	124		X	
W118	Gerdes Road	226		X	
W119	Gus Meyer Road	3012		X	
W120	Walter Mueller Road	3002		X	
W121	A Metting Road	3006		X	
W122	Schneider Ranch Road	365		X	
W123	Vahalik Road	221		X	
W124	Zimmerman Road	117		X	
W125	Seidel Road	141		X	
W126	Morris School Road	201		X	
W127	Frank Hinojosa Road	355		X	
W128	Lockhart Cemetery Road	160		X	
W129	Woods Cemetery Road	3478		X	
W130	Rosie Dunn Road	153		X	
W131	Sam Morris Road	127		X	
W132	Schultz Road	304		X	
W133	Seiler Road	362		X	
W134	Green Cemetery Road	247		X	
W135	Schmidt Road	229		X	
W136	Nelson Road	222		X	
W137	Gerhold Road	289		X	
W138	Lackey Ranch Road	343	X		
W139	Scheffler Road	325	X		
W140	H Harms Road	378	X		
W141	Respondek Road	-	X		

Road Rank	Road Name	County Road Number	Road Type Classification *		
			A	B	C
W034	Lackey Lane	125		X	
W035	Spies Road	388		X	
W036	Morris Community Road	200			X
W037	George Klein Road	344		X	
W038	Pargmann Road	203		X	
W039	Old Gonzales Road	108		X	
W040	Brown Road	245		X	
W041	Arndt Road	139		X	
W042	Herman Road	237		X	
W043	Hannessee	246		X	
W044	Dreyer-Turkey Bottom Road	230		X	
W045	Wofford Lane	162		X	
W046	Hrabovsky Road	215		X	
W047	Gruenau Road	305		X	
W048	E. Swartz Road	3457		X	
W049	Gohlke School Road	393		X	
W050	Hattenbach Road	3009		X	
W051	Von Haefen Road	119		X	
W052	Emil Blank Road	205		X	
W053	Old Davy Road	3015		X	
W054	Immenhauser Road	207		X	
W055	Schulle Road	143		X	
W056	Lone Tree Road	224		X	
W057	Hy Koopmann Road	3019		X	
W058	Martinez Road	227		X	
W059	Noe Hinojosa Road	351		X	
W060	Robert Meischen Road	346		X	
W061	Frels Road	241		X	
W062	Coskey Ranch Road	377		X	
W063	Williams Road	-		X	
W064	Frank Kozielski Road	318		X	
W065	Bootlegger Road	202		X	
W066	Wischkaemper Road	3010		X	
W067	Scheffler Road	357		X	
W068	Czaja Bros Road	3018		X	
W069	Romeo Korth Road	349		X	
W070	Wuench Road	389		X	
W071	Matejek Road	398		X	
W072	Nathan Mueller Road	337		X	
W073	Nolte-Boehl Road	132		X	

Road Rank	Road Name	County Road Number	Road Type Classification *		
			A	B	C
W142	Allen Lane	204	X		
W143	Haase Brothers Road	394	X		
W144	City of Hochheim Road	234	X		
W145	Plasczyk Road	3016	X		
W146	Guilford School Road	-	X		
W147	Ben Meischen Road	338	X		
W148	Interstate 13 Road	3013	X		
W149	Boehm Road	156	X		
W150	S. A. Butler Road	322	X		
W151	Muschalek Road	347	X		
W152	Edmund Mueller Road	359	X		
W153	Edna Hattenbach Road	135	X		
W154	K Thiele Road	220	X		
W155	Willie Blank Road	205	X		
W156	Pete Jablonski Road	3465	X		
W157	Chaddock Road	131	X		
W158	Center School Road	287	X		
W159	Blackwell Lane	121	X		
W160	Old San Antonio Road	-	X		
W161	Howard Weise Road	335	X		
W162	St. John School Road	126	X		
W163	Sandy Gate 2 Road	3007	X		
W164	Sandy Gate Road	3005	X		
W165	McElroy Road	239	X		
W166	Johnny Pokluda Road	321	X		
W167	Musselman Road	235	X		
W168	Ward Road	238	X		
W169	Sweet Potato Road	364	X		
W170	Blake Road	307	X		
W171	Schuenemann Road	379	X		
W172	Chilek Road	232	X		
W173	Onken Road	375	X		
W174	Crestview Road	301	X		
W175	Dieringer Road	290	X		
W176	Edwin Schroeder Road	390	X		
W177	Hells Gate Road	167	X		
W178	Buckhorn Road	371	X		
W179	Anderson Avenue	-	X		
W180	Warzecha Lane	-	X		
W181	Bluebonnet Lane	217	X		

Road Rank	Road Name	County Road Number	Road Type Classification *		
			A	B	C
W074	Hules Road	208		X	
W075	Herder Road	212		X	
W076	Stanchos Road	391		X	
W077	Meyer Road	142		X	
W078	Little McGehee Road	243		X	
W079	Henry Blank Road	231		X	
W080	Hoehne Road	166		X	
W081	Leo Nelson Road	3017		X	
W082	Larry Vasbinder Road	320		X	
W083	Rothkamp & Dreyer Road	223		X	
W084	Elroyce Helmers Road	356		X	
W085	Bill Lemke Road	334		X	
W086	Steen Road	155		X	
W087	Shows Brothers Road	353		X	
W088	Nessel Road	164		X	
W089	Sinclair Road	158		X	
W090	Thieme Road	360		X	
W091	Maron Road	361		X	
W092	Davy Road	-		X	
W093	Harvey Hahn Road	3041		X	
W094	Old Cheapside Road	163		X	
W095	Baker Road	3001		X	
W096	Roeder Ranch Road	342		X	
W097	Bramlette Road	244		X	
W098	Schlenstedt Road	137		X	
W099	Wild Road	159		X	
W100	Thiele Road	-		X	
W101	Sunday Lane	336		X	
W102	VFW Road	303		X	
W103	Richter Road	209		X	
W104	Whitley Road	236		X	
W105	Jackson Road	395		X	
W106	Robert Meischen Road	319		X	
W107	Morgan Road	-		X	
W108	Mueller Road	106		X	

Road Rank	Road Name	County Road Number	Road Type Classification *		
			A	B	C
W182	Mann Road	332	X		
W183	Arndt Bypass Road	-	X		
W184	Auction Ring Road	171	X		
W185	6th Street	314	X		
W186	7th Street	-	X		
W187	8th Street	315	X		
W188	8th Street	3462	X		
W189	Bunjus Road	-	X		
W190	Carter Road	-	X		
W191	Cook Road	-	X		
W192	Cottonwood Road	-	X		
W193	Crain Road	-	X		
W194	Elizabeth Street	-	X		
W195	Fay Avenue	-	X		
W196	Flato Street	-	X		
W197	Hochheim Cemetery Road	-	X		
W198	Houston Street	-	X		
W199	Isdale Road	216	X		
W200	Lane Avenue	-	X		
W201	Lee Avenue	-	X		
W202	Lynch Road	-	X		
W203	Main Street	-	X		
W204	Mesquite Lane	-	X		
W205	Mockingbird	-	X		
W206	Mulberry Road	-	X		
W207	Naranjo Road	-	X		
W208	Oliver Road	-	X		
W209	Petru Road	218	X		
W210	Procter Road	-	X		
W211	Railroad Street	-	X		
W212	River Ridge Road	-	X		
W213	Schleicher Road	-	X		
W214	Van Vleck	-	X		
W215	Westside Cemetery Road	316	X		
W216	Yorktown Heights	313	X		

* The classification is a recommendation and a traffic study and further analysis of the traffic should be completed prior to final design.

SUPPLEMENTAL APPENDIX 1



Supplemental Appendix 1
Rig-Up and Rig-Down Information from the Texas Department of Motor Vehicles Data

Description	Height	Length	Width	GVW	Axle			Axle			Axle			Axle			Axle			Axle			Axle			Axle			Unit Total EALF
					weight	Spacing	weight	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing		
FUEL TANK	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424		
FLOOR HOUSE	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	4'	17,077	4'	17,077	4'	17,077										4.4424		
GENERATOR	16'	85'	13'	118,700	14,300 0.3567	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750										3.9881		
B.O.P. HANDLER	16'	85'	13'	118,700	14,300 0.3567	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750										3.9881		
SUBSTRUCTURE	16'	95'	13'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679		
MUD PUMP	16'	85'	13'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679		
MUD TANK	16'	85'	13'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077								5.0771		
MUD PUMP	16'	85'	13'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077								5.0771		
MUD TANK	16'	85'	13'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077								5.0771		
MCC HOUSE	16'	85'	13'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077								5.0771		
GENERATOR	16'	85'	13'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652								3.7834		
TRIP TANK	16'	85'	13'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652								3.7834		
GAS COMPRESSOR	13'6"	105'	12'10"	187,700	14,300 0.3567	19'	23,000	4'	23,000	14'	23,000	4'	23,000	40'	16,280	4'	16,280	4'	16,280	5'	16,280	4'	16,280				10.0843		
UTILITY SKID	16'	85'	13'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679		
CENTER SUBSTRUCTURE	16'	85'	13'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077								5.0771		
BUNK HOUSE	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077									4.4424			
CREW HOUSE	16'	95'	14'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679		
SUBSTRUCTURE	16'	95'	13'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679		
B.O.P. HANDLER	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077									4.4424			
H.P.U. UNIT	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077									4.4424			
RAMP	14'	85'	14'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.4424			
SHELL SHAKER	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077									5.0771			
DERRICK	16'	95'	15'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077									4.4424			
Total				3,178,149	0.3567				2.5934						1.4923												4.4424		
																										105.526769			

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				2.1276
					0.1971			1.0972					0.8332											
DERRICK	EALF	16'	85'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
					0.3567			1.6576					1.6576											
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				2.1276
					0.1971			1.0972					0.8332											
FUEL TANK	EALF	15'	85'	10'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934					1.4923											
BUNKHOUSE	EALF	15'	85'	13'11"	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934					1.4923											
GENERATOR	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
SHAKER SKID	EALF	16'	85'	14'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
GENERATOR	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
KOOMEY UNIT	EALF	15'	85'	12'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
GENERATOR	EALF	16'	85'	12'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
RAMP	EALF	14'	85'	14'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
SCR HOUSE	EALF	16'	85'	12'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934					1.4923											
FLOOR HOUSE	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934					1.4923											
MUD TANK	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
					0.3567			2.5934					0.8332											
SUBSTRUCTURE	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
					0.3567			2.5934					0.8332											
MUD TANK	EALF	16'	85'	13'11"	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
MUD PUMP	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
MUD PUMP	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
CREW HOUSE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
WATER TANK	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
HPU UNIT	EALF	16'	85'	12'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
TRIP TANK	EALF	16'	85'	13'	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750				3.0523
					0.3567			1.6576					1.0380											
DRAWWORK	EALF	16'	85'	14'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
					0.3567			1.6576					1.6576											
Total					3,126,116																			93.8197047

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	2.1276
					0.1971			1.0972					0.8332												
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	2.1276
					0.1971			1.0972					0.8332												
DERRICK	EALF	16'	95'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000	4'	18,000	4'	18,000	4'	18,000	3.6719
					0.3567			1.6576					1.6576												
FUEL TANK	EALF	16'	85'	12'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
					0.3567			2.5934					1.4923												
GENERATOR	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
					0.3567			2.5934					1.0380												
GENERATOR	EALF	16'	85'	12'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
					0.3567			2.5934					1.0380												
GENERATOR	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
					0.3567			2.5934					1.0380												
SCR HOUSE	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5.0771
					1.9272			1.6576					1.4923												
MUD TANK	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	3.7834
					0.3567			2.5934					0.8332												
MUD TANK	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	3.7834
					0.3567			2.5934					0.8332												
MUD PUMP	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
MUD PUMP	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
WATER TANK	EALF	16'	85'	13'	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.0523
					0.3567			1.6576					1.0380												
SHAKER SKID	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5.0771
					1.9272			1.6576					1.4923												
TRIP TANK	EALF	16'	85'	14'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
					0.3567			2.5934					1.0380												
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
CENTER SUBSTRUCTURE	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	3.7834
					0.3567			2.5934					0.8332												
TOP HOUSE	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
					0.3567			2.5934					1.4923												
UTILITY SKID	EALF	16'	85'	14'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
					0.3567			2.5934					1.0380												
HPU UNIT	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	4'	17,077	4'	17,077	4'	17,077	4'	17,077	4'	17,077	4'	17,077	4.4424
					0.3567			2.5934					1.4923												
RAMP	EALF	14'	85'	14'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
					0.3567			2.5934					1.0380												
BOP SKID	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5.0771
					1.9272			1.6576					1.4923												
DRAWWORK	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5.0771
					1.9272			1.6576					1.4923												
BUNKHOUSE	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
					0.3567			2.5934					1.4923												
CREW HOUSE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
BOP HANDLER	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	3.7834
					0.3567			2.5934					0.8332												
MCC HOUSE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
DERRICK	EALF	16'	95'	15'	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.0523
					0.3567			1.6576					1.0380												
SUBSTRUCTURE	EALF	16'	95'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
					0.3567			1.6576					1.6536												
Total					3,997,199																				116.847788

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
FUEL TANK	16'	85'	10'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
GENERATOR	EALF	16'	85'	12'	130,508	20,800 1.9272	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								6.0130
GENERATOR	EALF	16'	85'	13'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						5.0771
GENERATOR	EALF	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424
SCR HOUSE	EALF	16'	85'	12'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						5.0771
MUD TANK	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
MUD TANK	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
MUD PUMP	EALF	16'	85'	14'	141,085	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077						4.6038
MUD PUMP	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				3.6679
WATER TANK	EALF	16'	85'	13'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424
SHAKER SKID	EALF	16'	85'	14'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						5.0771
TRIP TANK	EALF	16'	85'	14'	130,508	20,800 1.9272	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								6.0130
SUBSTRUCTURE	EALF	16'	85'	14'	141,085	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077						4.6038
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				3.6679
CENTER SUBSTRUCTURE	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
TOP HOUSE	EALF	16'	85'	14'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424
UTILITY SKID	EALF	16'	85'	14'	136,608	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.5066
RAMP	EALF	14'	85'	14'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
BOP SKID	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
DRAWWORK	EALF	16'	85'	14'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424
BUNKHOUSE	EALF	16'	85'	14'	124,008	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424
CREW HOUSE	EALF	16'	85'	14'	141,085	14,300 0.3567	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077						4.6038
BOP HANDLER	EALF	16'	85'	14'	143,108	20,800 1.9272	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						5.0771
MCC HOUSE	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				3.6679
DERRICK	EALF	16'	95'	15'	122,300	14,300 0.3567	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000								3.6719
DERRICK	EALF	16'	85'	15'	113,300	14,300 0.3567	17'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750										2.7703
Total				3,478,814																						112.66983

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
FUEL TANK	EALF	15'	85'	13'	124,008	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	17,077 1.4923	5'	17,077 1.4923	5'	17,077	5'	17,077									4.4424
GENERATOR	EALF	16'	85'	13'	130,508	20,800 1.9272	17'	20,700 2.5934	4'	20,700	32'	17,077 1.4923	5'	17,077 1.4923	5'	17,077	5'	17,077									6.0130
GENERATOR	EALF	16'	85'	13'	147,050	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	15,750 1.1502	4'	15,750	4'	15,750	4'	15,750	4'	15,750					3.1645
GENERATOR	EALF	16'	85'	13'	128,960	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	14,652 0.8332	4'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652							3.7834
SCR HOUSE	EALF	16'	85'	13'	153,685	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.6679
MUD TANK	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	14,652 0.8332	4'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652							3.7834
MUD TANK	EALF	16'	85'	14'	141,560	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.8476
MUD PUMP	EALF	16'	85'	14'	141,085	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	17,077 1.6536	5'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077							4.6038
MUD PUMP	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.6679
SHAKER SKID	EALF	16'	85'	14'	124,008	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	17,077 1.4923	5'	17,077 1.4923	5'	17,077	5'	17,077									4.4424
SUBSTRUCTURE	EALF	16'	85'	14'	141,085	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	17,077 1.6536	5'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077							4.6038
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.6679
CENTER SUBSTRUCTURE	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	14,652 0.8332	4'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652							3.7834
TOP HOUSE	EALF	16'	85'	14'	124,008	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	17,077 1.4923	5'	17,077 1.4923	5'	17,077	5'	17,077									4.4424
HPU UNIT	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	14,652 0.8332	4'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652							3.7834
RAMP	EALF	14'	85'	14'	128,960	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	14,652 0.8332	4'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652							3.7834
BOP SKID	EALF	16'	85'	14'	128,960	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	14,652 0.8332	4'	14,652 0.8332	4'	14,652	4'	14,652	4'	14,652							3.7834
DRAWWORK	EALF	16'	85'	13'	130,508	20,800 1.9272	17'	20,700 2.5934	4'	20,700	32'	17,077 1.4923	5'	17,077 1.4923	5'	17,077	5'	17,077									6.0130
BUNKHOUSE	EALF	16'	85'	14'	141,085	14,300 0.3567	17'	20,700 2.5934	4'	20,700	32'	17,077 1.6536	5'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077							4.6038
CREW HOUSE	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.6679
BOP HANDLER	EALF	16'	85'	14'	130,508	20,800 1.9272	17'	20,700 2.5934	4'	20,700	32'	17,077 1.4923	5'	17,077 1.4923	5'	17,077	5'	17,077									6.0130
MCC HOUSE	EALF	16'	85'	14'	153,685	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.6536	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.6679
DERRICK	EALF	16'	95'	15'	122,300	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	18,000 1.6576	4'	18,000	4'	18,000									3.6719
DERRICK	EALF	16'	95'	15'	131,300	14,300 0.3567	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	15,750 1.0380	4'	15,750	4'	15,750	4'	15,750							3.0523
DERRICK	EALF	16'	95'	15'	125,200	20,800 1.9272	17'	20,700 2.5934	4'	20,700	32'	15,750 1.0380	4'	15,750 1.0380	4'	15,750	4'	15,750									5.5586
CRADDEL	EALF	14'	85'	14'	143,108	20,800 1.9272	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.4923	5'	17,077	5'	17,077	5'	17,077							5.0771
DERRICK BOARD	EALF	14'	85'	14'	143,108	20,800 1.9272	14'	18,000 1.6576	4'	18,000	4'	18,000	32'	17,077 1.4923	5'	17,077	5'	17,077	5'	17,077							5.0771
Total					3,682,614																					114.666587	

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
Fuel Tank	EALF	15'	85'	10'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
					0.3567			2.5934					0.8332											
FUEL TANK	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934					1.4923											
FUEL TANK	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934					1.4923											
Trip Tank	EALF	16'	85'	13'	118,608	14,300	17'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.2246
					0.3567			1.3755					1.4923											
HPU	EALF	16'	85'	13'	118,608	14,300	17'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.2246
					0.3567			1.3755					1.4923											
Bunk House	EALF	16'	85'	13'	118,608	14,300	17'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.2246
					0.3567			1.3755					1.4923											
Generator	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
Mud Tank	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
Ramp	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
B.O.P. Handler	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
SCR	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
Floor House	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
B.O.P.	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576					1.4923											
Derrick	EALF	16'	95'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
					0.3567			1.6576					1.6576											
Derrick	EALF	16'	95'	15'	113,300	14,300	17'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750						2.7703
					0.3567			1.3755					1.0380											
Center Substructure	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
					0.3567			2.5934					0.8332											
Generator	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
Shaker Skid	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
Utility Skid	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
Drawworks	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934					1.0380											
Mud Tank	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
					0.3567			2.5934					0.8332											
Mud Pump	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
Substructure	EALF	16'	95'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
MCC	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
Mud Pump	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
Substructure	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
Crew house	EALF	16'	95'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576					1.6536											
Total					3,624,986																			109.850843

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
FUEL TANK	16'	85'	12'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
GENERATOR	16'	85'	13'	141,560	14,300	14'	18,000	4'	18,000	4'	18,000	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652			2.8476
GENERATOR	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
GENERATOR	16'	85'	13'	130,508	20,800	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							6.0130
SCR HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
MUD TANK	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
MUD TANK	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
MUD PUMP	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
MUD PUMP	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
SHAKER SKID	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
SUBSTRUCTURE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
SUBSTRUCTURE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
CENTER SUBSTRUCTURE	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
TOP HOUSE	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
HPU UNIT	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
RAMP	14'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
BOP SKID	15'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
BUNKHOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
CREW HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
BOP HANDLER	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
MCC HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
DERRICK	16'	95'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000							3.6719
DERRICK	16'	95'	15'	125,200	20,800	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750							5.5586
SCR HOUSE	16'	85'	14'	141,085	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
MUD PUMP	16'	85'	14'	141,085	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
SUBSTRUCTURE	16'	85'	14'	141,085	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
BUNKHOUSE	16'	85'	14'	141,085	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
CREW HOUSE	16'	85'	14'	141,085	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
Total				4,001,038																				123.6231

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
GENERATOR	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
GENERATOR	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
GENERATOR	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
SCR HOUSE	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
MUD TANK	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576										1.6536							
MUD TANK	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576										1.6536							
MUD PUMP	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576										1.6536							
MUD PUMP	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576										1.6536							
SHAKER SKID	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
TRIP TANK	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
SUBSTRUCTURE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576										1.6536							
SUBSTRUCTURE	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
RAMP	14'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
DERRICK	16'	85'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000							3.6719
	EALF				0.3567		1.6576									1.6576								
CREW HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576										1.6536							
FORKLIFT	15'6"	85'	10'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
Total				2,031,166																				65.2071289

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
GENERATOR	EALF	16'	85'	13'	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750						3.0523
					0.3567			1.6576						1.0380										
DERRICK CROWN	EALF	15'	95'	14'	122,300	14,300	17'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
					0.3567			1.6576						1.6576										
MUD PUMP	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
SUBSTRUCTURE	EALF	16'	95'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
HYDRAULIC UNIT	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
CREW HOUSE	EALF	15'8"	95'	14'3"	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
DIESEL TANK	EALF	15'6"	85'	9'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934						1.4923										
TOP HOUSE	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934						1.4923										
PUSHER HOUSE	EALF	15'6"	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
					0.3567			2.5934						1.4923										
GENERATOR	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934						1.0380										
UTILITY SKID	EALF	15'4"	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934						1.0380										
DRAWWORKS	EALF	15'6"	85'	12'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934						1.0380										
SCR HOUSE	EALF	16'	85'	11'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576						1.4923										
SHAKER SKID	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576						1.4923										
B.O.P SKID	EALF	16'	85'	13'5"	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
					1.9272			1.6576						1.4923										
SUCTION TANK	EALF	16'	90'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
					0.3567			2.5934						0.8332										
gas buster	EALF	16'	95'	12'	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				4.6038
					0.3567			2.5934						1.6536										
rig house	EALF	14'	95'	12'6"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				4.6038
					0.3567			2.5934						1.6536										
CENTER SUBSTRUCTURE	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
					0.3567			2.5934						0.8332										
RAMP	EALF	14'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
					0.3567			2.5934						0.8332										
GENERATOR	EALF	16'	85'	12'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934						1.0380										
TRIP TANK	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934						1.0380										
B.O.P HANDLER	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
					0.3567			2.5934						1.0380										
SHAKER TANK	EALF	16'	85'	13'5"	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
MUD PUMP	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
MCC HOUSE	EALF	16'	85'	13'5"	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
SUBSTRUCTURE	EALF	16'	95'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
					0.3567			1.6576						1.6536										
BACK DERRICK SECTION	EALF	16'	95'	14'	125,200	20,800	14'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						5.5586
					1.9272			2.5934						1.0380										
GENERATOR	EALF	16'	85'	12'	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750				3.0523
					0.3567			1.6576						1.0380										
UTILITY SKID	EALF	15'6"	85'	13'	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750				3.0523
					0.3567			1.6576						1.0380										
DRAWWORKS	EALF	15'4"	85'	13'5"	131,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750				3.0523
					0.3567			1.6576						1.0380										
Total					4,184,778																			123.828297

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
FUEL TANK	16'	85'	10'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
GENERATOR	16'	85'	13'	118,700	14,300	17"	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
GENERATOR	16'	85'	13'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
GENERATOR	16'	85'	13'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
SCR HOUSE	16'	85'	14'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
MUD TANK	16'	85'	14'	128,960	14,300	17"	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					3.7834
MUD TANK	16'	85'	14'	141,560	14,300	14'	18,000	4'	18,000	4'	18,000	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652			2.8476
MUD PUMP	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
MUD PUMP	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
TRIP TANK	16'	85'	14'	118,700	14,300	17"	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
SUBSTRUCTURE	16'	95'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
SUBSTRUCTURE	16'	95'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
CENTER SUBSTRUCTURE	16'	85'	14'	128,960	14,300	17"	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					3.7834
TOP HOUSE	16'	85'	14'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
UTILITY SKID	16'	85'	14'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
HPU UNIT	16'	85'	14'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
RAMP	14'	85'	14'	128,960	14,300	17"	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					3.7834
BOP SKID	15'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
DRAWWORK	15'	85'	14'	141,560	14,300	14'	18,000	4'	18,000	4'	18,000	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652			2.8476
BUNKHOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
CREW HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
BOP HANDLER	16'	85'	14'	124,008	14,300	17"	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
MCC HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
DERRICK	16'	95'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000							3.6719
DERRICK	16'	95'	15'	118,700	14,300	17"	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
MCC HOUSE	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077					5.0771
CREW HOUSE	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Total				3,656,160																				107.718766

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
Generator	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
Fuel Tank	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
Floor House	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
Generator	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
Ramp	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
Shaker Tank	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
Change House	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
Suction Tank	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
Koomey Unit	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
Trip Tank	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
Water Tank	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Substructure	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Mud Pump	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Substructure	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Shaker Skid	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
Bunk House	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
SCR House	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
HPU Unit	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
Mud Pump	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Crew Quarters	EALF	16'	95'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
DERRICK	EALF	16'	85'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
GENERATOR	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
TRIP TANK	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
WATER TANK	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
FUEL TANK	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
CREW QUARTERS	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
MUD PUMP	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
FLOOR HOUSE	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
MUD PUMP	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
GENERATOR	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
RAMP	EALF	14'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652						3.7834
SUBSTRUCTURE	EALF	16'	85'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
SHAKER SKID	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
SHAKER TANK	EALF	16'	85'	14'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
CHANGE HOUSE	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
BUNKHOUSE	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
SCR HOUSE	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
SUCTION TANK	EALF	16'	85'	14'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
KOOMEY UNIT	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
HPU UNIT	EALF	16'	85'	14'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
DERRICK	EALF	16'	85'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
Total					5,617,628																			169.926991

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
CRANE	15'	110'	14'	220,375	19,500	14'	20,000	4'	20,000	4'	20,000	12'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	10.8665
Mud Tank	15'6"	80'	12'	155,175	14,300	16'	23,000	4'	23,000	28'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	7.2154
Mud Tank	15'6"	80'	12'	155,175	14,300	16'	23,000	4'	23,000	28'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	7.2154
compressor	14'	90'	14'10"	156,875	16,000	14'	23,000	5'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	7.4473
BUNK HOUSE	15'5"	105'	14'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	2.1276
BUNK HOUSE	15'5"	105'	14'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652	2.1276
SUBSTRUCTURE	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
SUBSTRUCTURE	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
DRAWWORKS	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
EMPTY MUD TANK	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
EMPTY MUD TANK	15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
MUD PUMP	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
MUD PUMP	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
S C R HOUSE	15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
OILFIELD UTILITY SKID	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
CREW HOUSE	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
PUSHER HOUSE	15'6"	100'	14'	136,200	14,300	17'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.9557
CROWN SECTION	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
DERRICK LEG	15'6"	100'	14'	120,300	14,300	17'	23,000	4'	23,000	35'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	7.1244
DERRICK LEG	15'6"	100'	14'	120,300	14,300	17'	23,000	4'	23,000	35'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	7.1244
SHALE SHAKER	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
CRANE	15'	110'	14'	220,375	19,500	14'	20,000	4'	20,000	4'	20,000	12'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	10.8665
Total				3,455,075																				144.870211

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
EMPTY MUD TANK	EALF	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975				6.4101
EMPTY MUD TANK	EALF	15'6"	100'	14'	136,200	14,300	17'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975								6.9557
MUD PUMP	EALF	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.6698
MUD PUMP	EALF	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.6698
DRAWWORKS	EALF	15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975				6.4101
SUBSTRUCTURE	EALF	15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.6698
RAMP	EALF	15'6"	100'	14'	136,200	14,300	17'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975						6.9557
DERRICK (IN TOW)	EALF	15'6"	100'	14'	134,300	14,300	14'	20,000	4'	20,000	4'	20,000	43'	20,000	4'	20,000	4'	20,000						5.4985
PUSHER HOUSE	EALF	15'6"	100'	14'	120,300	14,300	17'	23,000	4'	23,000	35'	20,000	5'	20,000	5'	20,000								7.1244
CREW HOUSE	EALF	15'6"	100'	14'	136,200	14,300	17'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975						6.9557
DERRICK (IN TOW)	EALF	15'6"	100'	14'	134,300	14,300	14'	20,000	4'	20,000	4'	20,000	43'	20,000	4'	20,000	4'	20,000						5.4985
PUSHER HOUSE	EALF	15'6"	100'	14'	120,300	14,300	17'	23,000	4'	23,000	35'	20,000	5'	20,000	5'	20,000								7.1244
CREW HOUSE	EALF	15'6"	100'	14'	136,200	14,300	17'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975						6.9557
Total				1,887,925																				85.8982

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
EMPTY MUD TANK		15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.4022													6.4101
EMPTY MUD TANK		15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.4022													6.4101
MUD PUMP		15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.6619													6.6698
SHALE SHAKER		15'6"	100'	14'	139,500	19,500	14'	20,000	4'	20,000	4'	20,000	35'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	
	EALF				1.4369			2.5709						2.5709													6.5787
DRAWWORKS		15'6"	100'	14'	134,300	14,300	14'	20,000	4'	20,000	4'	20,000	35'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	
	EALF				0.3567			2.5709						2.5709													5.4985
SUBSTRUCTURE		15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.6619													6.6698
DERRICK RAMP		15'6"	100'	14'	120,300	14,300	17'	23,000	4'	23,000	35'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	
	EALF				0.3567			4.1968						2.5709													7.1244
DERRICK (IN TOW)		15'6"	100'	14'	139,500	19,500	14'	20,000	4'	20,000	4'	20,000	43'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	
	EALF				1.4369			2.5709						2.5709													6.5787
S C R HOUSE		15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				0.3567			2.5709						2.4022													5.3299
OILFIELD UTILITY SKID		15'6"	100'	14'	155,400	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.4022													6.4101
OILFIELD UTILITY SKID		15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				0.3567			2.5709						2.4022													5.3299
OILFIELD UTILITY SKID		15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				0.3567			2.5709						2.4022													5.3299
PUSHER HOUSE		15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				0.3567			2.5709						2.4022													5.3299
CREW HOUSE		15'6"	100'	14'	150,200	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				0.3567			2.5709						2.4022													5.3299
MUD PUMP		15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.6619													6.6698
CRANE		15'	110'	14'	200,285	19,500	14'	18,000	4'	18,000	4'	18,000	12'	20,700	4'	20,700	35'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	
	EALF				1.4369			1.6576						2.5934													7.3416
MUD PUMP		15'6"	100'	14'	174,375	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
	EALF				1.4369			2.5709						2.6619													6.6698
Total					2,648,585																						105.68062

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
CRANE	EALF	15'6"	100'	14'	220,375	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	12'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	10.8665
SUBSTRUCTURE	EALF	15'6"	100'	14'	174,375	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
SUBSTRUCTURE	EALF	15'6"	100'	14'	155,400	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
MUD BOAT	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
GENERATOR MOTOR	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
GENERATOR MOTOR	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
GENERATOR MOTOR	EALF	15'6"	100'	14'	155,400	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
S C R HOUSE	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
EMPTY MUD TANK	EALF	15'6"	100'	14'	155,400	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
EMPTY MUD TANK	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
SHALE SHAKER	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
DERRICK (IN TOW)	EALF	15'6"	100'	14'	134,300	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	43'	20,000	4'	20,000	4'	20,000									5.4985
GAS BUSTER	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
MUD PUMP	EALF	15'6"	100'	14'	174,375	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
MUD PUMP	EALF	15'6"	100'	14'	174,375	19,500 1.4369	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
PUSHER HOUSE	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
CREW HOUSE	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
TOP DOG HOUSE	EALF	15'6"	100'	14'	150,200	14,300 0.3567	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
Total				2,846,000																						108.903282	

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
CRANE	15'	110'	14'	220,375	19,500	14'	20,000	4'	20,000	4'	20,000	12'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	10.8665
EMPTY MUD TANK	EALF	15'6"	100'	14'	155,400	1.4369	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
EMPTY MUD TANK	EALF	15'6"	100'	14'	150,200	1.4369	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
MUD PUMP	EALF	15'6"	100'	14'	174,375	0.3567	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
MUD PUMP	EALF	15'6"	100'	14'	174,375	1.4369	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
SHALE SHAKER SKID	EALF	15'6"	100'	14'	150,200	1.4369	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
DRAWWORKS	EALF	15'6"	100'	14'	136,200	0.3567	14,300	17'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.9557
SUBSTRUCTURE	EALF	15'6"	100'	14'	174,375	4.1968	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
DERRICK RAMP	EALF	15'6"	100'	14'	134,300	1.4369	14,300	14'	20,000	4'	20,000	4'	20,000	35'	20,000	5'	20,000	5'	20,000	5'	20,000	5'	20,000	5.4985
DERRICK (IN TOW)	EALF	15'6"	100'	14'	139,500	0.3567	19,500	14'	20,000	4'	20,000	4'	20,000	43'	20,000	4'	20,000	4'	20,000	4'	20,000	4'	20,000	6.5787
S C R HOUSE	EALF	15'6"	100'	14'	150,200	1.4369	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
OILFIELD UTILITY SKID	EALF	15'6"	100'	14'	155,400	0.3567	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
OILFIELD UTILITY SKID	EALF	15'6"	100'	14'	174,375	1.4369	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.6698
OILFIELD UTILITY SKID	EALF	15'6"	100'	14'	150,200	1.4369	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
PUSHER HOUSE	EALF	15'6"	100'	14'	155,400	0.3567	19,500	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.4101
CREW HOUSE	EALF	15'6"	100'	14'	150,200	1.4369	14,300	14'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.3299
Total				2,545,075	0.3567				2.5709					2.4022										102.4582

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
DERRICK	EALF	15'6"	125'	16'	172,875	18,000	12'	20,000	4'	20,000	4'	20,000	80'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.2328
MUDPUMP	EALF	15'6"	110'	14'	174,875	20,000	12'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
VFD HOUSE	EALF	15'6"	110'	14'	174,875	20,000	12'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
MUDTANK	EALF	15'6"	110'	14'	141,700	14,300	16'	23,000	4'	23,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	5.8875
SUBSUCTURE	EALF	15'6"	110'	14'	141,700	14,300	16'	23,000	4'	23,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	5.8875
TRIPTANK	EALF	15'6"	110'	14'	141,700	14,300	16'	23,000	4'	23,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	5.8875
DRILLERS HOUSE	EALF	15'6"	110'	14'	141,700	14,300	16'	23,000	4'	23,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	5.8875
GENERATOR	EALF	15'6"	110'	14'	130,300	14,300	16'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.2197
CREW HOUSE	EALF	15'6"	110'	14'	130,300	14,300	16'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.2197
MUDBOAT	EALF	15'6"	110'	14'	130,300	14,300	16'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.2197
FUELTANK	EALF	15'6"	110'	14'	130,300	14,300	16'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.2197
PUSHER HOUSE	EALF	15'6"	110'	14'	130,300	14,300	16'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.2197
GENERATOR	EALF	15'6"	110'	14'	130,300	14,300	16'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.2197
CRAWLER CRANE	EALF	14'	115'	13'6"	155,175	14,300	16'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	7.2154
CRAWLER CRANE	EALF	14'	115'	13'6"	199,800	14,300	16'	23,000	4'	23,000	14'	23,000	5'	23,000	35'	18,700	5'	18,700	5'	18,700	5'	18,700	5'	18,700	11.2418
CRAWLER CRANE	EALF	14'	115'	13'6"	155,175	14,300	16'	23,000	4'	23,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	7.2154
DERRICK	EALF	15'6"	110'	14'	161,400	20,000	12'	20,000	4'	20,000	4'	20,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	5.5170
GENERATOR	EALF	15'6"	110'	14'	155,700	14,300	12'	20,000	4'	20,000	4'	20,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4.2616
EMPTY STEEL TANK	EALF	15'6"	110'	14'	155,700	14,300	12'	20,000	4'	20,000	4'	20,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4.2616
SUBSTRUCTURE	EALF	15'6"	110'	14'	155,700	14,300	12'	20,000	4'	20,000	4'	20,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4.2616
VFD HOUSE	EALF	15'6"	110'	14'	155,700	14,300	12'	20,000	4'	20,000	4'	20,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4.2616
RIG HOUSE	EALF	15'6"	110'	14'	130,000	14,000	12'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.1877
MUD BOAT	EALF	15'6"	110'	14'	130,000	14,000	12'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.1877
RIG FLOOR	EALF	15'6"	110'	14'	130,000	14,000	12'	23,000	4'	23,000	35'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	4'	17,500	6.1877
SUBSTCTOR	EALF	15'6"	110'	14'	141,400	14,000	12'	23,000	4'	23,000	35'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	5.8555
Total	EALF				3,696,975																			153.4455	

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
mud pump	15'6"	110'	14'	199,400	14,000	12'	20,000	4'	20,000	4'	20,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	15'	22,000	4'	7.6540
	EALF				0.3247		2.5709						1.3340										3.4244		
Derrick	15'6"	110'	16'	199,400	14,000	12'	20,000	4'	20,000	4'	20,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280	15'	22,000	4'	7.6540
	EALF				0.3247		2.5709						1.3340										3.4244		
mud pump	15'6"	110'	14'	190,000	14,000	12'	20,000	4'	20,000	4'	20,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500	15'	23,000	4'	23,000		8.7586
	EALF				0.3247		2.5709						1.6662									4.1968			
substructure	15'6"	110'	14'	190,000	14,000	12'	20,000	4'	20,000	4'	20,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500	15'	23,000	4'	23,000		8.7586
	EALF				0.3247		2.5709						1.6662									4.1968			
Empty steel tank	15'10"	110'	14'	159,400	18,000	12'	20,000	4'	20,000	4'	20,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280				4.9049
	EALF				1.0000		2.5709						1.3340												
BOP handler	15'6"	100'	12'	159,400	18,000	12'	20,000	4'	20,000	4'	20,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280				4.9049
	EALF				1.0000		2.5709						1.3340												
substructure	15'6"	110'	14'	159,400	18,000	12'	20,000	4'	20,000	4'	20,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280				4.9049
	EALF				1.0000		2.5709						1.3340												
Empty steel tank	15'10"	110'	14'	141,700	14,300	15'	23,000	4'	23,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280						5.8875
	EALF				0.3567		4.1968						1.3340												
VFD house	15'6"	110'	14'	141,700	14,300	15'	23,000	4'	23,000	36'	16,280	4'	16,280	4'	16,280	4'	16,280	4'	16,280						5.8875
	EALF				0.3567		4.1968						1.3340												
center steel	15'	100'	14'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
Generator house	15'6"	100'	14'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
Generator house	15'6"	100'	14'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
trip tank (empty)	15'8"	100'	14'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
Bunk house	15'6"	100'	14'	136,200	14,300	15'	23,000	4'	23,000	36'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557
	EALF				0.3567		4.1968						2.4022												
Drillers cabin	15'6"	100'	14'	136,200	14,300	15'	23,000	4'	23,000	36'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557
	EALF				0.3567		4.1968						2.4022												
Crew house	15'6"	100'	14'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
mud boat	14'	100'	15'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
empty diesel tank	15'6"	100'	12'	130,300	14,300	15'	23,000	4'	23,000	36'	17,500	4'	17,500	4'	17,500	4'	17,500								6.2197
	EALF				0.3567		4.1968						1.6662												
crawler crane	14'	120'	14'	196,300	14,300	15'	23,000	4'	23,000	15'	23,000	4'	23,000	36'	18,000	5'	18,000	5'	18,000	5'	18,000	5'	18,000		10.8469
	EALF				0.3567		4.1968					4.1968					2.0967								
Total				2,921,200																					127.6111

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
mud tank	EALF	15'6"	110'	14'	169,175	14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
sub structure		14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
shaker	EALF	15'6"	110'	14'	136,200	14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975								5.5895	
motor house		14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975													
derrick	EALF	15'6"	110'	14'	136,200	14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557	
derrick		14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975													
center steel	EALF	15'6"	110'	14'	155,175	14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975						7.2154	
draw works		14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'		18,975
motor	EALF	15'6"	110'	14'	136,200	14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557	
motor		14,300	0.3567	23,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'		18,975
mud tank	EALF	15'6"	110'	14'	168,995	14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,795	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
shaker		14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975											
sub structure	EALF	15'6"	110'	14'	169,175	14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.9557
Derrick		14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975													
derrick	EALF	15'6"	110'	14'	136,200	14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557	
tank		14,300	0.3567	23,000	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077													
structure	EALF	15'	110'	14'	124,008	14,300	0.3567	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
crown		14,300	0.3567	20,700	4'	18,000	4'	18,000	35'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'		17,077
Generator	EALF	15'	110'	14'	141,085	14,300	0.3567	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077						4.9233	
Tandem		14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'		18,975
derrick	EALF	15'	110'	14'6"	169,175	14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
Tandem		14,300	0.3567	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975													
crane	EALF	14'6"	110'	12'	169,175	14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.9557
Total		14,300	0.3567	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	
Total					3,451,856																					138.512	

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
motor	EALF	15'	110'	12'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
motor	EALF	15'	110'	12'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
motor	EALF	15'	110'	12'	169,175	14,300	15'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
motor	EALF	15'	110'	12'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
motor	EALF	15'	110'	12'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
tank	EALF	15'	110'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
tank	EALF	15'	110'	14'	136,200	14,300	15'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557	
House	EALF	15'	100'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
House	EALF	15'	100'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
House	EALF	15'	100'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
House	EALF	15'	100'	14'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
House	EALF	15'	100'	14'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
motor	EALF	15'	110'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
Mud Cleaning Equipment	EALF	15'	100'	12'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
shaker	EALF	15'	110'	12'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
Crane	EALF	15'6"	100'	14'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
House	EALF	15'	100'	12'	123,986	14,300	15'	18,000	4'	18,000	4'	18,000	34'	18,562	5'	18,562	5'	18,562								3.8983	
Derrick	EALF	13'6"	110'	14'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
Crane	EALF	14'6"	110'	12'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
Substructure	EALF	15'	110'	12'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
center steel	EALF	13'6"	110'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
mud boat	EALF	13'6"	110'	14'6"	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
substructure	EALF	15'	110'	12'	136,200	14,300	15'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975								6.9557	
mud tank	EALF	15'	110'	14'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
shaker skid	EALF	15'	110'	10'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
substructure	EALF	15'	110'	10'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
substructure	EALF	15'	110'	10'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
rig house	EALF	15'6"	110'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
rig house	EALF	15'6"	110'	14'	153,700	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	3.6692
rig house	EALF	15'6"	110'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
mud pump	EALF	15'	110'	12'	153,700	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	3.6692
mud pump	EALF	15'	110'	12'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
rig tank	EALF	15'6"	110'	10'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
rig tank	EALF	15'6"	110'	10'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
rig tank	EALF	15'6"	110'	10'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
empty mud tank	EALF	15'6"	110'	14'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
crane	EALF	14'6"	110'	12'	169,175	14,300	15'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
derrick	EALF	15'	110'	13'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
derrick	EALF	15'	110'	13'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
derrick	EALF	15'	110'	13'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077								4.4424	
crane	EALF	14'6"	110'	12'	161,071	20,000	15'	18,562	4'	18,562	4'	18,562	35'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5.1497
Total				5,681,272																						178.0090	

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
crane	14'6"	110'	12'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
SHAKER	EALF	15'	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
MUD TANK	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	35'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
MUD TANK	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
MUD TANK	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
MOTOR SKID	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
MOTOR SKID	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
PUMP	EALF	15'	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
PUMP	EALF	15'	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
MOTOR SKID	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
MOTOR	EALF	15'	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
shaker	EALF	15'	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
rig house	EALF	15'	110'	14'	153,700	0.3567	14,300	15'	18,000	4'	18,000	34'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	3.6692
rig house	EALF	15'	110'	14'	153,700	0.3567	14,300	15'	18,000	4'	18,000	34'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	3.6692
house	EALF	15'	110'	14'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
Draw works	EALF	15'	110'	13'	159,400	1.6121	20,000	15'	18,000	4'	18,000	35'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	5'	17,080	4.9246
webbing	EALF	14'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
crane	EALF	14'6"	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
crown section	EALF	15'	110'	14'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
derrick	EALF	15'	110'	12'	153,685	0.3567	14,300	15'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
derrick	EALF	15'	110'	12'	124,008	0.3567	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.4424
crane	EALF	14'6"	110'	12'	169,175	0.3567	14,300	15'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
Total				3,135,212																				90.8460

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
crane	14'6"	110'	12'	153,685	14,300	15'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
Crane	EALF	14'6"	110'	153,685	0.3567		18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
structure	15'6"	110'	12'	136,200	14,300	15'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
structure	EALF	15'6"	110'	153,685	0.3567		23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
derrick	15'6"	110'	14'	174,875	20,000	15'	20,000	4'	20,000	4'	20,000	35'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
derrick	EALF	15'6"	110'	169,175	1.6121		20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
center steel	15'	110'	14'	136,200	14,300	15'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
draw works	EALF	10'	110'	136,200	0.3567		23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
mud boat	10'	110'	14'	169,175	14,300	15'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
tank	EALF	15'6"	110'	136,200	0.3567		23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
pump	15'6"	110'	14'	136,200	14,300	15'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
pump	EALF	15'6"	110'	136,200	0.3567		23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							6.9557
GENERATOR	14'6"	110'	12'	124,008	14,300	15'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
pump	EALF	14'	110'	153,685	0.3567		18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
crane	14'6"	110'	12'	169,175	14,300	15'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
crane	EALF	14'6"	110'	169,175	0.3567		20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	5.5895
Total				2,407,523																				90.0516

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
GAS BUSTER	16'	100'	12'	149,175	14,300	16'	20,000	5'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975					
	EALF				0.3567		2.2175						2.6619											5.2362
MOTOR	15'8"	110'	11'1"	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
FUEL TANK	14'	110'	8'6"	149,175	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975					
	EALF				0.3567		2.2175						2.6619											5.2362
VFD HOUSE	15'2"	110'	10'6"	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
MOTOR	15'8"	110'	11'1"	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
MUD PUMP	15'8"	110'	12'	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
SHACKER SKID	15'8"	110'	12'6"	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
MUD PUMP	15'8"	110'	12'	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
CENTER STEAL	15'4"	110'	13'8"	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
MCC HOUSE	16'	100'	13'4"	169,175	14,300	16'	20,000	5'	20,000	5'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
MUD TANK	15'8"	110'	12'6"	130,200	14,300	16'	20,000	5'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
MUD TANK	15'8"	110'	12'6"	130,200	14,300	16'	20,000	5'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
CENTER STEEL	15'4"	100'	13'8"	169,175	14,300	16'	20,000	5'	20,000	5'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
substructure	15'3"	110'	12'6"	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
substructure	15'3"	110'	12'6"	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
HPU UNIT	15'1"	110'	12'2"	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
JUNK BOX	14'	110'	12'	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
WATER TANK	14'	110'	12'	122,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							
	EALF				0.3567		2.2175						1.4623											4.0365
BUTT SECTION	14'8"	110'	14'	150,200	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975					
	EALF				0.3567		2.5709						2.4022											5.3299
CROWN SECTION	14'6"	110'	15'	111,225	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975									
	EALF				0.3567		2.2175						2.0648											4.6391
DRAW WORKS	14'	110'	12'	149,175	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975					
	EALF				0.3567		2.2175						2.6619											5.2362
PUSHER HOUSE	14'	110'	12'6"	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
BOP	13'8"	95'	14'	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
BOP HANDLER	15'7"	95'	13'	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
TOP HOUSE	15'10"	100'	12'6"	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
crew house	15'6"	110'	14'	169,175	14,300	16'	20,000	4'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			
	EALF				0.3567		2.5709						2.6619											5.5895
MUD BOAT	13'6"	95'	14'	130,200	14,300	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975							
	EALF				0.3567		2.2175						2.4022											4.9765
Total				3,955,200																				140.3512

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
																							EALF	
MOTOR	15'8"	95'	11'1"	122,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.0365
	EALF				0.3567		2.2175				1.4623													
MOTOR	15'8"	95'	11'1"	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
MOTOR	15'8"	95'	11'1"	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
vfd house	15'8"	95'	12'1"	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
gas buster	15'10"	95'	13'1"	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
Crawler crane	14'	120'	14'	196,000	14,000	15'	23,000	4'	23,000	15'	23,000	4'	23,000	36'	18,000	5'	18,000	5'	18,000	5'	18,000			10.8149
	EALF				0.3247		4.1968				4.1968													
mcc house	16'	110'	13'4"	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
mudd pump	15'8"	110'	12'	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
mudd pump	15'8"	110'	12'	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
mudd tank	15'8"	110'	12'6"	105,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000									3.8806
	EALF				0.3567		2.2175				1.3064													
mudd tank	15'8"	110'	12'6"	122,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000									4.0365
	EALF				0.3567		2.2175				1.4623													
sub	15'3"	110'	12'6"	139,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.1946
	EALF				0.3567		2.2175				1.6203													
drawworks	13'6"	95'	12'	105,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000									3.8806
	EALF				0.3567		2.2175				1.3064													
crown derrick	14'6"	110'	15'	105,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000									3.8806
	EALF				0.3567		2.2175				1.3064													
butt derrick	14'8"	110'	14'	103,250	14,300	16'	18,975	4'	18,975	34'	17,000	5'	17,000	5'	17,000									3.4095
	EALF				0.3567		1.7464				1.3064													
center steel	15'4"	110'	13'8"	122,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							4.0365
	EALF				0.3567		2.2175				1.4623													
bop	14'	95'	14'	105,300	14,300	16'	20,000	4'	20,000	34'	17,000	5'	17,000	5'	17,000									3.8806
	EALF				0.3567		2.2175				1.3064													
Total				2,201,750																				75.4132

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
motor	EALF	15'8"	110'	11'1"	105,531	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077								3.9055	
motor	EALF	15'8"	110'	11'1"	105,531	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077								3.9055	
motor	EALF	15'8"	110'	11'1"	105,531	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077								3.9055	
mud tank	EALF	15'8"	110'	12'6"	153,685	14,300 0.3567	16'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
mud pump	EALF	15'8"	110'	12'	153,685	14,300 0.3567	16'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
mud tank	EALF	15'8"	110'	12'6"	124,008	14,300 0.3567	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424	
mud pump	EALF	15'8"	110'	12'	141,085	14,300 0.3567	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				4.6038	
shaker skid	EALF	15'8"	110'	12'6"	124,008	14,300 0.3567	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424	
mcc house	EALF	16'	110'	13'4"	153,685	14,300 0.3567	16'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
vfd house	EALF	15'2"	110'	10'6"	124,008	14,300 0.3567	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424	
gas buster	EALF	16'	110'	12'	124,008	14,300 0.3567	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424	
H P U	EALF	15'1"	110'	12'2"	124,008	14,300 0.3567	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077								4.4424	
CENTER STEEL	EALF	15'4"	110'	13'8"	139,685	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				4.2279	
SUBSTRUCTURE	EALF	15'6"	110'	12'6"	159,685	14,300 0.3567	16'	20,000	4'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			4.5812
DRAW WORKS	EALF	13'6"	110'	12'	122,608	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077						4.0666	
substructure	EALF	15'3"	110'	12'6"	136,200	14,300 0.3567	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975						6.9557	
bop handler	EALF	15'7"	110'	13'	122,608	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077								4.0666	
TOP HOUSE	EALF	15'10"	110'	12'6"	139,685	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077				4.2279	
B O P	EALF	14'	110'	14'	122,608	14,300 0.3567	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077								4.0666	
BUTT SECTION	EALF	14'8"	110'	14'	130,200	14,300 0.3567	16'	20,000	4'	20,000	34'	18,975	5'	18,975	5'	18,975								4.9765	
CROWN SECTION	EALF	14'6"	110'	15'	117,225	14,300 0.3567	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975								6.6183	
MUDD BOAT	EALF	14'	110'	14'	136,200	14,300 0.3567	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975								6.9557	
crew house	EALF	14'6"	110'	14'	117,225	14,300 0.3567	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975								6.6183	
crew house	EALF	14'6"	110'	14'	119,300	14,300 0.3567	16'	17,000	4'	17,000	34'	14,200	5'	14,200	5'	14,200	5'	14,200						2.1448	
Total				3,102,002																				109.0422	

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
RIG HOUSE	14'6"	100'	14'	120,000	14,000	16'	16,000	4'	16,000	34'	14,800	5'	14,800	5'	14,800	5'	14,800	5'	14,800					2.0058
RIG HOUSE	15'	110'	14'	120,000	14,000	16'	17,000	4'	17,000	34'	14,400	5'	14,400	5'	14,400	5'	14,400	5'	14,400					2.1592
RIG HOUSE	15'	110'	14'	120,000	14,000	16'	17,000	4'	17,000	34'	14,400	5'	14,400	5'	14,400	5'	14,400	5'	14,400					2.1592
GAS BUSTER	16'	110'	14'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
MUD TANK	15'8"	110'	14'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
RIG HOUSE	15'6"	100'	14'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
MOTOR	15'6"	100'	12'	118,300	14,300	16'	18,000	4'	18,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							3.1945
MOTOR	15'6"	100'	12'	118,300	14,300	16'	18,000	4'	18,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							3.1945
FUEL TANK	15'6"	100'	12'	120,000	13,000	16'	17,000	4'	17,000	34'	14,600	5'	14,600	5'	14,600	5'	14,600	5'	14,600					2.1174
VFD HOUSE	15'6"	110'	12'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
RIG MOTOR	15'6"	110'	12'	120,000	14,300	16'	17,000	4'	17,000	34'	14,340	5'	14,340	5'	14,340	5'	14,340	5'	14,340					2.1770
MUDD PUMP	15'8"	110'	12'	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
MUDD PUMP	15'8"	110'	12'	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
MCC HOUSE	16'	110'	13'4"	157,385	18,000	16'	18,000	4'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			4.3112
B.O.P. HANDLER	15'6"	100'	14'	118,300	14,300	16'	18,000	4'	18,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000							3.1945
DRAW WORKS	13'6"	100'	12'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
SUBSTRUCTURE	15'3"	100'	12'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
SUBSTRUCTURE	15'3"	100'	12'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
CENTER STEEL	15'3"	100'	14'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
B.O.P. SKID	15'	100'	14'	120,000	14,000	16'	17,000	4'	17,000	34'	14,400	5'	14,400	5'	14,400	5'	14,400	5'	14,400					2.1592
SHAKER SKID	15'8"	110'	12'6"	122,308	14,000	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0346
BUTT SECTION	14'8"	110'	14'	122,308	14,000	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0346
CROWN SECTION	14'6"	110'	15'	105,531	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077									3.9055
MUDD BOAT	14'	110'	14'	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
HPU UNIT	15'1"	110'	12'2"	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
DRILL LINE	14'	110'	14'	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
gas buster	16'	95'	12'	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
rig house	14'	95'	12'6"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
MUDD TANK	15'8"	95'	12'6"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
MUDD TANK	15'8"	95'	12'6"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
MUDD PUMP	15'10"	95'	12'	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
MUDD PUMP	15'10"	95'	12'	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
RIG HOUSE	16'	95'	13'	155,175	14,300	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975					7.2154
MOTOR	15'9"	95'	11'1"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
MOTOR	15'9"	95'	11'1"	124,008	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
MOTOR	15'9"	95'	11'1"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
shaker skid	15'8"	95'	12'6"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
crown section	14'6"	95'	15'	106,931	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077									4.2813
bop	13'8"	95'	12'1"	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
SUBSTRUCTURE	15'6"	95'	14'	152,762	14,300	16'	18,000	4'	18,000	4'	17,077	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.5531
SUBSTRUCTURE	15'6"	95'	14'	135,685	14,300	16'	18,000	4'	18,000	4'	17,077	34'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3918
CENTER STEEL	15'6"	95'	14'	152,762	14,300	16'	18,000	4'	18,000	4'	17,077	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.5531
DRAWWORKS	15'6"	95'	14'	118,608	14,300	16'	18,000	4'	18,000	4'	17,077	34'	17,077	5'	17,077	5'	17,077							3.2307
MUD BOAT	15'	95'	14'	135,685	14,300	16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					3.3859
HPU UNIT	15'	95'	14'	119,685	14,300	16'	17,500	4'	17,500	34'	14,077	5'	14,077	5'	14,077	5'	14,077	5'	14,077					

Descripton	Height	Length	Width	GVW	Axle		Axle		Axle		Axle		Axle		Axle		Axle		Axle		Axle		Axle		Unit Total	
					weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing	weight	Spacing
DERRICK BUTT SECTION	EALF	15'	95'	14'	118,608	0.3567		1.2113						0.6976												2.2656
					14,300		16'	18,000	4'	18,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077								
	EALF					0.3567		1.3755						1.4923												3.2246
Total				6,097,096																						171.4550

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
																							EALF	
motor	15'8"	95'	11'1"	124,008	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
motor	15'8"	95'	11'1"	124,008	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.4424
	EALF				0.3567		2.5934						1.4923											
rig house	16'	110'	13'4"	160,000	14,300	16'	19,000	4'	19,000	4'	19,000	34'	17,740	5'	17,740	5'	17,740	5'	17,740	5'	17,740	5'	17,740	4.3962
	EALF				0.3567		2.0762								1.9633									
mud pump	15'6"	95'	12'6"	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
	EALF				0.3567		2.2175								1.6536									
mud pump	15'6"	95'	12'6"	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
	EALF				0.3567		2.2175								1.6536									
shaker skid	15'8"	110'	12'6"	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
	EALF				0.3567		2.2175								1.6536									
mudd tank (empty)	15'8"	110'	12'6"	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
mudd tank (empty)	15'8"	110'	12'6"	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
gas buster	16'	110'	12'	141,085	14,300	16'	20,700	4'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.6038
	EALF				0.3567		2.5934								1.6536									
B.O.P SKID	15'	110'	14'	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
HOUSE	15'	110'	14'	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
	EALF				0.3567		2.2175								1.6536									
HOUSE	16'	110'	14'	104,608	14,300	16'	2,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							2.0046
	EALF				0.3567		0.1556								1.4923									
HOUSE	16'	110'	14'	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
HPU UNIT	15'3"	110'	12'2"	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
sub	15'3"	110'	12'6"	155,175	14,300	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975					7.2154
	EALF				0.3567		4.1968								2.6619									
sub	15'3"	110'	12'6"	155,175	14,300	16'	23,000	4'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975					7.2154
	EALF				0.3567		4.1968								2.6619									
drawworks	15'3"	110'	12'6"	120,000	13,300	16'	16,000	4'	16,000	34'	14,700	5'	15,000	5'	15,000	5'	15,000	5'	15,000					1.9773
	EALF				0.2589		0.8097								0.9087									
center steel	15'4"	110'	13'8"	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
bop handler	15'9"	110'	13'	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
crown section of derrick	14'6"	95'	15'	105,531	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077									3.9055
	EALF				0.3567		2.2175								1.3312									
mudd boat	14'	110'	14'	139,685	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					4.2279
	EALF				0.3567		2.2175								1.6536									
butt section of derrick	14'8"	95'	14'	122,608	14,300	16'	20,000	4'	20,000	34'	17,077	5'	17,077	5'	17,077	5'	17,077							4.0666
	EALF				0.3567		2.2175								1.4923									
Total				2,868,879																				93.8750

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
EXCAVATOR	14'	75'	12'	150,500	14,000	14'	20,500	5'	20,500	5'	20,500	36'	18,750	5'	18,750	5'	18,750	5'	18,750					5.4504
Pump	EALF	15'	98'	12'	153,685	0.3247	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Substructure	EALF	15'	98'	12'	153,685	0.3567	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Shaker	EALF	15'	98'	12'	153,685	0.3567	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
SCR House	EALF	15'	90'	12'	131,300	0.3567	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
Drillers Cabin	EALF	15'	90'	12'	131,300	0.3567	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
Derrick	EALF	15'	87'	13'6"	118,700	0.3567	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Drawworks	EALF	15'	87'	13'6"	118,700	0.3567	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Mud Tank	EALF	15'	87'	12'	118,700	0.3567	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Mud Boat	EALF	15'	87'	12'	118,700	0.3567	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Generator	EALF	15'	87'	12'	118,700	0.3567	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Catwalk	EALF	15'	87'	12'	118,525	0.3567	20,700	4'	20,700	38'	15,575	4'	15,750	4'	15,750	4'	15,750							3.9753
Total				1,586,180																				46.4747

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
MUD PUMP	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
DRILLERS CABIN	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
SCR HOUSE	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
SUBSTRUCTURE	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
CROWN	15'	87'	13'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
MUD TANK	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
BUNK HOUSE	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
SHAKER SKID	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
CENTER	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
GENERATOR	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
BUNK HOUSE	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
DRAWWORKS	15'	72'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
Total				1,564,340																						46.5767

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
Mud Pump	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536				1.6536							3.6679
Mud Pump	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536				1.6536							3.6679
Substructure	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536				1.6536							3.6679
Substructure	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536				1.6536							3.6679
Mud Pump	15'	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536				1.6536							3.6679
Crown	15'	95'	14'	141,085	14,300	18'	20,700	4'	20,700	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	4.6038
	EALF				0.3567		2.5934						1.6536				1.6536							4.6038
Mud Tank	15'	90'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.0523
	EALF				0.3567		1.6576						1.0380				1.0380							3.0523
Mud Tank	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Drawworks	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Catwalk	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Generator	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Generator	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Driller's Cabin	15'	87'	14'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Center	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Mud Boat	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Derrick	15'	87'	14'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	4'	15,750	3.9881
	EALF				0.3567		2.5934						1.0380				1.0380							3.9881
Total				2,109,110																				61.8889

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
DERRICK	15'6"	85'	14'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567		1.6576						1.0380											
DRAWWORKS	15'	82'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
CAT WALK	13'6"	91'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
TOP HOUSE	15'6"	98'	13'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
CHOKE MANIFOLD	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
PUMP	15'6"	98'	12'6"	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
PUMP	15'6"	98'	12'6"	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
SCR HOUSE	15'6"	98'	12'6"	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
SUBSTRUCTURE	15'6"	98'	12'6"	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
MCC UNIT	15'6"	90'	12'6"	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567		1.6576						1.0380											
PUSHER HOUSE	15'6"	90'	13'6"	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567		1.6576						1.0380											
PONY SUB	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
CHOKE	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
MUD BOAT	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
GENERATOR	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
HYDRAULIC UNIT	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
MUD TANK	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
SHAKER	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
MUD TANK	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
GENERATOR	15'6"	87'	12'6"	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Total				2,586,725									1.0380											75.3541

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
																								EALF
SUBSTRUCTURE	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567				1.6576						1.6536									
PUMP	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567				1.6576						1.6536									
CROWN SECTION	15'6"	98'	14'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567				1.6576						1.6536									
SHAKER	15'6"	90'	12'6"	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567				1.6576						1.0380									
CENTER	15'6"	90'	12'6"	131,300	14,300	18'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567				1.6576						1.0380									
HYDRAULIC UNIT	15'6"	98'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	5'	15,750					3.0523
	EALF				0.3567				1.6576						1.0380									
MUD TANK	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567				2.5934						1.0380									
SCR HOUSE	15'	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567				2.5934						1.0380									
MUD BOAT	15'6"	87'	14'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567				2.5934						1.0380									
DERRICK	15'6"	87'	14'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567				2.5934						1.0380									
GENERATOR	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567				2.5934						1.0380									
JUNK BOX	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	28'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567				2.5934						1.0380									
Total				1,567,155																				44.0894

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
Substructure	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
Substructure	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
Driller's Cabin	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
Pump	15'6"	97'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	39'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
Pump	15'6"	97'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	39'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
SCR House	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	3.6679
	EALF				0.3567		1.6576						1.6536											
Mud Tank	15'6"	90'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567		1.6576						1.0380											
Mud Tank	15'6"	90'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567		1.6576						1.0380											
Blow Out Preventer	15'6"	76'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	39'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
	EALF				0.3567		1.6576						1.0380											
Generator	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Generator	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Catwalk	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Shaker	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Shaker	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Drawworks	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Mud Boat	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF				0.3567		2.5934						1.0380											
Total				2,146,910																				59.0814

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
PUMP		15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	EALF
	EALF					0.3567			1.6576								1.6536										3.6679
SUBSTRUCTURE		15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	
	EALF					0.3567			1.6576								1.6536										3.6679
SCR HOUSE		15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077	
	EALF					0.3567			1.6576								1.6536										3.6679
MUD TANK		15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.6679
	EALF					0.3567			2.5934							1.0380											3.9881
DRAWWORKS		15'6"	72'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750									3.9881
	EALF					0.3567			2.5934							1.0380											3.9881
MUD BOAT		15'6"	90'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
	EALF					0.3567			1.6576							1.0380											3.0523
CROWN SECTION		15'6"	90'	14'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.0523
	EALF					0.3567			1.6576							1.0380											3.0523
DERRICK		15'6"	98'	14'	141,085	14,300	18'	20,700	4'	20,700	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077							4.6038
	EALF					0.3567			2.5934							1.6536											4.6038
Total					1,102,140																						29.6884

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total EALF
S.E.R. House	15'6"	93'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Pusher House	15'6"	99'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Mud Pump	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Shakers	15'6"	84'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Pony Sub	15'6"	80'	10'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Substructure	15'6"	84'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Mud Tank	15'6"	84'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Mud Tank	15'6"	98'	12'	153,685	14,300	17'	18,000	4'	18,000	4'	18,000	38'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			3.6679
Generator	15'6"	85'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
Generator	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Generator	15'6"	90'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
Choke Manifold	15'6"	90'	12'	131,300	14,300	17'	18,000	4'	18,000	4'	18,000	38'	15,750	4'	15,750	4'	15,750	4'	15,750					3.0523
Catwalk	15'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Derrick	15'6"	89'	12'	118,700	14,300	18'	20,700	4'	20,700	40'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Mud Boat	13'6"	87'	12'	118,700	14,300	18'	20,700	4'	20,700	38'	15,750	4'	15,750	4'	15,750	4'	15,750							3.9881
Drawworks	15'6"	83'	12'	109,700	14,300	18'	20,700	4'	20,700	43'	18,000	4'	18,000	4'	18,000									4.6077
Total				2,067,940																				60.3414

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
																								EALF
CRAWLER CRANE	EALF	15'	95'	12'	172,875	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2328
					1.0000																			
V F D HOUSE	EALF	14'6"	85'	12'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
GENERATOR HOUSE	EALF	14'6"	85'	12'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
GENERATOR HOUSE	EALF	15'6"	85'	12'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
GENERATOR HOUSE	EALF	15'6"	85'	12'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
MUD TANK	EALF	15'6"	85'	13'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
WATER TANK	EALF	15'6"	85'	12'	136,200	14,300	13'	23,000	4'	23,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975						6.9557
					0.3567																			
MUD PUMP	EALF	15'6"	85'	13'6"	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
mud pump	EALF	15'6"	85'	13'6"	158,875	18,000	17'	23,000	5'	23,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975				7.8587
					1.0000																			
TOP DOG HOUSE	EALF	15'6"	85'	13'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
DRAW WORKS	EALF	14'	85'	12'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
CENTER PIECE	EALF	14'6"	85'	15'	136,200	14,300	13'	23,000	4'	23,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975						6.9557
					0.3567																			
SUBSTRUCTURE	EALF	15'9"	85'	10'	158,875	18,000	17'	23,000	5'	23,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975				7.8587
					1.0000																			
CRAWLER CRANE	EALF	15'6"	85'	12'3"	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
TRIP TANK	EALF	15'6"	85'	12'	158,875	18,000	17'	23,000	5'	23,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975				7.8587
					1.0000																			
MUD BOAT	EALF	14'	85'	14'	158,875	18,000	17'	23,000	5'	23,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975				7.8587
					1.0000																			
DERRICK CROWN SECTION	EALF	15'6"	85'	14'	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
A LEG SECTION	EALF	15'6"	85'	14'4"	172,695	18,000	13'	20,000	4'	20,000	4'	20,000	37'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2100
					1.0000																			
Crane Truck	EALF	13'4"	69'	8'6"	102,500	12,500	18'	22,500	5'	22,500	34'	22,500	12'	22,500										9.5100
					0.1971																			
MANIFOLD	EALF	14'	69'	13'6"	84,490	12,000	17'	18,986	5'	18,986	42'	17,259	5'	17,259										3.0539
					0.1649																			
Sideboom	EALF	14'	110'	12'	133,000	13,000	14'	20,000	5'	20,000	5'	20,000	36'	20,000	5'	20,000	5'	20,000						5.3759
					0.2341																			
CRAWLER CRANE	EALF	15'3"	95'	12'6"	172,875	18,000	13'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2328
					1.0000																			
Compressor	EALF	13'6"	70'	11'	120,000	14,300	19'	22,850	4'	22,850	37'	20,000	5'	20,000	5'	20,000								7.0005
					0.3567																			
Total					3,593,285																			151.0622

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
Mud Tank	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Sub Structure	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
A Leg	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Mud Tank	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
SCR House	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Draw Works	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Mud Tank	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Mud Tank	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
A Leg	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
A Leg	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Mud Pump	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Crane	14'10"	110'	13'8"	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
SCR House	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
Motor Skid	16'	110'	14'	149,900	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975					5.5575
Center Steel	16'	105'	14'	149,900	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975					5.2979
SCR House	16'	105'	14'	149,900	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975					5.2979
SCR House	16'	95'	14'	120,000	16,000	18'	22,000	4'	22,000	32'	20,000	4'	20,000	4'	20,000									5.2979
Crown Section	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5839
SCR House	16'	110'	14'	168,875	14,000	18'	20,000	4'	20,000	4'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			5.5575
					0.3247				2.5709								2.6619							5.5575
Total				3,102,825																				105.8407

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				2.1276
					0.1971			1.0972						0.8332										
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				2.1276
					0.1971			1.0972						0.8332										
GAS BUSTER	EALF	16'	97'	14'	138,294	14,300	15'	18,562	5'	18,562	5'	18,562	32'	17,077	5'	17,077	5'	17,077	5'	17,077				3.7330
					0.3567			1.8840						1.4923										
SUCTION TANK	EALF	15'10"	110'	13'	169,175	14,300	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		5.5895
					0.3567			2.5709						2.6619										
PUMP	EALF	15'6"	90'	13'	158,875	18,000	20'	23,000	5'	23,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975				7.8587
					1.0000			4.1968						2.6619										
GRASS HOPPER	EALF	14'	110'	13'	120,000	14,300	15'	18,500	5'	18,500	32'	17,200	5'	17,200	5'	17,150	5'	17,150						3.4449
					0.3567			1.5570						1.5312										
MOTOR	EALF	15'6"	90'	13'	120,000	14,300	15'	17,500	5'	17,500	32'	17,700	5'	17,700	5'	17,700	5'	17,600						3.3107
					0.3567			1.2113						1.7427										
MUD PUMP	EALF	15'6"	90'	13'	169,175	14,300	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		5.5895
					0.3567			2.5709						2.6619										
WATER TANK	EALF	15'6"	110'	13'	120,000	14,300	20'	17,000	5'	17,000	32'	14,250	5'	14,250	5'	14,250	5'	14,700						2.1770
					0.3567			1.0630						0.7573										
SCR HOUSE	EALF	16'	110'	14'	120,000	14,300	20'	17,000	5'	17,000	32'	14,340	5'	14,340	5'	14,340	5'	14,340						2.1770
					0.3567			1.0630						0.7573										
SUB STRUCTURE	EALF	15'6"	100'	13'	172,875	18,000	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2328
					1.0000			2.5709						2.6619										
A LEG	EALF	15'	100'	10'	120,000	14,000	20'	18,000	5'	18,000	32'	14,000	5'	14,000	5'	14,000	5'	14,000						2.3811
					0.3247			1.3755						0.6808										
SUBSTRUCTURE	EALF	15'6"	110'	13'	168,875	14,000	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		5.5575
					0.3247			2.5709						2.6619										
A LEG	EALF	15'	110'	10'	120,000	14,300	20'	17,500	5'	17,500	32'	14,140	5'	14,140	5'	14,140	5'	14,140						2.2796
					0.3567			1.2113						0.7115										
DRAW WORKS	EALF	16'	90'	14'	172,875	18,000	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		6.2328
					1.0000			2.5709						2.6619										
CROWN	EALF	15'10"	110'	14'	177,275	20,600	15'	20,600	5'	20,600	5'	20,600	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		7.4145
					1.8442			2.9083						2.6619										
CRANE	EALF	14'	110'	11'	177,275	20,600	15'	20,600	5'	20,600	5'	20,600	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975		7.4145
					1.8442			2.9083						2.6619										
dog house	EALF	15'8"	110'	13'	120,000	14,000	15'	20,000	5'	20,000	32'	13,200	5'	13,200	5'	13,200	5'	13,200						3.0673
					0.3247			2.2175						0.5250										78.7157
Total				2,584,694																				

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
																							EALF	
CRANE	14'10"	100'	13'6"	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
FORK LIFT	15'3"	90'	10'	120,000	18,000	20'	16,000	5'	16,000	34'	14,000	5'	14,000	5'	14,000	5'	14,000	5'	14,000					2.4906
	EALF				1.0000				0.8097						0.6808									
BUNK HOUSE	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.1276
	EALF				0.1971				1.0972						0.8332									
BUNK HOUSE	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.1276
	EALF				0.1971				1.0972						0.8332									
BUNK HOUSE	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.1276
	EALF				0.1971				1.0972						0.8332									
CRANE	14'10"	110'	13'6"	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
TRIP TANK	16'3"	110'	12'	130,508	20,800	20'	20,700	5'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077							6.0130
	EALF				1.9272				2.5934						1.4923									
RIG HOUSE	15'6"	110'	14'	159,071	18,000	15'	18,562	5'	18,562	5'	18,562	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077			4.5376
	EALF				1.0000				1.8840						1.6536									
MUD PUMP	15'6"	110'	14'	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
MUD PUMP	15'6"	110'	14'	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
RIG HOUSE	15'6"	110'	14'	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
DERRICK SECTION	15'6"	120'	14'	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
DERRICK SECTION	15'6"	120'	14'	174,675	18,000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			6.5702
	EALF				1.0000				2.9083						2.6619									
RIG HOUSE	15'6"	110'	14'	155,700	18,000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975					6.3105
	EALF				1.0000				2.9083						2.4022									
scr house	14'	110'	11'	177,275	20,600	15'	20,600	5'	20,600	5'	20,600	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			7.4145
	EALF				1.8442				2.9083						2.6619									
MUD BOAT	14'	110'	15'	126,000	18,000	15'	18,000	5'	18,000	32'	18,000	5'	18,000	5'	18,000	5'	18,000							4.2677
	EALF				1.0000				1.3755						1.8921									
RIG HOUSE	16'	120'	14'	158,300	20,600	15'	20,600	5'	20,600	5'	20,600	32'	18,975	5'	18,975	5'	18,975	5'	18,975					7.1548
	EALF				1.8442				2.9083						2.4022									
SUB STRUCTURE	14'2"	105'	10'	144,785	18,000	20'	20,700	5'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					5.2470
	EALF				1.0000				2.5934						1.6536									
SUB STRUCTURE	14'2"	105'	10'	144,785	18,000	20'	20,700	5'	20,700	34'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077					5.2470
	EALF				1.0000				2.5934						1.6536									
BUNK HOUSE	14'	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.1276
	EALF				0.1971				1.0972						0.8332									
BUNK HOUSE	15'5"	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.1276
	EALF				0.1971				1.0972						0.8332									
BUNK HOUSE	15'5"	105'	16'	120,000	12,500	15'	17,120	4'	17,120	33'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					2.1276
	EALF				0.1971				1.0972						0.8332									
CRANE	14'6"	115'	13'6"	176,675	20,000	14'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			7.1823
	EALF				1.6121				2.9083						2.6619									
CRANE	14'6"	115'	13'6"	176,675	20,000	14'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975			7.1823
	EALF				1.6121				2.9083						2.6619									
Total				3,612,499																				121.8044

Descripton	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
mudtank	EALF	16'	110'	14'	174,875	20,000	1.6121	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
LINE TRUCK (Crane)	EALF	13'4"	69'	8'6"	102,500	12,500	0.1971	18'	22,500	5'	22,500	34'	22,500	12'	22,500	2.6619								9.5100
Rig Skid, House, Tank	EALF	16'	110'	14'	174,875	20,000	1.6121	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
mudtank	EALF	16'	110'	14'	174,875	20,000	1.6121	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
Fuel tank	EALF	16'	110'	14'	155,900	20,000	1.6121	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5853
motor	EALF	16'	110'	14'	120,000	14,000	0.3247	15'	20,000	5'	20,000	32'	16,500	5'	16,500	5'	16,500	5'	16,500					3.8209
House	EALF	16'	110'	14'	162,000	18,000	1.0000	15'	18,000	5'	18,000	5'	18,000	32'	18,000	5'	18,000	5'	18,000	5'	18,000	5'	18,000	4.7542
motor	EALF	16'	110'	14'	120,000	14,000	0.3247	15'	20,000	5'	20,000	32'	16,500	5'	16,500	5'	16,500	5'	16,500					3.8209
motor	EALF	16'	110'	14'	120,000	14,000	0.3247	15'	20,000	5'	20,000	32'	16,500	5'	16,500	5'	16,500	5'	16,500					3.8209
pump	EALF	16'	110'	14'	174,875	20,000	1.6121	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
pump	EALF	16'	110'	14'	174,875	20,000	1.6121	15'	20,000	5'	20,000	5'	20,000	32'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.8450
Manifold	EALF	14'	69'	13'6"	84,490	12,000	0.1649	17'	18,986	5'	18,986	42'	17,259	5'	17,259									3.0539
tool house	EALF	15'6"	85'	14'	152,950	18,000	1.0000	15'	20,600	5'	20,600	34'	18,750	5'	18,750	5'	18,750	5'	18,750					6.0587
RIG HOUSE	EALF	15'6"	110'	14'	120,000	14,300	0.3567	15'	18,695	5'	18,697	34'	17,077	5'	17,077	5'	17,077	5'	17,077					3.4821
SUB STRUCTURE	EALF	15'	105'	9'8"	174,675	18,000	1.0000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5702
CRANE	EALF	14'10"	110'	13'6"	174,675	18,000	1.0000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5702
RIG HOUSE	EALF	16'	105'	14'	120,000	18,000	1.0000	20'	17,100	5'	17,100	34'	13,500	5'	13,500	5'	13,500	5'	13,800	5'	13,500			2.6826
RIG HOUSE	EALF	16'	105'	14'	120,000	18,000	1.0000	20'	17,100	5'	17,100	34'	13,600	5'	13,600	5'	13,600	5'	13,500	5'	13,500			2.6826
DOG HOUSE	EALF	16'	100'	10'	120,000	14,300	0.3567	15'	18,696	5'	18,696	34'	17,077	5'	17,077	5'	17,077	5'	17,077					3.4821
WIRE TRAY	EALF	14'	110'	8'6"	140,994	17,000	0.7728	15'	18,562	5'	18,562	5'	18,562	34'	17,077	5'	17,077	5'	17,077	5'	17,077			4.1491
SUB STRUCTURE	EALF	16'	110'	14'	174,675	18,000	1.0000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5702
CENTER STEEL	EALF	14'	90'	14'	120,000	14,000	0.3247	15'	17,000	5'	17,000	34'	18,000	5'	18,000	5'	18,000	5'	18,000					3.2799
DRAW WORKS	EALF	15'6"	105'	14'	174,675	18,000	1.0000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5702
A LEG	EALF	16'	110'	10'	158,875	18,000	1.0000	20'	23,000	5'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975					7.8587
CROWN SECTION	EALF	16'	110'	14'	174,675	18,000	1.0000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5702
A LEG	EALF	16'	110'	10'	158,875	18,000	1.0000	20'	23,000	5'	23,000	34'	18,975	5'	18,975	5'	18,975	5'	18,975					7.8587
JUNK BOX	EALF	14'	105'	14'	137,000	18,000	1.0000	15'	17,000	5'	17,000	5'	17,000	34'	17,000	5'	17,000	5'	17,000	5'	17,000			3.7686
CRANE	EALF	14'	105'	13'6"	174,675	18,000	1.0000	15'	20,600	5'	20,600	5'	20,600	34'	18,975	5'	18,975	5'	18,975	5'	18,975	5'	18,975	6.5702
Total					4,136,009																			154.3151

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total	
CRANE	EALF	14'10"	110'	13'6"	174,675	18,000 1.0000	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	6.5702
BUNK HOUSE	EALF	14'	105'	16'	120,000	12,500 0.1971	15'	17,120 1.0972	4'	17,120 1.0972	33'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	2.1276
BUNK HOUSE	EALF	15'5"	105'	14'	120,000	12,500 0.1971	15'	17,120 1.0972	4'	17,120 1.0972	33'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	4'	14,652 0.8332	2.1276
CRANE	EALF	14'10"	106'	13'6"	174,675	18,000 1.0000	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	6.5702
MUD TANK	EALF	15'6"	110'	13'	170,975	14,300 0.3567	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5.9269
MUD PUMP	EALF	15'6"	90'	14'	170,975	14,300 0.3567	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5.9269
MUD TANK	EALF	15'6"	110'	13'	174,675	18,000 1.0000	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	6.5702
MUD PUMP	EALF	15'6"	90'	14'	174,675	18,000 1.0000	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	6.5702
MUD TANK	EALF	16'6"	90'	14'	155,700	18,000 1.0000	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	6.3105
MUD TANK	EALF	16'6"	90'	14'	152,000	14,300 0.3567	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5.6673
MOTOR	EALF	14'	90'	12'	170,875	16,000 0.5887	14'	20,000 2.5709	5'	20,000 2.5709	5'	20,000 2.5709	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5.8215
SCR HOUSE	EALF	14'6"	90'	13'	161,385	16,000 0.5887	19'	20,000 2.5709	5'	20,000 2.5709	5'	20,000 2.5709	34'	17,077 1.6536	5'	17,077 1.6536	5'	17,077 1.6536	5'	17,077 1.6536	5'	17,077 1.6536	5'	17,077 1.6536	4.8132
DRAW WORKS	EALF	15'6"	90'	13'	174,675	18,000 1.0000	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	6.5702
SUB STRUCTURE	EALF	15'6"	105'	13'	170,975	14,300 0.3567	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5.9269
SUB STRUCTURE	EALF	15'6"	105'	13'	170,975	14,300 0.3567	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5.9269
RIG HOUSE	EALF	15'10"	90'	12'	120,000	18,000 1.0000	20'	16,000 0.8097	5'	16,000 0.8097	34'	17,500 1.6662	5'	17,500 1.6662	5'	17,500 1.6662	5'	17,500 1.6662	5'	17,500 1.6662	5'	17,500 1.6662	5'	17,500 1.6662	3.4759
A LEG	EALF	16'	120'	10'	170,975	14,300 0.3567	15'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5.9269
A LEG	EALF	16'	120'	10'	155,175	14,300 0.3567	20'	23,000 4.1968	5'	23,000 4.1968	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	7.2154
RIG HOUSE	EALF	15'10"	105'	14'	130,200	14,300 0.3567	20'	20,000 2.2175	5'	20,000 2.2175	34'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	5'	18,975 2.4022	4.9765
CROWN SECTION	EALF	15'9"	110'	17'	120,000	18,000 1.0000	20'	17,000 1.0630	5'	17,000 1.0630	34'	13,500 0.5989	5'	13,500 0.5989	5'	13,500 0.5989	5'	13,750 0.5989	5'	13,750 0.5989	5'	13,750 0.5989	5'	13,750 0.5989	2.6619
CRANE	EALF	14'	105'	12'	177,275	20,600 1.8442	14'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	7.4145
CRANE	EALF	14'6"	110'	13'6"	177,275	20,600 1.8442	14'	20,600 2.9083	5'	20,600 2.9083	5'	20,600 2.9083	34'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	5'	18,975 2.6619	7.4145
MANIFOLD	EALF	16'6"	100'	10'	114,125	14,300 0.3567	16'	20,625 2.9230	5'	20,625 2.9230	5'	20,625 2.9230	35'	18,975 1.7464	5'	18,975 1.7464	5'	18,975 1.7464	5'	18,975 1.7464	5'	18,975 1.7464	5'	18,975 1.7464	5.0262
Total					3,602,260																			127.538	

SUPPLEMENTAL APPENDIX 2



Supplemental Appendix 2
Typical Rig Vehicle Combination

Descriptor	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Unit Total
Fuel Tank	15'	85'	10'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652					3.7834
FUEL TANK	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
FUEL TANK	EALF	16'	85'	13'	124,008	14,300	17'	20,700	4'	20,700	32'	17,077	5'	17,077	5'	17,077	5'	17,077						4.4424
Trip Tank	EALF	16'	85'	13'	118,608	14,300	17'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.2246
HPU	EALF	16'	85'	13'	118,608	14,300	17'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.2246
Bunk House	EALF	16'	85'	13'	118,608	14,300	17'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077						3.2246
Generator	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
Mud Tank	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
Ramp	EALF	16'	85'	14'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
B.O.P. Handler	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
SCR	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
Floor House	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
B.O.P.	EALF	16'	85'	13'	143,108	20,800	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077				5.0771
Derrick	EALF	16'	95'	15'	122,300	14,300	14'	18,000	4'	18,000	4'	18,000	32'	18,000	4'	18,000	4'	18,000						3.6719
Derrick	EALF	16'	95'	15'	113,300	14,300	17'	18,000	4'	18,000	32'	15,750	4'	15,750	4'	15,750	4'	15,750						2.7703
Center Substructure	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
Generator	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
Shaker Skid	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
Utility Skid	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
Drawworks	EALF	16'	85'	13'	118,700	14,300	17'	20,700	4'	20,700	32'	15,750	4'	15,750	4'	15,750	4'	15,750						3.9881
Mud Tank	EALF	16'	85'	13'	128,960	14,300	17'	20,700	4'	20,700	32'	14,652	4'	14,652	4'	14,652	4'	14,652	4'	14,652				3.7834
Mud Pump	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Substructure	EALF	16'	95'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
MCC	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Mud Pump	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Substructure	EALF	16'	85'	13'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Crew house	EALF	16'	95'	14'	153,685	14,300	14'	18,000	4'	18,000	4'	18,000	32'	17,077	5'	17,077	5'	17,077	5'	17,077	5'	17,077		3.6679
Total				3,624,986																				109.850843

SUPPLEMENTAL APPENDIX 3



Supplemental Appendix 3
Texas Department of Motor Vehicles (TxDMV) Data

Note: The following data is from the Texas Department of Motor Vehicles and delivered to NEI on May 25, 2012. The data was modified by omitting identifying information of the permit holder for the inclusion into this study.

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
11/2/2011	11/6/2011	Manufactured House	13'6"	100'	14'	0																						
11/2/2011	11/6/2011	Manufactured House	14'	95'	14'	0																						
11/2/2011	11/6/2011	Manufactured House	14'	95'	14'	0																						
11/2/2011	11/6/2011	MT OIL FIELD PIPE SKID	15'	74'	11'4"	109700	14300	16'	20700	4'	20700	36'	18000	4'	18000		18000		18000		18000		18000		18000		18000	
11/2/2011	11/6/2011	PIPELAYER	14'	75'	12'10"	155000	20000	14'	20000	5'	20000	5'	20000	36'	18750	5'	18750	5'	18750	5'	18750		18750		18750		18750	
11/2/2011	11/6/2011	Manufactured House	14'	96'	14'	0																						
11/2/2011	11/6/2011	Manufactured House	14'	96'	14'	0																						
11/2/2011	11/6/2011	Manufactured House	14'	96'	14'	0																						
11/2/2011	11/6/2011	EXCAVATOR	14'	75'	12'	150320	14000	14'	20500	5'	20500	5'	20500	36'	18570	5'	18750	5'	18750	5'	18750		18750		18750		18750	
11/2/2011	11/6/2011	EMPTY STEEL TANK	14'	80'	16'	0																						
11/2/2011	11/6/2011	EXCAVATOR	14'	75'	12'	150500	14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750		18750		18750		18750	
11/4/2011	11/7/2011	EMPTY STEEL TANK	15'	65'	12'4"	0																						
11/2/2011	11/6/2011	MUD PUMP	14'6"	80'	11'6"	169175	14300	15'	20000	4'	20000	4'	20000	30'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
11/2/2011	11/6/2011	MUD PUMP	14'6"	80'	11'6"	169175	14300	15'	20000	4'	20000	4'	20000	30'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
11/3/2011	11/7/2011	BUNKHOUSE	14'	105'	16'	120000	12500	15'	17120	4'	17120	33'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
11/3/2011	11/7/2011	BUNKHOUSE	14'	105'	16'	120000	12500	15'	17120	4'	17120	33'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
11/3/2011	11/7/2011	BUNKHOUSE	15'5"	105'	14'	120000	12500	15'	17120	4'	17120	33'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
11/3/2011	11/3/2011	BUNKHOUSE	14'	105'	16'	120000	12500	15'	17120	4'	17120	33'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
11/3/2011	11/7/2011	SUBSTRUCTURE	15'6"	70'	12'	130300	14300	15'	23000	4'	23000	30'	17500	4'	17500		17500		17500		17500		17500		17500		17500	
11/3/2011	11/7/2011	SUBSTRUCTURE	15'5"	75'	12'	155175	14300	15'	23000	4'	23000	30'	18975	5'	18975		18975		18975		18975		18975		18975		18975	
11/3/2011	11/7/2011	SHALE SHAKER SKID	15'5"	70'	15'6"	130300	14300	15'	23000	4'	23000	30'	17500	4'	17500		17500		17500		17500		17500		17500		17500	
11/3/2011	11/7/2011	EMPTY SAND BIN	13'8"	80'	11'9"	0																						
11/3/2011	11/7/2011	EMPTY SAND BIN	13'8"	80'	11'9"	0																						
11/3/2011	11/7/2011	EMPTY SAND BIN	13'8"	80'	11'9"	0																						
11/3/2011	11/7/2011	Manufactured House	14'	99'	14'	0																						
11/3/2011	11/7/2011	SEPARATOR SKID	15'8"	69'	11'6"	0																						
11/3/2011	11/7/2011	SEPARATOR SKID	15'8"	69'	11'6"	0																						
11/2/2011	11/7/2011	Manufactured House	14'	99'	14'	0																						
11/4/2011	11/8/2011	EMPTY SAND BIN	13'8"	80'	11'9"	0																						
11/5/2011	11/8/2011	OIL FIELD SKID	13'6"	70'	14'	0																						
11/4/2011	11/8/2011	STACKED STEEL PLATES	10'	108'	10'	0																						
11/4/2011	11/8/2011	STACKED STEEL PLATES	10'	108'	10'	0																						
11/4/2011	11/8/2011	STACKED STEEL PLATES	10'	108'	10'	0																						
11/4/2011	11/8/2011	SEPARATOR SKID	15'8"	69'	11'6"	0																						
11/5/2011	11/9/2011	2 EMPTY STEEL TANKS ele	14'10"	75'	12'	0																						
11/5/2011	11/9/2011	2 EMPTY STEEL TANKS ele	14'10"	75'	12'	0																						
11/5/2011	11/9/2011	2 EMPTY STEEL TANKS ele	14'10"	75'	12'	0																						
11/5/2011	11/9/2011	2 EMPTY STEEL TANKS ele	14'10"	75'	12'	0																						
11/5/2011	11/6/2011	Manufactured House	14'	95'	14'	0																						
11/5/2011	11/6/2011	Manufactured House	14'	95'	14'	0																						
11/7/2011	11/11/2011	Manufactured House	14'	95'	14'	0																						
11/7/2011	11/11/2011	Manufactured House	14'	95'	14'	0																						
11/7/2011	11/11/2011	Manufactured House	14'	96'	14'	0																						
11/7/2011	11/11/2011	Manufactured House	14'	96'	14'	0																						
11/7/2011	11/11/2011	DOZER	14'	65'	13'4"	106300	14300	19'	23000	5'	23000	34'	23000	5'	23000													
11/7/2011	11/11/2011	Manufactured House	13'	100'	14'	0																						
11/7/2011	11/11/2011	Manufactured House	13'	100'	14'	0																						
11/7/2011	11/11/2011	EMPTY 400 BBL TANKS E/E SAME SIZE	16'	78'	12'	0																						
11/7/2011	11/11/2011	EMPTY 400 BBL TANKS E/E SAME SIZE	16'	78'	12'	0																						
11/9/2011	11/13/2011	Manufactured House	13'6"	100'	14'	0																						
11/9/2011	11/13/2011	excavator	14'	85'	12'	155700	14300	12'	20000	4'	20000	4'	20000	40'	16280	4'	16280	4'	16280	4'	16280	4'	16280	4'	16280	4'	16280	4'
11/10/2011	11/14/2011	Manufactured House	14'	96'	14'	0																						
11/10/2011	11/14/2011	Manufactured House	14'	96'	14'	0																						
11/10/2011	11/14/2011	Manufactured House	14'	96'	14'	0																						
11/9/2011	11/13/2011	COMPRESSOR	14'7"	110'	16'	198650	16000	17'	18975	5'	18975	5'	18975	5'	17875	14'	17875	5'	17875	5'	17875	35'	17875	5'	17875	5'	17875	5'
11/9/2011	11/13/2011	COOLER	16'9"	80'	13'7"	0																						
11/10/2011	11/14/2011	TRACHOGE	13'6"	74'	12'	130900	13000	19'	21000	5'	21000	35'	18975	5'	18975		18975		18975		18975		18975		18975		18975	
11/10/2011	11/14/2011	DERRICK	16'	95'	15'	122300	14300	14'	18000	4'	18000	4'	18000	32'	18000	4'	18000		18000		18000		18000		18000		18000	
11/10/2011	11/14/2011	FUEL TANK	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
11/10/2011	11/14/2011	FLOOR HOUSE	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	17077	5'	17077	4'	17077	4'	17077	4'	17077	5'	17077	5'	17077	5'	17077	5'
11/10/2011	11/14/2011	GENERATOR	16'	85'	13'	118700	14300	17'	20700	4'	20700	32'	15750	4'	15750		15750		15750		15750		15750		15750		15750	
11/10/2011	11/14/2011	B.O.P. HANDLER	16'	85'	13'	118700	14300	17'	20700	4'	20700	32'	15750	4'	15750		15750		15750		15750		15750		15750		15750	
11/10/2011	11/14/2011	SUBSTRUCTURE	16'	95'	13'	153685	14300	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'								

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

[illegible]

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	
12/30/2011	12/7/2011	A Leg	15'	117'	14'	168875																			
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/3/2011	12/7/2011	Mud Tank	15'	110'	14'	168875	14000	18'	18000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/3/2011	12/7/2011	SCR House	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/3/2011	12/7/2011	SCR House	15'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/3/2011	12/7/2011	SCR House	15'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/3/2011	12/7/2011	A Leg	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/3/2011	12/7/2011	A Leg	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	SCR House	14'	99'	14'	0																			
12/3/2011	12/7/2011	Mud Pump	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	Manufactured House	14'	99'	14'	0																			
12/3/2011	12/7/2011	SCR House	14'	110'	136"	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	SCR House	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	Motor Skid	16'	110'	14'	149900	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	Center Steel	16'	105'	14'	149900	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	SCR House	16'	105'	14'	149900	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	SCR House	16'	95'	14'	120000	16000	18'	22000	4'	22000	32'	20000	4'	20000										
12/3/2011	12/7/2011	Crown Section	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/3/2011	12/7/2011	SCR House	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/4/2011	12/8/2011	Manufactured House	14'	95'	14'	0																			
12/4/2011	12/8/2011	Manufactured House	14'	95'	14'	0																			
12/4/2011	12/8/2011	SUBSTRUCTURE	16'	95'	14'	153685	14300	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/5/2011	12/9/2011	Drivers Cabin	16'	83'	10'	152800	16900	15'	20000	4'	20000	4'	20000	36'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	FRAC PUMP INTOW	136"	65'	86"	83000	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/5/2011	12/9/2011	Haul Steel tank	15'	75'	10'	0																			
12/5/2011	12/9/2011	Motor Skid	14'	83'	86"	171775	16900	15'	20000	4'	20000	4'	20000	36'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	Steel Tank	15'	75'	10'	0																			
12/5/2011	12/9/2011	Manufactured House	13'	80'	14'	0																			
12/5/2011	12/9/2011	Manufactured House	13'	80'	14'	0																			
12/6/2011	12/10/2011	Manufactured House	14'	96'	14'	0																			
12/6/2011	12/10/2011	Manufactured House	14'	96'	14'	0																			
12/6/2011	12/10/2011	Manufactured House	14'	96'	14'	0																			
12/6/2011	12/10/2011	Manufactured House	14'	96'	14'	0																			
12/5/2011	12/9/2011	crane 32856 63027	146"	110'	12'	169175	14300	15'	20000	4'	20000	4'	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/5/2011	12/9/2011	crane 32873 62073	146"	110'	12'	169175	14300	15'	20000	4'	20000	4'	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/6/2011	12/10/2011	CRANE	155'	65'	125'	0																			
12/6/2011	12/10/2011	EXCAVATOR	14'	75'	12'	150500	14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750
12/6/2011	12/10/2011	Manufactured House	14'	95'	14'	0																			
12/6/2011	12/10/2011	Pump	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/6/2011	12/10/2011	Substructure	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/6/2011	12/10/2011	Shaker	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/6/2011	12/10/2011	SCR House	15'	90'	12'	131300	14300	17'	18000	4'	18000	4'	18000	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/6/2011	12/10/2011	Drillers Cabin	15'	90'	12'	131300	14300	17'	18000	4'	18000	4'	18000	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/6/2011	12/10/2011	Drawworks	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750										
12/6/2011	12/10/2011	Drawworks	15'	87'	136"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750										
12/6/2011	12/10/2011	Mud Tank	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750										
12/6/2011	12/10/2011	Mud Tank	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750										
12/6/2011	12/10/2011	Mud Tank	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750										
12/6/2011	12/10/2011	Generator	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750										
12/6/2011	12/10/2011	Catwalk	15'	87'	12'	118525	14300	18'	20700	4'	20700	38'	15575	4'	15750										
12/6/2011	12/10/2011	Bunkhouse	15'	90'	12'	0																			
12/6/2011	12/10/2011	Diesel Tank (empty)	15'	87'	12'	0																			
12/6/2011	12/10/2011	Bunk House	15'	87'	12'	0																			
12/7/2011	12/11/2011	Manufactured House	13'	100'	14'	0																			
12/6/2011	12/10/2011	FRAC PUMP IN TOW	136"	65'	86"	83075	12000	18'	18000	4'	18000	29'	17500	4'	17500										
12/6/2011	12/10/2011	Manufactured House	14'	70'	14'	0																			
12/6/2011	12/10/2011	GAS COMPRESSOR	156"	72'	139'	135600	15600	16'	20000	4'	20000	4'	20000	36'	20000	4'	20000	4'	20000	4'					

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	
12/17/2011	12/21/2011	Manufactured House	14'	96'	14'	0																							
12/17/2011	12/21/2011	Manufactured House	14'	96'	14'	0																							
12/17/2011	12/21/2011	Manufactured House	14'	96'	14'	0																							
12/16/2011	12/20/2011	SCRAPER	146'	72'	22'	143400	23400	14'	20000	4'	20000	4'	20000	38'	20000	4'	20000	4'	20000										
12/16/2011	12/20/2011	SCRAPER	146'	72'	22'	143400	23400	14'	20000	4'	20000	4'	20000	38'	20000	4'	20000	4'	20000										
12/15/2011	12/19/2011	Manufactured House	14'	100'	14'	0																							
12/15/2011	12/19/2011	Manufactured House	14'	99'	14'	0																							
12/16/2011	12/20/2011	SEPARATOR SKID	158'	69'	119'	0																							
12/16/2011	12/20/2011	Manufactured House	14'	99'	14'	0																							
12/16/2011	12/20/2011	Steel tank	15'	75'	10'	0																							
12/16/2011	12/20/2011	empty steel tank	15'	75'	12"	0																							
12/16/2011	12/20/2011	House 32919 63022	158'	110'	12'	0																							
12/17/2011	12/21/2011	Manufactured House	13'	100'	14'	0																							
12/19/2011	12/23/2011	Manufactured House	13'	100'	14'	0																							
12/16/2011	12/20/2011	House 32871 63022	158'	110'	12'	0																							
12/16/2011	12/20/2011	house 32939 63022	158'	110'	12'	0																							
12/16/2011	12/20/2011	house 32919 63022	158'	110'	12'	0																							
12/16/2011	12/20/2011	Motor	146'	110'	10'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/16/2011	12/20/2011	STEEL TANK	15'	75'	10'	0																							
12/17/2011	12/21/2011	STEEL TANK	15'	75'	10'	0																							
12/17/2011	12/21/2011	MOTOR 32892 63022	146'	110'	10'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	Tank 32890 63022	158'	110'	13'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	link	15'	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	jump 32873 63022	15'	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	crane 32892 63022	146'	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	pump	15'	110'	12'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	motor	158'	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/17/2011	12/21/2011	FORKLIFT	14'10"	90'	10'	134000	14000	14'	15000	5'	15000	4'	15000	34'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000
12/18/2011	12/22/2011	SCRAPER PUMP	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/18/2011	12/22/2011	DRILLERS CABIN	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/18/2011	12/22/2011	SCR HOUSE	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/18/2011	12/22/2011	SCR HOUSE	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/18/2011	12/22/2011	SUBSTRUCTURE	15'	98'	12'	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/18/2011	12/22/2011	CROWN	15'	87'	139'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	MUD TANK	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	BUNK HOUSE	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	SHAKER SKID	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	CENTER	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	GENERATOR	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	BUNK HOUSE	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	DRAWWORKS	15'	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750
12/18/2011	12/22/2011	Crane	14'10"	110'	139'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/18/2011	12/22/2011	Crane	14'10"	110'	139'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/18/2011	12/22/2011	Crane	14'10"	110'	139'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/18/2011	12/22/2011	Manufactured House	14'	99'	14'	0																							
12/19/2011	12/23/2011	derrick 32849 63022	15'	110'	12'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/19/2011	12/23/2011	crane 32892 63022	146'	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/19/2011	12/23/2011	crane 32880 63022	154'	110'	14'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077
12/19/2011	12/23/2011	Mud Pump	16'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/19/2011	12/23/2011	Mud Pump	158'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/19/2011	12/23/2011	Mud Pump	158'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/19/2011	12/23/2011	Mud Tank	158'	110'	14'	168875	14000	18'	20000	4'	20000	4'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975
12/19/2011	12/23/2011	Mud Tank	16'	105'	14'	149720	14000	18'	20000	4'	20000	4'	20000	32'	18795	5'	18795	5'											

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	
12/28/2011	1/2/2012	Crane	14'10"	117'	13'8"	177800																							
12/28/2011	1/1/2012	Manufactured House	14'	99'	14'	0																							
12/28/2011	1/1/2012	PIPELAYER	14'	75'	12'10"	155000	20000	14'	20000	5'	20000	5'	20000	36'	18750	5'	18750	5'	18750	5'	18750								
12/29/2011	1/2/2012	Manufactured House	14'	99'	14'	0																							
12/29/2011	1/2/2012	Manufactured House	14'	99'	14'	0																							
12/29/2011	1/2/2012	EMPTY STEEL TANK	156"	65'	124"	0																							
12/29/2011	1/2/2012	Oil FIELD MATERIAL	156"	70'	105"	0																							
12/30/2011	1/3/2012	Manufactured House	13'	100'	14'	0																							
12/31/2011	1/4/2012	Manufactured House	13'	100'	14'	0																							
12/29/2011	1/2/2012	Manufactured House	14'	99'	14'	0																							
12/29/2011	1/2/2012	Manufactured House	14'	99'	14'	0																							
12/30/2011	1/3/2012	Manufactured House	14'	99'	14'	0																							
12/29/2011	1/2/2012	Manufactured House	14'	99'	14'	0																							
12/30/2011	1/3/2012	COMPRESSOR	156"	75'	15'10"	139500	18500	18'	20000	5'	20000	5'	20000	36'	20000	4'	20000	4'	20000										
12/31/2011	1/4/2012	CRADLE	14'	85'	14'	143108	20800	14'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077										
12/31/2011	1/4/2012	DERICK BOARD	14'	85'	14'	143108	20800	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077										
12/30/2011	1/3/2012	Manufactured House	14'	99'	14'	0																							
12/30/2011	1/3/2012	Manufactured House	13'	70'	14'	0																							
12/31/2011	1/4/2012	Derick	156"	94'	15'	144300	14300	17'	20000	4'	20000	4'	20000	42'	17500	4'	17500	4'	17500										
12/2/2012	1/6/2012	Manufactured House	14'	96'	14'	0																							
12/2/2012	1/6/2012	Manufactured House	14'	96'	14'	0																							
12/2/2012	1/6/2012	Manufactured House	14'	96'	14'	0																							
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	blender	139"	70'	8'6"	105000	12000	12'	20000	5'	20000	5'	18000	43'	17500	5'	17500												
12/2/2012	1/6/2012	Manufactured House	14'	99'	14'	0																							
12/2/2012	1/6/2012	empty sand bin	138"	80'	11'9"	0																							
12/2/2012	1/6/2012	empty sand bin	138"	80'	11'9"	0																							
12/2/2012	1/6/2012	empty sand bin	138"	80'	11'9"	0																							
12/2/2012	1/6/2012	motor (32878 63725)	15'	110'	12'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077										
12/2/2012	1/6/2012	motor 32873 63725	15'	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	motor 32890 63725	15'	110'	12'	169175	14300	15'	20000	4'	20000	4'	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	17077						
12/2/2012	1/6/2012	motor 32897 63725	15'	110'	12'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	18975	5'	18975						
12/2/2012	1/6/2012	motor 32933 63725	15'	110'	12'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	link 32849 63725	15'	110'	14'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	link 32919 63725	15'	110'	14'	136200	14300	15'	23000	4'	23000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975								
12/2/2012	1/6/2012	House	15'	100'	100'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	House	15'	100'	100'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	House	15'	100'	100'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	House	15'	100'	100'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077						
12/2/2012	1/6/2012	House	15'	100'	100'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077						
12/2/2012	1/6/2012	motor (32884 63725)	15'	110'	14'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	Mud Cleaning Equipment	15'	100'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077						
12/2/2012	1/6/2012	shaker (32939 62375)	15'	110'	12'	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077								
12/2/2012	1/6/2012	Crane	156"	100'	14'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077								
1/3/2012	1/7/2012	Manufactured House	14'	96'	14'	0																							
1/3/2012	1/7/2012	Manufactured House	14'	96'	14'	0																							
1/3/2012	1/7/2012	Manufactured House	14'	96'	14'	0																							
1/2/2012	1/6/2012	Manufactured House	14'	99'	14'	0																							
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	frac pump	139"	70'	8'6"	105000	12500	22'	18500	5'	18500	26'	18500	5'	18500	5'	18500												
12/2/2012	1/6/2012	blender	139"	70'	8'6"	105000	12000	12'	20000	5'	20000	5'	18000	43'	17500	5'	17500												
12/2/2012	1/6/2012	Dog House	15'	80'	11'6"	103000	13000	18'	18000	4'	18000	38'	18000	5'	18000	5'	18000												
12/2/2012	1/6/2012	House	124"	69'	8'6"	102000	12500	18'	22500	5'	22500	34'	22500	5'	22500	5'	22500												
12/2/2012	1/6/2012	House	15'	100'	12'	123986	14300	15'	18000	4'	18000	4'	18000	34'	18562	5'	18562	5'	18562										
12/2/2012	1/6/2012	manifold	14'	69'	13'6"	84490	12000																						

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

[illegible]

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
1/17/2012	1/21/2012	denick 32873 65030	15'	110'	12"	153685	14300	15	18000	4	18000	4	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
1/17/2012	1/21/2012	denick 32849 65030	15'	110'	12"	124008	14300	15	20700	4	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
1/17/2012	1/21/2012	SHACKER SKID	158"	110'	126"	169175	14300	16	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	MUD PUMP	159"	110'	12"	169175	14300	16	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	MUD TANK	154"	110'	127"	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	MCC HOUSE	16'	100'	134"	169175	14300	16	20000	5	20000	5	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	MUD TANK	159"	110'	126"	130200	14300	16	20000	5	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	BUTT SEVEN HOUSE	159"	110'	124"	130200	14300	16	20000	5	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	CENTER STEEL	154"	100'	138"	169175	14300	16	20000	5	20000	5	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	substructure	153"	110'	126"	169175	14300	16	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	substructure	153"	110'	126"	169175	14300	16	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	MPI UNIT	151"	110'	127"	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	JUNK BOX	14'	110'	12"	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	WATER TANK	14'	110'	12"	122300	14300	16	20000	4	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
1/17/2012	1/21/2012	BUTT SEVEN HOUSE	148"	110'	14"	150200	14300	16	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	CROWN SECTION	146"	110'	15"	111225	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	Manufactured House	13'	100'	14'	0																						
1/17/2012	1/21/2012	DRAW WORKS	14'	110'	12"	149175	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/18/2012	1/22/2012	Manufactured House	14'	96'	14'	0																						
1/18/2012	1/22/2012	Manufactured House	14'	96'	14'	0																						
1/18/2012	1/22/2012	Manufactured House	14'	96'	14'	0																						
1/17/2012	1/21/2012	MANUHER HOUSE	14'	110'	126"	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	BOP	138"	95'	14'	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	BOP HANDLER	157"	95'	13'	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	TOP HOUSE	1510"	100'	126"	169175	14300	16	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	CRK HOUSE	156"	110'	14"	169175	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/17/2012	1/21/2012	MUD BOAT	136"	95'	14'	130200	14300	16	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/18/2012	1/22/2012	EMPTY STEEL TANK	156"	65'	124"	0																						
1/18/2012	1/22/2012	Manufactured House	14'	99'	14'	0																						
1/18/2012	1/22/2012	crane 32873	146"	107'	12"	169175	14300	15'	20000	4	20000	4	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/18/2012	1/22/2012	Manufactured House	14'	99'	14'	0																						
1/18/2012	1/22/2012	Empty Tank	156"	70'	105"	0																						
1/18/2012	1/22/2012	Manufactured House	14'	95'	14'	0																						
1/18/2012	1/22/2012	Manufactured House	14'	95'	14'	0																						
1/18/2012	1/22/2012	MUD PUMP	12'	90'	106"	170875	16000	14'	20000	5'	20000	5'	20000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
1/19/2012	1/23/2012	Manufactured House	14'	100'	14'	0																						
1/19/2012	1/23/2012	Manufactured House	14'	100'	14'	0																						
1/20/2012	1/24/2012	EMPTY OILFIELD BUNKHOUSE	14'	100'	14'	101300	14300	15'	17500	4	17500	36'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'
1/20/2012	1/24/2012	EMPTY OILFIELD BUNKHOUSE	14'	100'	14'	101300	14300	15'	17500	4	17500	36'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'	13000	4'
1/20/2012	1/24/2012	Empty Tank	156"	70'	105"	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STEEL TANKS	1410"	76'	12'	0																						
1/21/2012	1/25/2012	EMPTY STE																										

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	G/V/W	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing
2/24/2012	2/28/2012	SUBSTRUCTURE	15'6"	98'	12'6"	153685	14300	17'	18000	4'	18000	4'	18000	38'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
2/24/2012	2/28/2012	MCC UNIT	15'6"	90'	12'6"	131300	14300	17'	18000	4'	18000	4'	18000	38'	15750	5'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	PURGE HOUSE	15'6"	90'	12'6"	131300	14300	17'	18000	4'	18000	4'	18000	38'	15750	5'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	PONY SUB	15'6"	87'	12'	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	CHOKE	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	MUD BOAT	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	GENERATOR	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	CHANGE HOUSE	15'6"	87'	13'	0																		
2/24/2012	2/28/2012	HYDRAULIC UNIT	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	MUD TANK	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	SHAKER	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	MUD TANK	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	GENERATOR	15'6"	87'	12'6"	118700	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/24/2012	2/28/2012	DIESEL TANK	15'6"	87'	12'6"	0																		
2/24/2012	2/28/2012	BUNK HOUSE	15'6"	87'	13'	0																		
2/26/2012	3/1/2012	Manufactured House	14'	100'	14'	0																		
2/26/2012	3/1/2012	Manufactured House	14'	100'	14'	0																		
2/26/2012	3/1/2012	Manufactured House	14'	100'	14'	0																		
2/24/2012	2/28/2012	Manufactured House	14'	95'	14'	0																		
2/24/2012	2/28/2012	Manufactured House	14'	95'	14'	0																		
2/24/2012	2/28/2012	BUNK HOUSE	14'	105'	16'	120000	12500	15'	17120	4'	17120	33'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
2/24/2012	2/28/2012	BUNK HOUSE	14'	105'	16'	120000	12500	15'	17120	4'	17120	33'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
2/25/2012	2/29/2012	crawler crane	14'	120'	14'	196300	14300	15'	23000	4'	23000	15'	23000	4'	23000	36'	18000	5'	18000	5'	18000	5'	18000	5'
2/25/2012	2/29/2012	GAS BUSTER	16'	97'	14'	138294	14300	15'	18652	5'	18652	5'	18652	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
2/25/2012	2/29/2012	SCTION TANK	15'6"	110'	13'	169175	14300	18'	20700	4'	20700	38'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
2/25/2012	2/29/2012	DERRICK	15'6"	95'	15'	153685	14300	17'	18000	4'	18000	4'	18000	40'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
2/27/2012	3/2/2012	Manufactured House	14'	100'	14'	0																		
2/27/2012	3/2/2012	Manufactured House	14'	100'	14'	0																		
2/25/2012	2/29/2012	PUMP	15'6"	90'	13'	158875	18000	20'	23000	5'	23000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
2/27/2012	3/2/2012	Manufactured House	14'	100'	14'	0																		
2/27/2012	3/2/2012	Manufactured House	14'	100'	14'	0																		
2/27/2012	3/2/2012	Manufactured House	14'	105'	14'	0																		
2/25/2012	2/29/2012	GRASS HOPPER	14'	110'	13'	120000	14300	15'	18500	5'	18500	32'	17200	5'	17200	5'	17150	5'	17150	5'	17150	5'	17150	5'
2/25/2012	2/29/2012	MOTOR	15'6"	90'	13'	120000	14300	15'	17500	5'	17500	32'	17700	5'	17700	5'	17700	5'	17600	5'	17600	5'	17600	5'
2/25/2012	2/29/2012	MUD PUMP	15'6"	90'	13'	169175	14300	15'	20000	5'	20000	5'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
2/25/2012	2/29/2012	400 BBL TANKS E/E SAME SIZE	15'6"	110'	13'	120000	14300	20'	17000	5'	17000	32'	14250	5'	14250	5'	14250	5'	14250	5'	14250	5'	14250	5'
2/25/2012	2/29/2012	SCR HOUSE	16'	110'	14'	120000	14300	20'	17000	5'	17000	32'	14340	5'	14340	5'	14340	5'	14340	5'	14340	5'	14340	5'
2/25/2012	2/29/2012	SUB STRUCTURE	15'6"	100'	13'	172875	18000	15'	20000	5'	20000	5'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
2/25/2012	2/29/2012	A LLEG	15'6"	100'	10'	120000	14000	20'	18000	5'	18000	32'	14000	5'	14000	5'	14000	5'	14000	5'	14000	5'	14000	5'
2/25/2012	2/29/2012	CENTER STEEL	14'	95'	13'	0																		
2/25/2012	2/29/2012	SUBSTRUCTURE	15'6"	110'	13'	168875	14000	15'	20000	5'	20000	5'	20000	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
2/26/2012	2/29/2012	A LLEG	15'	110'	10'	120000	14000	20'	17500	5'	17500	32'	14140	5'	14140	5'	14140	5'	14140	5'	14140	5'	14140	5'
2/26/2012	3/1/2012	DRILLER WORKS	15'6"	16'	90'	14'	177275	20600	15'	20600	5'	20600	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	
2/26/2012	3/1/2012	CROWN	15'6"	110'	14'	177275	20600	15'	20600	5'	20600	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
2/26/2012	3/1/2012	CRANE	14'	110'	11'	177275	20600	15'	20600	5'	20600	32'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
2/26/2012	3/1/2012	dog house	15'6"	110'	13'	120000	14000	15'	20000	5'	20000	32'	13200	5'	13200	5'	13200	5'	13200	5'	13200	5'	13200	5'
2/26/2012	3/1/2012	Manufactured House	13'5"	100'	14'	0																		
2/26/2012	3/1/2012	MOTOR	15'6"	95'	11'1"	122300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/26/2012	3/1/2012	MOTOR	15'6"	95'	11'1"	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/26/2012	3/1/2012	MOTOR	15'6"	95'	11'1"	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/26/2012	3/1/2012	vid house	15'6"	95'	12'1"	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/26/2012	3/1/2012	gas buster	15'10"	95'	13'1"	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	crane 32872 106	14'6"	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
2/27/2012	3/2/2012	Crawler crane	14'	110'	14'	139600	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	mcc house	14'	110'	13'4"	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	mud pump	15'6"	110'	12'	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	mud pump	15'6"	110'	12'	139300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	mud tank	15'6"	110'	12'	105300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	mud tank	15'6"	110'	12'6"	122300	14300	16'	20000	4'	20000	34'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'	17000	5'
2/27/2012	3/2/2012	EMPTY 400 BBL TANKS E/E SAME SIZE	16'	78'	12'	0																		
2/27/2012	3/2/2012	EMPTY 400 BBL TANKS E/E SAME SIZE	16'	78'	12'	0																		
2/28/2012	3/3/2012	Manufactured House	14'	100'	14'	0																		
2/27/2012	3/2/2012	2011 atoka trailer	13'6"																					

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

[illegible]

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	
3/26/2012	3/30/2012	SHAKER SKID	158"	110'	12"	120008	14000	16	20700	4	20700	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/26/2012	3/30/2012	BUTT SECTION	148"	110'	14"	122308	14000	16	20000	4	20000	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/26/2012	3/30/2012	CROWN SECTION	146"	110'	15"	105531	14300	16	20000	4	20000	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/26/2012	3/30/2012	MUDD BOAT	14"	110'	14"	139685	14300	16	20000	4	20000	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/26/2012	3/30/2012	HPU UNIT	151"	110'	17"	139685	14300	16	20000	4	20000	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/26/2012	3/30/2012	DRILL LINE	14"	110'	14"	139685	14300	16	20000	4	20000	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/26/2012	3/30/2012	Manufactured House	14"	99'	14"	0																					
3/26/2012	3/30/2012	Manufactured House	14"	99'	14"	0																					
3/26/2012	3/30/2012	Manufactured House	14"	99'	14"	0																					
3/27/2012	3/31/2012	CRANE	148"	95'	128"	172875	18000	15	20000	4	20000	4	20000	30	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
3/27/2012	3/31/2012	crane	148"	95'	128"	172875	18000	15	20000	4	20000	4	20000	30	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
3/28/2012	4/1/2012	GENERATOR	16"	85'	13'	131300	14300	14	18000	4	18000	4	18000	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	DERRICK CROWN	15"	95'	14"	122300	14300	17	18000	4	18000	4	18000	32	18000	4	18000	4	18000	4	18000	4	18000	4	18000	4	18000
3/28/2012	4/1/2012	DERRICK CROWN	15"	95'	14"	122300	14300	17	18000	4	18000	4	18000	32	18000	4	18000	4	18000	4	18000	4	18000	4	18000	4	18000
3/28/2012	4/1/2012	MUD PUMP	16"	85'	13'	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	MUD PUMP	16"	85'	13'	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	SUBSTRUCTURE	16"	85'	13'	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	HYDRAULIC UNIT	16"	85'	13'	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	HYDRAULIC UNIT	16"	85'	13'	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	CREW HOUSE	158"	95'	147"	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	CREW HOUSE	158"	95'	147"	153685	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	DIESEL TANK	159"	85'	9"	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	DIESEL TANK	159"	85'	9"	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	TOP HOUSE	154"	85'	12'	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	TOP HOUSE	154"	85'	12'	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	PUSHER HOUSE	159"	85'	13'	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	PUSHER HOUSE	159"	85'	13'	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	GENERATOR	16"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	GENERATOR	16"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	SKID	154"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	UTILITY SKID	154"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	DRAWWORKS	159"	85'	12'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	DRAWWORKS	159"	85'	12'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	SCR HOUSE	16"	85'	11'	143108	20800	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	SHAKER SKID	16"	85'	13'	143108	20800	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	SHAKER SKID	16"	85'	13'	143108	20800	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	B.O.P SKID	16"	85'	135"	143108	20800	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	B.O.P SKID	16"	85'	135"	143108	20800	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	SUCTION TANK	16"	90'	13'	128960	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
3/28/2012	4/1/2012	SUCTION TANK	145"	90'	13'	128960	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
3/27/2012	3/31/2012	gas buster	16"	95'	12'	141085	14300	16	20700	4	20700	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/27/2012	3/31/2012	rig house	14"	95'	126"	141085	14300	16	20700	4	20700	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
3/28/2012	4/1/2012	SUBSTRUCTURE	16"	85'	14'	128960	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
3/28/2012	4/1/2012	CENTER SUBSTRUCTURE	16"	85'	14'	128960	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
3/28/2012	4/1/2012	RAMP	14"	85'	14'	128960	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
3/28/2012	4/1/2012	RAMP	14"	85'	14'	128960	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
3/28/2012	4/1/2012	GENERATOR	16"	85'	12'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	TRIP TANK	16"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	TRIP TANK	16"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	B.O.P HANDLER	16"	85'	13'	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
3/28/2012	4/1/2012	B.O.P HANDLER	16"	85'	13'	118700	14300	17	20700	4	20700	32</															

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle Weight	Spacing	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
3/31/2012	4/4/2012	Coil Tubing Unit #19	143"	74	8"	150500	14000	19	20500	5	20500	5	20500	26	18750	5	18750	5	18750	5	18750	5	18750	5	18750	5	18750	5	18750	5
3/31/2012	4/4/2012	CRANE	146"	115	13"	176875	20000	14	20600	5	20600	5	20600	34	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
3/31/2012	4/4/2012	CRANE	146"	115	13"	176875	20000	14	20600	5	20600	5	20600	34	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
3/31/2012	4/4/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	6	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
3/31/2012	4/4/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5
4/1/2012	4/5/2012	FRAC PUMP	139"	70	8"	105000	12500	22	18500	5	18500	26	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5	18500	5				

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight
4/11/2012	4/15/2012	DRAWWORK	15	85	14	141560	14300	14	18000	4	18000	4	18000	32	14652	4	14652	4	14652	4	14652	4	14652	4	14652	4	14652
4/11/2012	4/15/2012	BUNKHOUSE	16	85	14	153885	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	CREW HOUSE	16	85	14	153885	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	BOP HANDLER	16	85	14	124008	14300	17	20700	4	20700	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	MCC HOUSE	16	85	14	153885	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	DERRICK	16	85	15	122280	14300	14	18000	32	18000	4	18000	32	18000	4	18000	32	18000	4	18000	32	18000	4	18000	32	18000
4/11/2012	4/15/2012	DERRICK	16	95	15	118700	14300	17	20700	4	20700	32	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
4/11/2012	4/15/2012	Manufactured House	14	96	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	96	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	96	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	96	14	0																					
4/11/2012	4/15/2012	Manufactured House	13	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	Manufactured House	13	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	MCC HOUSE	16	85	14	143108	20800	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	CREW HOUSE	16	85	14	153885	14300	14	18000	4	18000	4	18000	32	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	CRANE	136	70	8	91500	12000	19	15900	5	15900	34	15900	5	15900	5	15900	5	15900	5	15900	5	15900	5	15900	5	15900
4/11/2012	4/15/2012	EMPTY STEEL TANKS	14	10	76	12	0																				
4/11/2012	4/15/2012	EMPTY STEEL TANKS	14	10	76	12	0																				
4/11/2012	4/15/2012	EMPTY STEEL TANKS	14	10	76	12	0																				
4/11/2012	4/15/2012	Manufactured House	13	74	14	0																					
4/11/2012	4/15/2012	EXCAVATOR	14	10	80	12	146094	22100	17	18562	5	18562	5	18562	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	
4/11/2012	4/15/2012	EMPTY STEEL TANKS	13	70	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	CENTER STEEL	163	75	1310	13000	14000	16	23000	5	23000	34	17500	5	17500	5	17500	5	17500	5	17500	5	17500	5	17500	5	17500
4/11/2012	4/15/2012	EMPTY STEEL TANKS	14	10	76	12	0																				
4/11/2012	4/15/2012	LUBE HOUSE	147	75	8	9																					
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	SHAKER TANK	15	115	12	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	INTERMEDIATE TANK	15	115	12	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	SUCTION TANK	15	115	12	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	PUMP #1	15	115	12	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	PUMP #2	15	115	12	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	SCR HOUSE	15	115	12	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	EXCAVATOR	14	82	12	162000	12000	20	20000	4	20000	4	20000	36	17500	4	17500	4	17500	4	17500	4	17500	4	17500	4	17500
4/11/2012	4/15/2012	Manufactured House	14	99	14	0																					
4/11/2012	4/15/2012	Trencher	15	10	90	11	163200	18200	16	20000	5	20000	5	20000	34	20000	4	20000	4	20000	4	20000	12	25000			
4/11/2012	4/15/2012	Manufactured House	136	100	15	0																					
4/11/2012	4/15/2012	CRANE SECTION	15	115	14	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	MIDDLE DERRICK SECTION	15	115	14	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	DERRICK SECTION (A-LEG)	15	115	14	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	CENTER STEEL	14	115	14	176250	19500	15	20625	5	20625	5	20625	32	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975
4/11/2012	4/15/2012	Substructure	148	80	10	120000	14300	18	20700	4	20700	38	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750	4	15750
4/11/2012	4/15/2012	PIPELAYER	14	80	12	150500	14000	14	20500	5	20500	5	20500	36	18750	5	18750	5	18750	5	18750	5	18750	5	18750	5	18750
4/11/2012	4/15/2012	2 EMPTY STEEL TANKS	14	10	76	12	0																				
4/11/2012	4/15/2012	2 EMPTY STEEL TANKS	14	10	76	12	0																				
4/11/2012	4/15/2012	1 EMPTY STEEL TANK	14	10	76	12	0																				
4/11/2012	4/15/2012	EMPTY 500BBL TANK	154	75	121	0																					
4/11/2012	4/15/2012	EMPTY 500BBL TANK	154	75	121	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	Manufactured House	136	100	14	0																					
4/11/2012	4/15/2012	S.E.R. House	156	93	12	153885	14300	17	18000	4	18000	4	18000	38	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	Pusher House	156	99	12	153885	14300	17	18000	4	18000	4	18000	38	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077
4/11/2012	4/15/2012	Mud Pump	156	88	12	153885	14300	17	18000	4	18000	4	18000														

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
4/19/2012	4/23/2012	DRAW WORKS	15'6"	97'	12'	14300	1500	15	1500	15	1500	15	1500	15	1500	15	1500	15	1500	15	1500	15	1500	15	1500	15	1500	15
4/19/2012	4/23/2012	SUB STRUCTURE	15'6"	105'	13'	170975	14300	15	20600	5	20600	5	20600	5	20600	34	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
4/19/2012	4/23/2012	SUB STRUCTURE	15'6"	105'	13'	170975	14300	15	20600	5	20600	5	20600	5	20600	34	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
4/19/2012	4/23/2012	RIG HOUSE	15'	110'	14'	0																						
4/19/2012	4/23/2012	CENTER STEEL	14'	90'	14'	0																						
4/19/2012	4/23/2012	RIG HOUSE	15'	110'	14'	0																						
4/19/2012	4/23/2012	RIG HOUSE	15'10"	90'	12'	120000	18000	20'	16000	5	16000	5	16000	34'	17500	5	17500	5	17500	5	17500	5	17500	5	17500	5	17500	5
4/20/2012	4/24/2012	1 A LEG	14'	120'	12'	170975	14300	15	20600	5	20600	5	20600	34	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
4/20/2012	4/24/2012	1 A LEG	16"	120'	10'	155175	14300	20'	23000	5	23000	34'	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
4/20/2012	4/24/2012	32873 Crane	14'6"	110'	12'	156610	14300	15	18975	4	18975	4	18975	34	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5	17077	5
4/20/2012	4/24/2012	RIG HOUSE	15'10"	105'	14'	130000	14300	20'	20000	5	20000	34	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5	18975	5
4/20/2012	4/24/2012	CROWN BOARD	5'10"	80'	12'	0																						
4/20/2012	4/24/2012	CROWN SECTION	15'9"	110'	17'	120000	18000	20'	17000	5	17000	34'	13500	5	13500	5	13500	5	13500	5	13500	5	13500	5	13500	5	13500	5
4/20/2012	4/24/2012	Manufactured House	14'	99'	14'	0																						
4/21/2012	4/25/2012	Manufactured House	14'	96'	14'	0																						
4/21/2012	4/25/2012	Manufactured House	14'	96'	14'	0																						
4/21/2012	4/25/2012	Manufactured House	14'	96'	14'	0																						
4/21/2012	4/25/2012	Manufactured House	14'	96'	14'	0																						
4/20/2012	4/24/2012	61261 Crane in	14'6"	110'	12'	153306	14000	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/21/2012	4/25/2012	Manufactured House	14'	96'	14'	0																						
4/20/2012	4/24/2012	DOZER	13'6"	74'	8'9"	0																						
4/21/2012	4/25/2012	Manufactured House	13'6"	100'	13'	0																						
4/20/2012	4/24/2012	Manufactured House	14'	99'	14'	0																						
4/21/2012	4/25/2012	Crane	14'6"	110'	12'	153685	14300	15'	18000	4'	18000	4'	18000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/21/2012	4/25/2012	Forklift	14'	90'	10'6"	124008	14300	15'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/21/2012	4/25/2012	CRANE	14'	105'	12'	177575	20600	14'	20600	5'	20600	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/21/2012	4/25/2012	Manufactured House	14'	14'	14'	0																						
4/21/2012	4/25/2012	11701 CRANE	14'6"	110'	13'6"	177275	20600	14'	20600	5'	20600	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/21/2012	4/25/2012	Frag manifest	15'6"	100'	9'	112475	14300	16'	20625	5'	20625	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/21/2012	4/25/2012	Manufactured House	14'	99'	14'	0																						
4/21/2012	4/25/2012	Manufactured House	14'	99'	14'	0																						
4/22/2012	4/26/2012	Generator	16'	85'	13'	143108	20800	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Ramp	16'	85'	13'	143108	20800	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Fuel Tank	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Fuel Tank	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Floor House	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Floor House	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Generator	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Generator	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Generator	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Shaker Tank	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Shaker Tank	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Change House	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Change House	16'	85'	13'	128960	14300	17'	20700	4'	20700	32'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'	14652	4'
4/22/2012	4/26/2012	Suction Tank	16'	85'	13'	118700	14300	17'	20700	4'	20700	32'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
4/22/2012	4/26/2012	Suction Tank	16'	85'	13'	118700	14300	17'	20700	4'	20700	32'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
4/22/2012	4/26/2012	Koomey Unit	16'	85'	13'	118700	14300	17'	20700	4'	20700	32'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
4/22/2012	4/26/2012	Koomey Unit	16'	85'	13'	118700	14300	17'	20700	4'	20700	32'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'	15750	4'
4/22/2012	4/26/2012	Tip Tank	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Tip Tank	16'	85'	13'	124008	14300	17'	20700	4'	20700	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Water Tank	16'	85'	13'	153685	14300	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Water Tank	16'	85'	13'	153685	14300	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Substructure	16'	85'	13'	153685	14300	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Substructure	16'	85'	13'	153685	14300	14'	18000	4'	18000	4'	18000	32'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/22/2012	4/26/2012	Mud Pump	16'	85'	13'	153685	14300	14'</																				

Data Set: 1- DEWITTGeneral.xls

This is a list of all "General" type permits that started or stopped within 10 miles of the coordinates you provided. Due to the fact that some permits started AND stopped within this area there will be some duplicates.

Start Date	End Date	Load Description	Height	Length	Width	GVW	Axle Weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
4/25/2012	4/29/2012	Separator	14ft	75	8'6"	0																						
4/25/2012	4/29/2012	ng house	16"	110'	13'4"	160000	14300	16'	19000	4'	19000	4'	19000	34'	17740	5'	17740	5'	17740	5'	17740	5'	17740	5'	17740	5'	17740	5'
4/25/2012	4/29/2012	empty fuel tank	14"	95'	8'6"	136200	14300	16'	23000	4'	23000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/25/2012	4/29/2012	mud pump	15ft"	95'	12ft"	139685	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/25/2012	4/29/2012	OIL WELL SERVICING UNIT	13ft"	64ft"	8'10"	100000	15000	14'	21250	4'	21250	38'	21250	4'	21250													
4/25/2012	4/29/2012	mud pump	15ft"	95'	12ft"	139685	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/25/2012	4/29/2012	shaker skid	15ft"	110'	12ft"	139685	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/25/2012	4/29/2012	mudd tank (empty)	15ft"	110'	12ft"	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/25/2012	4/29/2012	mudd tank (empty)	15ft"	110'	12ft"	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	EMPTY STEEL TANK	15'	79'	10ft"	0																						
4/25/2012	4/29/2012	gas boiler	16'	110'	12'	141085	14300	16'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	R.O.P SKID	15'	110'	14'	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	PIPE REELS E/E	16'	73'	12'	0																						
4/26/2012	4/30/2012	HOUSE	15'	110'	14'	139685	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HOUSE	16'	110'	14'	104008	14300	16'	2000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HOUSE	16'	110'	14'	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HFU UNIT	15ft"	110'	12ft"	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	sub	15ft"	110'	12ft"	155175	14300	16'	23000	4'	23000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/26/2012	4/30/2012	sub	15ft"	110'	12ft"	155175	14300	16'	23000	4'	23000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/26/2012	4/30/2012	drawworks	15ft"	110'	12ft"	120000	13300	16'	16000	4'	16000	34'	14700	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'
4/26/2012	4/30/2012	empty fuel tank	15'	110'	10'	0																						
4/26/2012	4/30/2012	center steel	15ft"	110'	13ft"	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	hog handler	15ft"	110'	13'	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	crown section of derrick	14ft"	95'	15'	105531	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	mudd boat	14'	110'	14'	139685	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	butt section of derrick	14ft"	95'	14'	122608	14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	COMPRESSOR	14ft"	69'	14'	120000	14300	16'	22850	4'	22850	34'	20000	4'	20000													
4/26/2012	4/30/2012	SEPARATOR SKID	15ft"	69'	11'	0																						
4/27/2012	5/1/2012	EMPTY MUD TANK	15ft"	100'	14'	155400	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	EMPTY MUD TANK	15ft"	100'	14'	150200	14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	MUD PUMP	15ft"	100'	14'	174375	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	MUD PUMP	15ft"	100'	14'	174375	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	SHALE SHAKER SKID	15ft"	100'	14'	150200	14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	DRAWWORKS	15ft"	100'	14'	136200	14300	17'	23000	4'	23000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	SUBSTRUCTURE	15ft"	100'	14'	174375	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	DERRICK RAMP	15ft"	100'	14'	134300	14300	14'	20000	4'	20000	4'	20000	35'	20000	5'	20000	5'	20000	5'	20000	5'	20000	5'	20000	5'	20000	5'
4/27/2012	5/1/2012	DERRICK (IN TOW)	15ft"	100'	14'	139500	19500	14'	20000	4'	20000	4'	20000	41'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'
4/27/2012	5/1/2012	S C R HOUSE	15ft"	100'	14'	150200	14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	OILFIELD UTILITY SKID	15ft"	100'	14'	155400	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	OILFIELD UTILITY SKID	15ft"	100'	14'	174375	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	OILFIELD UTILITY SKID	15ft"	100'	14'	150200	14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	PUSHER HOUSE	15ft"	100'	14'	155400	19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	CREW HOUSE	15ft"	100'	14'	150200	14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/26/2012	4/30/2012	Manufactured House	1ft"	100'	13'	0																						
4/27/2012	5/1/2012	EXCAVATOR	14'	75'	12'	150500	14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'
4/27/2012	5/1/2012	Manufactured House	14'	96'	14'	0																						
4/27/2012	5/1/2012	EMPTY TANK (S)	14'10"	75'	12'	0																						
4/27/2012	5/1/2012	EMPTY TANK (S)	14'10"	75'	12'	0																						
4/27/2012	5/1/2012	EMPTY TANK (S)	14'10"	75'	12'	0																						
4/27/2012	5/1/2012	EXCAVATOR	14'	75'	12'	150500	14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'
4/28/2012	5/2/2012	Manufactured House	14'	100'	14'	0																						
4/28/2012	5/2/2012	Manufactured House	14'	100'	14'	0																						
4/27/2012	5/1/2012	EXCAVATOR	14'	75'	12'	150500	14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5								

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description	Height	Length	Width	GVW	Axle weight 18000	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing	Axle weight Spacing
3/22/2012	6/18/2012	Well Service Unit	125'	705'	111"	7560	19500	4"	22500	19"	25500	4"	25500	4"	18100				
3/20/2012	6/18/2012	Well Service Unit	136'	65'	106"	93000	19500	4"	22500	19"	25500	4"	25500	4"					
4/6/2012	7/5/2012	Well Service Unit	174'	58'	86"	82950	15625	4"	15625	192"	25850	89"	25850						
4/6/2012	7/5/2012	Well Service Unit	138'	42'	87"	87700	18800	42"	18400	212"	29700	45"	19700						
4/6/2012	7/5/2012	Well Service Unit	133'	376"	8"	76880	14500	41"	14500	34"	23840	43"	23840						
3/12/2012	6/18/2012	Well Service Unit	136'	70'	86"	92000	12000	154"	20000	44"	20000	3110"	20000	6"	20000				
3/12/2012	6/18/2012	WELL SERVICING UNIT	14'	68'	116"	106800	18300	46"	19500	187"	23000	46"	23300	46"	22700				
3/12/2012	6/28/2012	Well Service Unit	136'	75'	86"	113600	13360	45"	14840	48"	14840	47"	14840	298"	18550				
4/1/2012	6/30/2012	Well Service Unit	145'	586"	116"	113000	23500	4"	23500	16"	22000	4"	22000	4"	22000	52"	18540	52"	18540
3/23/2012	6/21/2012	Crane	135'	67'	105"	127950	25500	46"	25500	16"	25650	45"	25650	56"	25650				
3/23/2012	6/21/2012	WELL SERVICING UNIT	135'	67'	105"	127950	25500	46"	25500	16"	25650	45"	25650	56"	25650				
3/23/2012	6/21/2012	WELL SERVICING UNIT	135'	67'	105"	127950	25500	46"	25500	16"	25650	45"	25650	56"	25650				
3/23/2012	6/21/2012	WELL SERVICING UNIT	135'	67'	105"	127950	25500	46"	25500	16"	25650	45"	25650	56"	25650				
3/23/2012	6/21/2012	WELL SERVICING UNIT	135'	67'	105"	127950	25500	46"	25500	16"	25650	45"	25650	56"	25650				
3/23/2012	6/21/2012	WELL SERVICING UNIT	135'	67'	105"	127950	25500	46"	25500	16"	25650	45"	25650	56"	25650				
3/26/2012	6/24/2012	CRANE	1110'	484"	86"	103420	18800	5"	26100	15"	29650	5"	29650						
3/22/2012	6/20/2012	WELL SERVICING UNIT	171'	62'	910"	105720	22960	44"	21920	1611"	24380	45"	23720	46"	12740				
3/23/2012	6/20/2012	Well Service Unit	136'	60'	86"	115000	14300	18"	20350	4"	20350	22"	20000	4"	20000	4"	20000		
3/23/2012	6/20/2012	Well Service Unit	14'	60'	10'	10000	25000	44"	25000	187"	25000	43"	25000						
3/28/2012	6/26/2012	Crane	1210'	4410"	86"	103000	22000	5"	22000	136"	29500	5"	29500						
3/28/2012	6/26/2012	Crane	12'	446"	86"	93500	24500	5"	24000	136"	22500	5"	22500						
3/23/2012	6/26/2012	Crane	136'	535'	99"	120895	24170	54"	24170	54"	24170	61"	24170		24170				
3/25/2012	6/23/2012	Well Service Unit	146'	66'	104"	110000	23500	4"	23500	15"	21000	4"	21000	4"	21000				
3/23/2012	6/20/2012	Well Service Unit	1310'	599"	102"	117000	22500	52"	22500	219"	24000	45"	24000	45"	24000				
3/23/2012	6/20/2012	Coiled Tubing Unit	14'	768"	9"	167000	20000	1310"	12000	47"	17000	47"	17000	47"	17000	207"	21000	46"	21000
3/23/2012	6/20/2012	Crane	224'	62'	24500"	157000	24500	5"	24500	13"	18000	5"	18000	5"	18000	116"	18000	46"	18000
3/23/2012	6/20/2012	Well Service Unit	136'	67'	88"	104000	12000	15"	19000	4"	19000	28"	18000	5"	18000				
3/23/2012	6/20/2012	Well Service Unit	126'	664"	84"	90000	18000	178"	18000	44"	18000	242"	18000	102"	18000				
3/23/2012	6/20/2012	Well Service Unit	126'	664"	84"	90000	18000	178"	18000	44"	18000	242"	18000	102"	18000				
3/23/2012	6/20/2012	CRANE	232'	49'	86"	136500	23500	4"	23500	83"	27500	53"	27000	54"	27000				
3/23/2012	6/20/2012	COIL TUBING UNIT	1711'	66	86"	146180	15000	132"	17180	46"	25250	46"	27880	264"	20980	42"	19680	42"	19940
3/23/2012	6/20/2012	Coiled Tubing Unit	14'	70'	86"	164000	21000	133"	23000	47"	24000	46"	24000	264"	24000	42"	24000	42"	24000
3/23/2012	6/20/2012	COIL TUBING UNIT	14'	745"	108'	188500	26500	152"	26500	45"	20000	46"	20000	46"	20000	27"	22500	42"	22500
3/23/2012	6/20/2012	COIL TUBING UNIT	13'	34'	8"	64000	16000	18"	24000	4"	24000								
3/30/2012	6/28/2012	Well Service Unit	1711'	738"	86"	162000	22000	17"	20000	46"	24000	46"	24000	3211"	24000	46"	24000	46"	24000
3/23/2012	6/21/2012	Well Service Unit	144'	611"	811"	95250	18000	42"	19100	1610"	19800	46"	20000	46"	18350				
6/28/2012	6/28/2012	Crane	126'	376"	84"	82000	10000	15"	20000	46"	24000	46"	24000	46"	24000				
3/23/2012	6/21/2012	Well Service Unit	13'	64'	86"	90000	10000	15"	20000	46"	20000	274"	20000	42"	20000				
3/23/2012	6/21/2012	Well Service Unit	132'	624"	8"	92000	12000	16"	20000	44"	20000	232"	20000	122"	20000				
3/23/2012	6/21/2012	Well Service Unit	132'	624"	8"	92000	12000	16"	20000	44"	20000	232"	20000	122"	20000				
3/23/2012	6/21/2012	Well Service Unit	132'	624"	8"	92000	12000	16"	20000	44"	20000	232"	20000	122"	20000				
3/23/2012	6/21/2012	Well Service Unit	132'	624"	8"	92000	12000	16"	20000	44"	20000	232"	20000	122"	20000				
3/23/2012	6/21/2012	Crane	136'	528"	102"	137500	27500	88"	27500	55"	27500	8"	27500	59"	27500				
4/1/2012	6/30/2012	Well Service Unit	2310'	678"	86"	120400	23000	45"	23000	154"	24800	52"	24800	52"	24800				
4/1/2012	6/30/2012	Well Service Unit	13'	366"	8"	50400	11420	173"	19490	43"	19490								
4/1/2012	6/30/2012	WELL SERVICING UNIT	144'	653"	10'	115500	22000	42"	22000	202"	24000	45"	24000	45"	23500				
4/1/2012	6/30/2012	WELL SERVICING UNIT	144'	653"	10'	115500	22000	42"	22000	202"	24000	45"	24000	45"	23500				
4/1/2012	6/30/2012	Well Service Unit	144'	653"	10'	115500	22000	42"	22000	202"	24000	45"	24000	45"	23500				
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	106"	118000	24500	41"	24500	22"	23000	46"	23000	46"	23000				
4/1/2012	6/30/2012	WELL SERVICING UNIT	142'	565"	98"	98000	18000	56"	20000	195"	30000	46"	30000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	142'	565"	98"	98000	18000	56"	20000	195"	30000	46"	30000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	106"	118000	24500	44"	24500	22"	23000	46"	23000	46"	23000				
4/1/2012	6/30/2012	WELL SERVICING UNIT	142'	565"	98"	98000	18000	56"	20000	198"	23000	47"	23000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	142'	483"	105"	76000	18000	56"	18000	195"	20000	46"	20000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	106"	118000	23500	42"	23500	22"	23700	46"	23700	46"	23700				
4/1/2012	6/30/2012	WELL SERVICING UNIT	1310'	58'	86"	118000	24500	56"	24500	20"	23000	46"	23000	46"	23000				
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	106"	118000	24500	44"	24500	22"	23000	46"	23000	46"	23000				
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	106"	118000	24500	44"	24500	22"	23000	46"	23000	46"	23000				
4/1/2012	6/30/2012	WELL SERVICING UNIT	142'	56'	86"	100000	20000	56"	20000	192"	30000	56"	30000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	142'	56'	86"	100000	20000	56"	20000	192"	30000	56"	30000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	10'	9000	20000	42"	20000	199"	25000	46"	25000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	106"	107000	22500	44"	22500	19"	25000	46"	25000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	14'	60'	100"	90000	20000	42"	20000	199"	25000	46"	25000						
4/1/2012	6/30/2012	WELL SERVICING UNIT	146'	62'	10'	110560	20500	48"	20500	213"	23187	45"	23187	45"	23186				
4/1/2012	6/30/2012	WELL SERVICING UNIT	144'	574"	91"	108500	22000	41"	22000	198"	20000	44"	20000	44"	20000				
4/1/2012	6/30/2012	WELL SERVICING UNIT	146'	62'	10'	110560	20500	48"	20500	213"	23187	45"	23187	45"	23186				
4/1/2012	6/30/2012	WELL SERVICING UNIT	109'	45'	91"	44100	11000	177"	17700	44"	15400								
4/1/2012	6/30/2012	WELL SERVICING UNIT	1211'	416"	89"	95500	13700	214"	26400	44"	21400								
4/1/2012	6/30/2012	WELL SERVICING UNIT	11'	446"	81"	43200	18000	178"	18000	43"	14300								
4/1/2012	6/30/2012	Well Service Unit	146'	62'	10'	108000	21270	4"	21270	20"	21820	46"	21820	46"	21820				
4/1/2012	6/30/2012	Well Service Unit	144'	653"	10'	115500	22000	42"	22000	202"	24000	45"	24000	45"	23500				
4/1/2012	6/30/2012	Well Service Unit	144'	653"	10'	115500	22000	42"	22000	202"	24000	45"	24000	45"	23500				
4/1/2012	6/30/2012	Well Service Unit	144'	6															

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date		Load Description	Axle weight						Axle weight						Axle weight						Axle weight						Axle weight					
				weight	Length	Width	GWV	Spacing	weight	Length	Width	GWV	Spacing	weight	Length	Width	GWV	Spacing	weight	Length	Width	GWV	Spacing	weight	Length	Width	GWV	Spacing	weight	Length	Width	GWV	Spacing
4/10/2012	7/9/2012	Coiled Tubing Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Coiled Tubing Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	12'10"	67'6"	8'6"	104000	14000	176"	18000	45"	18000	2711"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	
4/10/2012	7/9/2012	Well Service Unit	13'6"	59'11"	8'4"	118000	12000	15"	20000	44"	20000	299"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	
4/10/2012	7/9/2012	Well Service Unit	13'6"	59'11"	8'4"	118000	12000	15"	20000	44"	20000	299"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	
4/15/2012	7/14/2012	Well Service Unit	13'6"	59'11"	8'4"	118000	12000	15"	20000	44"	20000	299"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	
4/10/2012	7/9/2012	Crane	13'2"	42'	8'5"	104080	23000	176"	11000	4"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	23360	47"	
4/12/2012	7/11/2012	Well Service Unit	12'10"	65"	7'8"	92421	10780	17"	16570	47"	16570	27"	16167	5"	16167	5"	16167	5"	16167	5"	16167												

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description	Height	Length	Width	C/W	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight
------------	----------	------------------	--------	--------	-------	-----	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------	---------	-------------

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
4/27/2012	7/26/2012	Well Service Unit	14	67	10	77000	25000	4	25000	4	25000	4	25000	4	25000	4	25000	4	25000	4	25000	4	25000	4	25000	4
4/27/2012	7/26/2012	Well Service Unit	14	67	12	107000	24500	4	24500	19	29000	4	29000													
5/9/2012	8/1/2012	Crane	1378	459"	910"	109300	27325	58"	27325	81"	27325	58"	27325													
4/27/2012	7/26/2012	Well Service Unit	1376	67	8"	92320	11800	18	18180	46"	18180	28"	18180	28"	18180	28"	18180	28"	18180	28"	18180	28"	18180	28"	18180	28"
4/27/2012	7/26/2012	Well Service Unit	12	45	18"	97000	22000	5	22000	14	26500	5	26500	5	26500	5	26500	5	26500	5	26500	5	26500	5	26500	5
4/27/2012	7/26/2012	Crane	1376	56	11"	96000	18000	4	18000	14	30000	4	30000													
4/27/2012	7/26/2012	Crane	1376	56	11"	96000	18000	4	18000	14	30000	4	30000													
4/27/2012	7/26/2012	Crane	124	56	10"	139650	28500	5	28500	8	26650	12"	26650	12"	26650	12"	26650	12"	26650	12"	26650	12"	26650	12"	26650	12"
4/27/2012	7/26/2012	CRANE	13	436"	9	113800	28450	58"	28450	8	28450	511"	28450													
4/27/2012	7/26/2012	Crane	12	45	8"	104000	25500	5	25500	13	26500	5	26500													
4/27/2012	7/26/2012	Well Service Unit	1376	70	8"	110000	12000	19	18000		19000	29	20000	5	20000											
4/27/2012	7/26/2012	Well Service Unit	1376	67	9	90000	18500	48"	18500	1910"	26500	49"	26500													
4/27/2012	7/26/2012	Well Service Unit	1377	657"	8	95000	13800	189"	21000	45"	21000	27	20000	10	20000											
4/27/2012	7/26/2012	Coiled Tubing Unit	1376	761"	8"	163850	20650	168"	18000	49"	21000	49"	21000	268"	21300	45"	21300	45"	21300	45"	21300	45"	21300	45"	21300	45"
4/27/2012	7/26/2012	Well Service Unit	1376	65	8"	112500	12000	153"	20000	44"	20000	28	20000	46"	20000	46"	20000	46"	20000	46"	20000	46"	20000	46"	20000	46"
4/27/2012	7/26/2012	Well Service Unit	1376	65	8"	108000	12000	153"	21000	44"	21000	28	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"
4/27/2012	7/26/2012	Well Service Unit	1376	65	8"	112000	12000	153"	20000	44"	20000	28	20000	46"	20000	46"	20000	46"	20000	46"	20000	46"	20000	46"	20000	46"
4/27/2012	7/26/2012	Well Service Unit	1376	65	8"	108000	12000	153"	21000	44"	21000	28	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"
4/27/2012	7/26/2012	Well Service Unit	1376	65	8"	108000	12000	153"	21000	44"	21000	28	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"
4/27/2012	7/26/2012	Well Service Unit	1376	65	8"	108000	12000	153"	21000	44"	21000	28	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"	18000	46"
4/30/2012	7/29/2012	Well Service Unit	14	68	8"	110000	22000	4	22000	19	22000	4	22000	4	22000											
4/30/2012	7/29/2012	Well Service Unit	1375	648"	8	82800	10000	13	17000	4	17000	29	19400	4	19400											
5/7/2012	8/5/2012	Coiled Tubing Unit	122	403"	8"	69000	18000	21	17300	48"	17300	46"	17300													
5/7/2012	8/5/2012	Well Service Unit	1376	718"	8"	110200	14200	168"	15500	47"	15500	249"	16500	5	16500	5	16500	5	16500	5	16500	5	16500	5	16500	5
4/30/2012	7/29/2012	Well Service Unit	14	66	115"	69240	14350	4	14350	158"	20270	4	20270													
5/1/2012	8/6/2012	Well Service Unit	14	65	8"	93000	13000	17	20000	4	20000	32	20000	9	20000											
5/1/2012	8/1/2012	Well Service Unit	17	65	8"	98800	11000	14	17500	48"	17500	27	17600	5	17600	5	17600	5	17600	5	17600	5	17600	5	17600	5
4/30/2012	7/29/2012	Well Service Unit	125	55	8"	97000	13000	16	20000	4	20000	25	22000	10	22000											
4/30/2012	7/29/2012	Crane	1376	37	8"	70000	20000	18	10000	4	20000	32	22000	5	22000											
4/30/2012	7/29/2012	Well Service Unit	125	65	8"	11000	13000	16	20000	4	20000	32	22000	5	22000											
4/30/2012	7/29/2012	Crane	125	437"	12"	18000	12000	41"	15200	144"	14800	49"	14800													
4/30/2012	7/29/2012	Well Service Unit	14	75	12	98000	10000	15	20000	5	20000	36	16000	4	16000	4	16000	4	16000	4	16000	4	16000	4	16000	4
5/1/2012	7/30/2012	Coiled Tubing Unit	1376	681"	8"	132000	12000	16	20000	4	20000	4	20000	28	20000	4	20000	4	20000	4	20000	4	20000	4	20000	4
5/1/2012	7/30/2012	Well Service Unit	13	65	8"	92000	12000	16	20000	4	20000	27	22500	9	22500											
5/4/2012	8/2/2012	Well Service Unit	1376	78	1010"	83000	11000	125"	17000	47"	17000	436"	19000	42"	19000											
5/1/2012	7/30/2012	Well Service Unit	14	58	11	107600	23840	4	23760	19	20000	4	20000	4	20000											
5/1/2012	7/30/2012	Coiled Tubing Unit	1376	74	8"	157980	15000	117"	14100	48"	22440	48"	22440	258"	21000	46"	21000	46"	21000	46"	21000	46"	21000	46"	21000	46"
5/1/2012	7/30/2012	Well Service Unit	1376	58	8"	90000	12000	16	20000	4	20000	27	20000	4	20000											
5/1/2012	7/30/2012	Well Service Unit	1376	58	8"	90000	12000	143"	18000	47"	20000	267"	20000	44"	20000											
5/1/2012	7/30/2012	Well Service Unit	1376	58	8"	90000	12000	143"	18000	47"	20000	267"	20000	44"	20000											
5/1/2012	7/30/2012	Well Service Unit	1376	58	8"	90000	12000	143"	18000	47"	20000	267"	20000	44"	20000											
5/1/2012	7/30/2012	Well Service Unit	1376	58	8"	90000	12000	143"	18000	47"	20000	267"	20000	44"	20000											
5/1/2012	7/30/2012	Well Service Unit	1376	58	8"	90000	12000	143"	18000	47"	20000	267"	20000	44"	20000											
5/1/2012	8/8/2012	Well Service Unit	14	65	8"	93000	13000	16	20000	4	20000	25	20000	10	20000											
5/1/2012	8/8/2012	Well Service Unit	14	65	8"	93000	13000	16	20000	4	20000	25	20000	10	20000											
5/1/2012	7/30/2012	Well Service Unit	125	65	8"	119000	13000	16	20000	4	20000	32	22000	5	22000	5	22000	5	22000	5	22000	5	22000	5	22000	5
5/4/2012	8/2/2012	Well Service Unit	1376	58	8"	98000	13000	16	20000	4	20000	25	20000	10	20000											
5/3/2012	8/1/2012	Coiled Tubing Unit	1376	65	8	163050	15580	121"	19933	51"	19933	46"	19933	25	21920	46"	21920	46"	21920	46"	21920	46"	21920	46"	21920	46"
5/1/2012	7/30/2012	Well Service Unit	123	61	8"	94000	12000	20	21000	4	21000	31	20000	6	20000											
5/1/2012	7/30/2012	Crane	1372	5910"	8"	92000	14000	182"	15600	44"	15600	292"	15600	41"	15600	41"	15600	41"	15600	41"	15600	41"	15600	41"	15600	41"
5/1/2012	7/30/2012	Coiled Tubing Unit	14710	5810"	18"	121120	18500	148"	121018	276"	18800	44"	18800	274"	19312	42"	19312	42"	19312	42"	19312	42"	19312	42"	19312	42"
5/1/2012	7/30/2012	Coiled Tubing Unit	134	698"	8"	134300	14300	157"	20000	47"	20000	44"	20000	267"	20000	42"	20000	42"	20000	42"	20000	42"	20000	42"	20000	42"
5/1/2012	7/30/2012	Coiled Tubing Unit	1376	75	8"	151000	19000	154"	22000	48"	22000	48"	22000	256"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"	22000	41"
5/1/2012	7/30/2012	Crane	14	50"	8"	97600	21520	42"	22620	15	20400	5	21420													
5/7/2012	8/5/2012	Crane	1376	945"	12	198980	19400	145"	19400	93"	19400	107"	17080	57"	17080	81"	17080	55"	17080	15"	19988	59"	19988	59"	19988	59"
5/1/2012	7/30/2012	Well Service Unit	14	70	11	113000	22000	43"	22000	17	23000	42"	23000	43"	23000											
5/1/2012	8/8/2012	Well Service Unit	14	62	12	100000	25000	42"	25000	263"	25000	42"	25000	42"	25000											
5/2/2012	7/31/2012	Well Service Unit	14	66	10"	113410	2439																			

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

[illegible]

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description		Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
5/17/2012	8/15/2012	Well Service Unit		137"	572"	8"	88000	12000	14"	19000	4"	19000	28"	19000	4"	19000													
5/17/2012	8/15/2012	Well Service Unit		132"	74"	8 3/4"	85000	11500	14"	17000	4"	17000	24"	17900	4"	19750													
5/16/2012	8/14/2012	Well Service Unit		146"	67"	10 7/8"	122500	23000	110"	23000	196"	25500	*10"	25500	*10"	25500													
5/17/2012	8/15/2012	Well Service Unit		136"	78"	8 7/16"	85000	11000	124"	17000	4"	17000	24"	17000	4"	20000	4"	20000	4"	20000	4"	20000	4"	20000	4"	20000	4"	20000	4"
5/17/2012	8/15/2012	Well Service Unit		136"	78"	10 1/10"	83000	11000	125"	17000	47"	17000	436"	19000	42"	19000													
5/16/2012	8/14/2012	Well Service Unit		1272"	468"	8 1/16"	124700	18200	8"	21000	8"	17200	55"	17200	8"	17000	55"	17450	57"	17450									
5/16/2012	8/14/2012	Well Service Unit		136"	45"	8 9/16"	66000	20000	137"	20000	4"	20000	46"	20000	30"	20000	5"	20000	45"	20000	45"	20000	45"	20000	45"	20000	45"	20000	45"
5/16/2012	8/14/2012	Coiled Tubing Unit		146"	786"	11 1/2"	196000	22500	153"	20000	46"	21500	46"	21500	46"	21500	236"	22000	46"	22000	46"	22000	46"	22000	46"	22000	46"	22000	46"
5/16/2012	8/14/2012	Well Service Unit		14"	70"	8 1/16"	93000	13000	17"	20000	4"	20000	25"	21000	5"	21000	5"	21000	5"	21000	5"	21000	5"	21000	5"	21000	5"	21000	5"
5/16/2012	8/14/2012	Crane		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	25"	20000	10"	20000													
5/16/2012	8/14/2012	Well Service Unit		113"	441"	10 1/4"	93950	17500	4"	16200	86"	23150	45"	18650	45"	18650	45"	18650	45"	18650	45"	18650	45"	18650	45"	18650	45"	18650	45"
5/16/2012	8/14/2012	Crane		132"	70"	9 9/16"	141600	26400	85"	26400	83"	26400	52"	26400	162"	18000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	25"	20000	10"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	25"	20000	10"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	25"	20000	10"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	25"	20000	10"	20000													
5/16/2012	8/14/2012	Concrete Pump		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Concrete Pump		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Concrete Pump		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65"	8 6/16"	93000	13000	17"	20000	4"	20000	27"	20000	5"	20000													
5/16/2012	8/14/2012	Well Service Unit		14"	65																								

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description	Height	Length	Width	GWW	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight	Aisle Spacing	Aisle weight</
------------	----------	------------------	--------	--------	-------	-----	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	--------------	---------------	----------------

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
4/20/2012	4/24/2012 A LEG	1F 1207	14"	1207	20	23000	14300	20	18975	4	18975	5	18975	5	18975	5	18975	5	18975	5
4/20/2012	4/24/2012 32873 Crane	14"	149"	110	12"	14300	15	18975	4	18975	4	18975	34	18975	5	18975	5	18975	5	18975
4/20/2012	4/24/2012 RIG HOUSE	1510"	105	14"	14"	14300	20	20000	4	20000	34	18975	5	18975	5	18975	5	18975	5	18975
4/20/2012	4/24/2012 MCKINNEY BOARD	1510"	80	12"	14"	14300	20	20000	4	20000	34	18975	5	18975	5	18975	5	18975	5	18975
4/20/2012	4/24/2012 CROWN SECTION	1510"	110	11"	14"	18000	20	17000	5	17000	34	13500	5	13500	5	13500	5	13750	5	13750
4/20/2012	4/24/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	14652
4/21/2012	4/25/2012 Manufactured House	14"	96	14"	14"	14300	17	20700	4	20700	32	14652	4	14652	4	14652	4	14652	4	1

Data Set: 2- DEWITTHub.xls

This is a list of all active Hub permits which can be used to determine mean and median values for various measurements related to Hub permits

Start date	End date	Load Description	Height	Length	Width	GVW	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing	Axle weight	Spacing
4/25/2012	4/29/2012	mudd tank (empty)	15'8"	110'	12'6"		14300	16'	20700	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	EMPTY STEEL TANK	15'	79'	10'6"		14300	16'	20700	4'	20700	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/29/2012	gas buster	16'	110'	12'		14300	16'	20700	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	B.O.P SKID	15'	110'	14'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	PIPE REELS EJE	16'	73'	12'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HOUSE	15'	110'	14'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HOUSE	16'	110'	14'		14300	16'	2000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HOUSE	16'	110'	14'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	HPU UNIT	15'3"	110'	12'2"		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	sub	15'3"	110'	12'6"		14300	16'	23000	4'	23000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/26/2012	4/30/2012	sub	15'3"	110'	12'6"		14300	16'	23000	4'	23000	34'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/26/2012	4/30/2012	drawworks	15'3"	110'	12'6"		13300	16'	16000	4'	16000	34'	14700	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'	15000	5'
4/26/2012	4/30/2012	empty fuel tank	15'	110'	10'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	center steel	15'4"	110'	13'8"		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	top handler	15'5"	110'	13'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	crow section of derrick	14'6"	95'	15'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	mudd boat	14'	110'	14'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	butt section of derrick	14'8"	95'	14'		14300	16'	20000	4'	20000	34'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'	17077	5'
4/26/2012	4/30/2012	COMPRESSOR	14'6"	69'	14'		14300	16'	22850	4'	22850	34'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'	20000	4'
4/30/2012	4/30/2012	SEPARATOR SKID	15'6"	69'	11'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	EMPTY MUD TANK	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	EMPTY MUD TANK	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	MUD PUMP	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	MUD PUMP	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	SHALE SHAKER SKID	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	DRAWWORKS	15'6"	100'	14'		14300	17'	23000	4'	23000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	SUBSTRUCTURE	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	DERRICK RAMP	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	20000	5'	20000	5'	20000	5'	20000	5'	20000	5'	20000	5'	20000	5'
4/27/2012	5/1/2012	DERRICK (IN TOW)	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	S c R HOUSE	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	OILFIELD UTILITY SKID	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	OILFIELD UTILITY SKID	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	OILFIELD UTILITY SKID	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	PUSHER HOUSE	15'6"	100'	14'		19500	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/27/2012	5/1/2012	CREW HOUSE	15'6"	100'	14'		14300	14'	20000	4'	20000	4'	20000	35'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'	18975	5'
4/26/2012	4/30/2012	Manufactured House	13'5"	100'	13'																							
4/27/2012	5/1/2012	EXCAVATOR	14'	75'	12'		14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'
4/27/2012	5/1/2012	Manufactured House	14'	96'	14'																							
4/27/2012	5/1/2012	EMPTY TANK (S)	14'10"	76'	12'																							
4/27/2012	5/1/2012	EMPTY TANK (S)	14'10"	76'	12'																							
4/27/2012	5/1/2012	EMPTY TANK (S)	14'10"	76'	12'																							
4/27/2012	5/1/2012	EXCAVATOR	14'	75'	12'		14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'
4/26/2012	5/2/2012	Manufactured House	14'	100'	14'																							
4/26/2012	5/2/2012	Manufactured House	14'	100'	14'																							
4/27/2012	5/1/2012	EXCAVATOR	14'	75'	12'		14000	14'	20500	5'	20500	5'	20500	36'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'	18750	5'
4/27/2012	5/1/2012	Building	14'6"	75'	9'6"																							
4/27/2012	5/1/2012	Manufactured House	13'5"	100'	13'																							
4/27/2012	5/1/2012	slideboom	13'3"	88'	13'10"		16000	21'	20000	5'	20000	5'	20000	32'	18950	5'	18950	5'	18950	5'	18950	5'	18950	5'	18950	5'	18950	5'
4/27/2012	5/1/2012	400 tank	16'4"	100'	12'																							
4/27/2012	5/1/2012	400 tank	16'4"	100'	12'																							
4/26/2012	5/3/2012	Empty Steel tank	15'	75'	10'																							
4/28/2012	5/2/2012	Manufactured House	14'	95'	14'																							
4/30/2012	5/4/2012	Meter Skid	13'6"	75'	9'																							
4/30/2012	5/4/2012	Manufactured House	14'	99'	14'																							
4/30/2012	5/4/2012	Manufactured House	14'	99'	14'																							
4/30/2012	5/4/2012	Manufactured House	14'	99'	14'																							

